



Government of West Bengal
Irrigation & Waterways Directorate
Jalasampad Bhavan, Bidhannagar,
Salt Lake City, Kolkata 700 091

Memo No. 4S-1/120 (9)

Dated, 25th January, 2018

From: Superintending Engineer,
Metropolitan Drainage Circle,
Irrigation & Waterways Directorate
& Member-cum-Convener,
Departmental Unified Schedule of Rates Revision Committee

- To:**
1. Chief Engineer (South)
Irrigation & Waterways Directorate
 2. Chief Engineer (West)
Irrigation & Waterways Directorate
 3. Chief Engineer (South West)
Irrigation & Waterways Directorate
 4. Chief Engineer (North)
Irrigation & Waterways Directorate
 5. Chief Engineer (Design & Research)
Irrigation & Waterways Directorate
 6. Chief Engineer
Teesta Barrage Project
Irrigation & Waterways Directorate
 7. Director of Personnel & Ex-officio Chief Engineer
Irrigation & Waterways Directorate
 8. Chief Engineer (North East)
Irrigation & Waterways Directorate
 9. Project Director & Ex-officio Chief Engineer
West Bengal Major Irrigation and Flood Management Project (WBMIFMP)
Irrigation & Waterways Directorate

Sub: 1st Addenda & Corrigenda to the Unified Schedule of Rates of I & W Department (w.e.f 19.01.2018)

Sir,
Please find enclosed herewith the 1st Addenda & Corrigenda to the Unified Schedule of Rates of I & W Department (w.e.f 19.01.2018) for information and forwarding to all Superintending Engineers.

Yours faithfully

Encl: As stated

Superintending Engineer,
Metropolitan Drainage Circle,
Irrigation & Waterways Directorate
& Member-cum-Convener,
Departmental Unified Schedule of Rates Revision Committee

Memo No. 4S-1/120 (9)/1

Dated, 25th January, 2018

Copy with the copy of enclosure submitted for favour of kind information to the Secretary to the Govt. of West Bengal, I & W Department Chairman, Departmental Unified Schedule of Rates Revision Committee




Superintending Engineer,
Metropolitan Drainage Circle,
Irrigation & Waterways Directorate
& Member-cum-Convener,
Departmental Unified Schedule of Rates Revision Committee

Memo No. 4S-1/120 (9)/1/1

Dated, 25th January, 2018

✓ Copy with copy of enclosure forwarded to: Sri R.K Sharma, Executive Engineer, DVC Study Cell & e-Governance Cell
Irrigation & Waterways Directorate

He is requested to upload this order in the Departmental website www.wbiwd.gov.in



Superintending Engineer,
Metropolitan Drainage Circle,
Irrigation & Waterways Directorate
& Member-cum-Convener,
Departmental Unified Schedule of Rates Revision Committee

1st ADDENDA & CORRIGENDA

TO THE UNIFIED SCHEDULE OF RATES OF I&W DEPARTMENT (w.e.f. 19.01.2018)

Dated. 25.01.2018

A. CORRIGENDA OF UNIFIED SCHEDULE OF RATES, JANUARY, 2018

Following corrections to be made to the item as shown below :-

1.

Item No.	Page No	Description of item	Unit	Present rate in the USoR				New rate to be read as			
				Rs.				Rs.			
				Zone - I	Zone -II	Zone - III	Zone -IV	Zone - I	Zone -II	Zone - III	Zone - IV
2.49	C-17	Supplying to site and pitching with 1st class kiln burnt or picked Jhama bricks including dressing, ramming and preparing bed to proper slope complete with necessary earth work not exceeding 300 m.m. in depth and filling gaps with powdered earth or local sand etc. complete (The rate is including cost of sand).									
		i) With 1st class kiln burnt brick									
		a) 7.50 cm thick	Sqm	3115.00	3106.00	3092.00	3459.00	311.00	311.00	309.00	346.00
		b) 12.50 cm thick	Sqm	5017.00	5008.00	4983.00	5571.00	502.00	501.00	498.00	557.00
		c) 20.00 cm thick	Sqm	7617.00	7638.00	7562.00	8499.00	762.00	764.00	756.00	850.00
		d) 25.00 cm thick	Sqm	9531.00	9556.00	9463.00	10634.00	953.00	956.00	946.00	1063.00
		e) 32.50 cm thick	Sqm	12519.00	12537.00	12434.00	13943.00	1252.00	1254.00	1243.00	1394.00
		ii) With picked jhama brick No.1.									
		a) 7.50 cm thick	Sqm	3084.00	3075.00	3062.00	3428.00	308.00	308.00	306.00	343.00


2. Please Read Item No. 2.96 in place of Item No.2.91 in the Drawing of R C C Tetrapod Vide Page No. D-3 & D-4

3. Please Read Page No. B-22,B-23,B-24,B-25,B-26,B-27 in place of B-27 in all.

B. ADDENDA OF UNIFIED SCHEDULE OF RATES, JANUARY,2018

MATERIALS SUPPLIED AT SITE INCLUDING OVERHEAD CHARGES AND CONTRACTOR'S PROFIT

Item No.	Page No	Description of item	Unit	Present rate in the USoR			
				Rs.	Zone - I	Zone -II	Zone - III
2.99 (New Item)	C-28	Supplying at site the following materials including carriage Overhead Charges and Contractor's Profit					
I)		8,10,12 SWG G I Wire	Quintol	6115.00	6115.00	6115.00	6115.00
II)		16 SWG GI Wire	Quintol	7484.00	7484.00	7484.00	7484.00
III)		Long Nails	Quintol	8108.00	8108.00	8108.00	8108.00
IV)		Long Nuts & Bolts	Quintol	8108.00	8108.00	8108.00	8108.00


 Member-cum- Convener, USoR Committee
 Superintending Engineer,
 Metropolitan Drainage Circle
 I & W Directorate