Table of Contents

Annexure- 1:	Ambient Air Quality Standards1
Annexure- 2:	Ambient Noise Quality Standards2
Annexure- 3:	Sediment Quality Standard2
Annexure- 4:	Water Quality Criteria
Annexure- 5:	Noise standard for the construction vehicle4
Annexure- 6:	Emission Standards for Construction Equipment Vehicles5
Annexure- 7:	41 Nos. canal/ drainage channel proposed for desiltation
Annexure- 8:	Block wise ST population percentage in project district8
Annexure- 9:	Environmental and Social Screening Report9
Annexure- 10:	Environmental & Social features within 500m, 3km and 10 Km. periphery 25
Annexure- 11:	Map showing habitations, facilities and CPR having potential of impact47
Annexure- 12:	Block wise sampling villages where field study was carried out48
Annexure- 13:	Stake-holder consultation
Annexure- 14: Clearance (EC)	Letter from Dept. of Environment on Non-requirement of Environment 54
Annexure- 15 (a	a): Sediment quality report of Mundeswari River by RRI55
Annexure- 15 (b WBPCB recogn	b): Sediment Quality of Mundeswari and other drainage canal by MoEF & ized laboratory60
Annexure- 16:	River Water Quality (Tested by SWID)62
Annexure- 17(a)): Baseline Environmental Report of Air, River Water, & Noise Quality 64
Annexure- 17(b): Map showing Baseline Environmental Monitoring location72
Annexure- 18:	Photo graphs of ESIA study74
Annexure- 19:	MoM on ESMP Consultation & sharing workshop92
Annexure- 20 (a	a): MoM with Sand Miners Regarding Utilization of Desilted Material99
Annexure- 20 (b	b): Proposal by Sand Miners Regarding Utilization of Desilted Material101
Annexure- 21:	MoM with Brick Kiln Owners Regarding Utilization of Desilted Material 104
Annexure- 22:	List of Activity Require Regulatory Clearance106
Annexure- 23: during Project I	Parameters for Air, Surface & Ground Water, Soil quality Monitoring mplementation
Annexure- 24: stage	Map showing future monitoring location during construction and Operation 108

Annexure- 25 (a): Implementation	Format for Monthly & Quarterly E&S Monitoring Report on ESM 109	Р
Annexure- 25 (b):	Format for SPMU's Half Yearly E&S Management Monitoring Re 114	eport
Annexure- 26: and DPMU	Terms of Reference (ToR) for Position of Environmental Expert at S 116	PMU
ANNEXURE- 26.A	TOR FOR SENIOR ENVIRONMENTAL SPECIALIST	116
ANNEXURE- 26.B	TOR FOR ENVIRONMENTAL SPECIALIST	118
ANNEXURE- 26.C	TOR FOR SENIOR SOCIAL CUM GENDER DEVELOPMENT SPECIALIST	120
ANNEXURE- 26.D	TOR FOR SOCIAL CUM GENDER DEVELOPMENT SPECIALIST	123
Annexure- 27:	Guidance on Chance Find Procedures	126
Annexure- 28:	ESMP Implementation Monitoring Plan by Project Activities	128
ANNEXURE- 28(A)	ESMP IMPLEMENTATION MONITORING PLAN FOR IRRIGATION MODERNIZATION	128
ANNEXURE- 28(B)	ESMP IMPLEMENTATION MONITORING PLAN FOR FLOOD MANAGEMENT	142

Annexure- 1: Ambient Air Quality Standards

Sl. No.	Pollutant	Time-	Concentration in amb	oient air	
		weighted	Industrial,	Ecologically	Method of Measurement
		average		sensitive area	
			and other areas		
1	SO _{2, μg/m³}	Annual*	50	20	Improved West &Gaeke
					Ultraviolet fluorescence
		24hrs**	80	80	
2	$NO_{2, \mu g/m}^{3}$	Annual*	40	30	Modified Jacob
					&Hocheisser
		24hrs**	80	80	Chemiluminence
3	$PM_{10 \mu\text{g/m}}^3$	Annual	60	60	Gravimetric
					TOEM
		24hrs	100	100	Beta attenuation
4	$PM_{2.5\mu\text{g/m}}{}^3$	Annual*	40	40	Gravimetric
					TOEM
		24hrs**	60	60	Beta attenuation
5	$O_{3 \mu g/m}^{3}$	8hrs**	100	100	UV Photometry
		1hr**	180	180	Chemiluminescence
-					Chemical method
6	Pb $\mu g/m^3$	Annual*	0.50	0.50	AAS/ICP method after
		0.41 ***	1.00	1.00	sampling on EPM2000
		24hrs**	1.00	1.00	ED-XRF using Teflon
7	<u> </u>	8 hrs**	00	02	Filter
7	CO mg/m ³	8 nrs**	02	02	Non-dispersive Infra-red
		1hr.**	04	04	spectroscopy
8	Panzana 3	Annual*	04 05	04 05	Gas chromatography based
0	Benzene _{µg/m} ³	Allilual	03	05	continuous analyser
9	BenzoPyrene,	Annual*	01	01	Solvent extraction
7	(Particulate phase		01	01	followed by HPLC/GC
	(1 articulate phase only) ng/m^3				analysis
10	Arsenic ng/m ³	Annual*	06	06	AAS/ICP method after
10	insente ng/m	1 minuur	00	00	sampling on EPM 2000
11	Nickel ng/ ³	Annual*	20	20	AAS/ICP method after
		1 minut	20	20	sampling on EPM 2000
12	NH _{3 µg/m} ³	Annual*	100	100	Chmilumuminescence
14	- · με/ m	· · · · · · · · · · · · · · · · · · · ·	100	100	Indophenol blue method
		24hrs**	400	400	

*Annual arithmetic means of minimum 104 measurements in a year at a particular site taken twice a week 24 hrs at uniform intervals.

** 24hrs/08hrs/02 hourly monitored values as applicable, shall be complied with 98% of the time in a year. 2% of time they may exceed the limits but not on two consecutive days of monitoring.

Annexure- 2: Ambient Noise Quality Standards

Sl. No.	Category of Area / Zone	Limits in dB(A) Leq*	
		Day Time	Night Time
А	Industrial area	75	70
В	Commercial area	65	55
С	Residential area	55	45
D	Silence Zone	50	40

Note:

1. Day time shall mean from 6.00 a.m. to 10.00 p.m.

2. Night time shall mean from 10.00 p.m. to 6.00 a.m.

3. Silence zone is an area comprising not less than 100 metres around hospitals, educational institutions, courts, religious places or any other area which is declared as such by the competent authority.

4. Mixed categories of areas may be declared as one of the four above mentioned categories by the competent authority.

* *dB(A) Leq denotes the time weighted average of the level of sound in decibels on scale A which is relatable to human hearing.*

A "decibel" is a unit in which noise is measured.

"A", in dB(A) Leq, denotes the frequency weighting in the measurement of noise and corresponds to frequency response characteristics of the human ear.

Leq: It is an energy mean of the noise level over a specified period.

Annexure- 3: Sediment Quality Standard

Level of Pollution (mg./ kg. dry)	Cd.	Cr.	Cu.	Pb.	Zn.
Threshold Effect Level (TEL)	0.68	52.3	18.7	30.2	124
Probable Effect Level (PEL)	4.2	160.4	108.2	112.2	271
Non-Polluted	-	<25	<25	<40	<90
Moderate Polluted	>6	>75	>50	>60	>200
Heavily Polluted	>6	>75	>50	>60	>200

Source: US-EPA

Note: Probable Effect Level (PTL) i.e. the values above which adverse biological affected would frequency occur Threshold Effect Level (TEL) is the value below which adverse biological effects would be infrequently expect

Annexure- 4: Water Quality Criteria

	General Standards for disch	narge of enviro			Effluents
SN	Parameter			Standards	
		Inland	Public	Land for	Marine Coastal
		Surface	Sewers	Irrigation	Area
		Water			
1	Colour and Odour	5 to 25	-	5 to 25	5 to 25 Agreeable
		Agreeable		Agreeable	
2	Suspended Solids mg/l, Max.	100	600	200	(a) For process
					waste water-100
	(b) For Cooling water effluent 10				
	percent above total suspended				
3	matter of influent Particular size of suspended	Shall page			(a) Floatable colida
3	solids	Shall pass 850 microns	-	-	(a) Floatable solids, max. 3 mm
	solids	IS Sieve			max. 5 mm
		15 51676			(b) Settleable
					solids, max850
					microns
4*		-	-		-
5	pH value	5.5 to 9.0	5.5 to	5.5 to 9.0	5.5 to 9.0
	1		9.0		
6	Temperature	Shall not	-	-	Shall not exceed
		exceed 5oC			5oC above the
		above the			receiving water
		receiving			temperature
		water			
7		temperature	20	10	20
7 8	Oil and grease (mg/L Max)	10	20	10	20
0	Total residual chlorine mg/1, Max	1	-	-	1
9	Ammonical nitrogen (as N),	50	50		50
,	mg/1 max.	50	50	_	50
10	Total Kjeldhal nitrogen (as NH3)	100	-	_	100
10	mg/l, Max	100			100
11	Free Ammonia (as NH3) mg/1,	5	-	-	5
	Max				
12	Biochemical oxygen demand (5	30	350	100	100
	days at 20oC), mg/1 Max)				
13	Chemical Oxygen demand, mg/1	250	-	-	250
	Max				
14	Arsenic (as) mg/1 Max	0.2	0.2	0.2	0.2
15	Mercury (As Hg), mg/1 max)	0.01	0.01	-	0.01
16	Lead (as Pb) mg/L, Max	0.1	1	-	2
17	Cadmium (as Cd) mg/1, Max	2	1	-	2
18	Hexavalent chromium, (as $Cr + 6) mg/1$ May	0.1	2	-	1
10	6) mg/1, Max	2	2		2
19	Total chromium (as Cr) mg/l,	2	2	-	2
20	Max Copper (as Cu) mg/l Max	3	3		3
20	Copper (as Cu) mg/l, Max Zinc (as Zn) mg/l, Max	5	15	-	15
21	Selenium (as Se) mg/l, Max	0.05	0.05	-	0.05
22	Nickel (as Ni) mg/l, Max	3	3	-	5
23	1 10K01 (as 111) 111g/1, 191aA	J	5	-	5

	General Standards for discharge of environment Pollutants Part-A: Effluents						
SN	Parameter			Standards			
		Inland Surface Water	Public Sewers	Land for Irrigation	Marine Coastal Area		
24*	-	-	-	-			
25*	-	-	-	-	-		
26	-	-	-	-	-		
27	Cyanide (as CN), mg/l Max	0.2	2	0.2	0.2		
28*	-	-	-	-	-		
29	Fluoride (as F) mg/l Max	2	15	-	15		
30	Dissolved Phosphates (as p), mg/l Max	5	-	-	-		
31*	-	-	-	-	-		
32	Sulphide (as S) mg/l Max	2	-	-	5		
33	Phenolic Compounds (as C6H5OH) mg/l Max	1	5	-	5		
34	Radioactive materials:						
	(a) Alpha emitter micro curie/ml	10-7	10-7	10-8	10-7		
	(b) Beta emitter micro curie/ml)	10-6	10-6	10-7	10-6		
35	Bio-assay test	90% survival	90%	90%	90% survival of		
		of fish after	survival	survival of	fish after 96 hours		
		96 hours in	of fish	fish after	in 100% effluent		
		100%	after 96	96 hours in			
		effluent	hours in	100%			
			100%	effluent			
			effluent				
36	Manganese (as Mn)	2 mg/l	2 mg/l	-	2 mg/l		
37	Iron (as Fe)	3 mg/l	3 mg/l		3 mg/l		
38	Vanadium (as V)	0.2 mg/l	0.2 mg/l		0.2 mg/l		
39	Nitrate Nitrogen	10 mg/l	-	-	20 mg/l		
40	-	-	-	-	-		

Annexure- 5: Noise standard for the construction vehicle

Sl. No.	Equipment	Noise Level (in dB)
1	Tractor-scraper	93
2	Rock drill	87
3	Unmuffled concrete breaker	85
4	Hand-held tree saw	82
5	Large rotary diesel compressor	80
6	1 ^{1/2} tonne dumper truck diesel	75
7	Concrete mixture	75

Source: The Noise pollution (Regulation & Control) Rules, 2000

Annexure- 6: Emission Standards for Construction Equipment Vehicles

Engine Power	СО	НС	HC+NOx	NOx	PM
kW			g/kWh		
Bharat (CEV) Stage II					
P < 8	8.0	1.3	-	9.2	1.00
$8 \le P < 19$	6.6	1.3	-	9.2	0.85
$19 \le P < 37$	6.5	1.3	-	9.2	0.85
$37 \le P < 75$	6.5	1.3	-	9.2	0.85
$75 \le P < 130$	5.0	1.3	-	9.2	0.70
$130 \le P < 560$	5.0	1.3	-	9.2	0.54
Bharat (CEV) Stage III					
P < 8	8.0	-	7.5	-	0.80
$8 \le P < 19$	6.6	-	7.5	-	0.80
$19 \le P < 37$	5.5	-	7.5	-	0.60
$37 \le P < 75$	5.0	-	4.7	-	0.40
$75 \le P < 130$	5.0	-	4.0	-	0.30
$130 \le P \le 560$	3.5	-	4.0	-	0.20

Bharat (CEV) Stage II - III emission standards for diesel construction machinery

Bharat (CEV) Stage III Useful Life Periods

Power Rating		Useful Life Period (hours)
< 19 kW		3000
19-37 kW	Constant speed	3000
	Variable speed	5000
> 37 kW		8000

Bharat (CEV/Trem) Stage IV - V emission standards

Engine Power	СО	HC	NOx	PM	PN	Test Cycle
kW		g/k	Wh		1/kWh	
Bharat (CEV/Trem) Stage IV						
$37 \le P < 56$	5.0	4.	7*	0.025	-	NRSC and NRTC
$56 \le P < 130$	5.0	0.19	0.4	0.025	-	
$130 \le P \le 560$	3.5	0.19	0.4	0.025	-	
Bharat (CEV/Trem) Stage V						
P < 8	8.0	7.	5*	0.4	-	NRSC
$8 \le P < 19$	6.6	7.	5*	0.4	-	
$19 \le P < 37$	5.0	4.	7*	0.015	1×10^{12}	NRSC and NRTC
$37 \le P < 56$	5.0	4.	7*	0.015	1×10^{12}	
$56 \le P < 130$	5.0	0.19	0.4	0.015	1×10^{12}	
$130 \le P \le 560$	3.5	0.19	0.4	0.015	1×10^{12}	
$P \ge 560$	3.5	0.19	3.5	0.045	_	NRSC

Bharat (CEV/Trem) Stage IV - V Useful Life Periods

	Power Rating	Useful Life Period (hours)
\leq 37 kW	Constant speed	3000
	Variable speed	5000
> 37 kW		8000

Annexure- 7: 41 Nos. canal/ drainage channel proposed for desiltation

	1		horn out		and a second of	Cutfell		Off-take					
\$1. 40.	Name of Rhal/Channel/River	Length: In KM	theid width in mit (av)	Rate/km in Lack	Total cust in Lack	tatitude(N)	Longitude(E)	Latitude(N)	Longitude(E)	Block	District	Remarks	
1	Maja Darkotar	12.00	7.00	41.86	507 32	222371.72°N	47'54'0632'E	22°46 42.72°N	87597.263	Udaynamay angwr	Howsen:	with sluice at its off take	111111
a.	thanbon that	6.94	12.00	61.71	428.27	22'37'38.45'N	87"56'47 87"E	22"36"29.51"N	87:58:59.68°E	Udaynaray angur	Howcall	15	-Weigton
3	Unity/ars.ctal	7.64	\$.00	80.92	.253.51	22*39/0.65°W	A7*58'38.10*E	22'42'38.01'N	875920.2611	Udaynaray annur	Howfulh		interior
4	Kainoria stur	4.802	12.00	64.71	296.33	22140(30.14"N	88'01'52.62'T	22'41'17,45"N	BR-00/14.53*E	Extagnaray anpur	Howrah	with slate at its out-fail	WANTE:
÷	-Capity Rempion (c) of	0.00	7.00	41.86	-0:00	2213918.47%	117:54:02.15*2	22*40'29.84*N	87'57'37.99'0	Udayneray anour	Howah		universited.
4	Madaria Khal	12.90	100.00	747,72	9645,59	12'34'55 00'N	87'59'36.04'E	22'41'37.45'N	BH: 00 14 53 E	Utlaynaray anpur & Amta-L	Hawceh	150	007,000
1	Someswar Khal	4.843	7.00	41.86	202.75	22"35/45 #7"11	17759'12.73°E	22°37'46.38°N	88° 0'11.51°E	Antsi	Howrall	with sluice at its out-fall	- and that
8	Mahisamori Khal	4.195	12.00	61.71	758.87	22°3¥11 N/N	87'37'7.50°E	22'32'48.30'N	87'59'28.67'1	Amta G	Howrah	with sluke at its out-fail & Officiale	electric TDD
0	Sutgaintaca khat	A,489	5.00	32,92	147.78	22°54'3.49'%	875545.78*6	22"39"2.82"N	87'56'00.85'1	Amta A	Hourah	with shakes at its cost-fail	ingen/faci
10	Tiecla ilhai	1.195	5.00	32.92	195,18	223698.139	87°56'45.83°E	22°36'18.49'N	87'58'29.34'1	āmta-II	Howrah	with shire at its out-fail	Server TSD
=	Khorigeria khal	3,9	5.00	32.92	126.39	22*33'33.30*	87'54'43.44"	22'37'20.17°	87.23.6.36.	Amta II	Howrah	with slore at	HANAS

Re eac wation of Khal/Channel/River

						Outfall	1.000	Off-take	1		-	1	SL A
SI. Vo.	Name of Khal/Channel/River	Longth in KM	Bed width in mt (av)	Rate/km in Lack	Total cost in Lack	Latitude(N)	Longitude(E)	Latitude(N)	Longitude(E)	Block	District	Remarks	
12	Bankara khal	2.58	7.00	41.86	108.00	22'30'42.92*	87'57'23.67'	22'31'41.59'	87*57*29.75*	Amta 8	Bowrah	with sluice at its out-fall	+041420
13	Chinan to Bhoumikpara	0.95	7.00	41.86	39.77	22'32'43.64"	87*52'40.57*	22'32'17.35'	87"53'45.45"	Amta li	Howrah	Lines.	194115.2
14	Chitrian to Bhovmilipara	0,276	7.00	41.86	11.55	32"3326.71"	87*52'43.33*	22*32'28.79*	87*52'35.28*	Anstall	Howrait		+141107-31
15	Mirgram to beral	3.011	7.00	45.86	126.12	22'52'95.81"	87*52'48.78*	32*32'38.62"	87'59'11.85'	Arma II	Howrah		MANOLIS
16	Hatgachia Khai	1.587	7.00	41.86	66.41	22*52*43.32*	#7*51'23.41*	22'33'26.16"	87*51'44.93"	Arrita II	Howrah		WWW
17	Kulla Khal	3.95	5.00	32.92	64,19	32"33"24.78"	\$7"52'15.61"	22"33"44.96"	87'51'72.32"	Ainta II.	Howrab		Invited
58	Ghoraberia Khal	1.038	5,00	32.92	34.17	22*33'50.14*	\$7*52'02.16"	22"34'21,41"	87"51"38.35"	Amtail	Howrah		WWW/D
19	Gorupara	1.928	5.00	92.92	63.47	22:05:57.18*	87'52'30.89"	22'36'23.01*	87'53'3.15"	Amta II	Howrah	with sluice at its out-fail	erideiji (Li
20	Kaulvmoli Khul	4.002	5.00	32.92	134.71	22'33'22.52"	87'52'22.13*	22'34'31.93"	67*53'48:12*	Amta II	Howrah	With sluice at its out-fail	manuto
21	Mellock Diversion Khal	10.50	5.00	32.92	345.66	22" 27' 50.96"	87" 53' 53.11"	22* 27' 58.99*	87" 54" 47.02"	Bagnan (Howrah		ebcomp (
22	Kolatola Khal	4.839	5.00	32.92	159.3	22*27 29/0*N	88° 0'13.22°F	32*27'8.25"N	87°57'58.75"E	Bagnan-I	Howrah	with sluice at its out-fail	HWH/SJ
23	Mahadevpur Khal	1.752	5.00	32.92	57.68	22"27"54.1.2"N	87"59"A1 23"F	22*27'41.64''N	87*58'59.12*E	Bagnan-I	Howrah	with sluice at its out-fall	HWH/SI
24	Mankur khal	1.88	5.00	32.92	61.89	22*30/46.40*	87'53'46.52"	22*30'48.64*	87:54'37.02"	Bagsan I	Howrah	with sluice at its out-fall	HWH/LO
25	Gopalpur Khul	1.42	5.00	32.62	46.75	32'28'50.71"	87'57'51.88"	22*28'53.18*	87*57'14.94"	Bagnan I	Howrah	with sluice at its out-fall	HWH/LO
26	Koria Brumpur Drainage channel	9.75	5.00	32.92	320.97	22, 58, 23 25,	87° 54' 19.67"	22" 31' 14 35"	87*56' 17.46*	Bainan-R	Howrab	1	LOC/LOSE III
27	Jagocampur khal	2.90	5.00	32.92	128.39	22" 33' 26,57"	88° 03' 24.64"	22' 31:26.75'	68*3' 20.93"	Uluberta-II	Howrah	1	SDC/LDSC
		-			-	and the second se						_	

SI.	Name of	Length	Sed width	Rate/km	Total cost in	Outlait	And the second	Off-take	4		-	a colao	1.1
No.	Khal/Channel/River	in KM	in mt (m)	in Lack	Lack	Latitude(N)	Longitude(E)	Latitude(N)	Longitude(E)	Block	District	Remarks	
28	Kamer Khali khal	5.00	5.00	12.92	364.6	22*29'16.89*	88" 05" 57.73"	22* 29/27.94*	88'05' 57.57*		1		1
29.	Chackbagebotiper khal	5.00	5.00	32.92	164.6	22* 29/46.13*	68' 01' 29.84"	22' 29'53.48"	86'01' 29.02"		1.26		200
30	Matur Hana Khal	3,00	5.00	32.92	98.76	22" 28 19.45"	B8" 06' 23.72"	22" 28'19.01"	88'06' 21.79"	-		34-11	
31	Banitala Abadi Khai	4.50	5.00	32.92	148.14	22" 297 52"	84' 05' 53 80"	22" 29'5.71"	48'05' 53.03"	â.			
32	Latibpur Khal	4.00	5.00	32.92	131.68	22" 28'41,39"	88" 06" 4.08"	22" 28'33.9"	88'05'53.24*	30	1 100	10.2	
33	Malika khal	3.50	5.00	32.92	115.22	22120152561	88* 06' 32.28*	22" 29"15.17"	88'06' 3.12"	1	1		1
34	Kataberia khal	6.00	5.00	32.92	197.52	22, 39,35.01,	88" 04" 48.48"	22" 29'40.35"	68'04' 48,48"		0	1.19	1
35	Mohisguha	3.00	5.00	32.92	98.76	22' 34'57.10'	88.05,20'81,	22" 35'32.11"	88'02' 54.36"	1771			
36	Rajapur khai	3.50	5.00	32.92	115.22	22" 29'83,64"	88' 05' 23.93"	22" 29'29.18"	86'05' 17.21"		1.1	1	
37	Siber Hana khal	3.00	5.00	32.92	98.76	22*3151.77*	88" 03" 27.27"	22" 31'53.11"	88'03' 19.48"	68. S		1.1	1
38	Dhekin Ramchandrapur-1	3.50	5.00	32.92	115.22	22* 34'30.30*	88° 03° 0.77°	22'34'28.19'	88"02"38.59"		1.0		
39	Tatiberia khal	3.00	5.00	32.92	98.75	22* 29 2.14*	88" 06" 7.92"	22'29'1.49'	88'06' 7.75*	12	10.0	1	
40	Majukhatra-2	4.00	5.00	32.92	131,65	22" 33"2.80"	88' 02' 7.5"	22'335.63*	88'02'5.30"	1.2.	1		<u>8-2</u>
4	Purona Khal	14.00	12.00	61.71	863.94	22" 34'31.43"	88' 03' 3.74"	22"28"14.39"	88'06' 35.97'	0.073		1. 2	12.5
-	Tutal	181.36	8M	1.0	16,278.88	Laks		0.000			1		222

* Roner khal to be included with this list of drainage channel proposed for desiltation

Bankura		Purba Bardl	naman	Paschim Bardham	an	Howrah		Hooghly	
Block	% of ST Populati on	Block	% of ST Populati on	Block	% of ST Populatio n	Block	% of ST Population	Block	% of ST Population
Barjora	1.64	Katwa - II	1.44	Faridpur Durgapur		Uluberia - II	0.04	Khanakul - II	0.02
Indus	1.85	Katwa - I	1.45	Kanksa	10.24	Shyampur - II	0.06	Chanditala - I	0.16
Patrasayer	3.01	Khandaghos h	2.29			Uluberia - I		Khanakul - I	0.30
Sonamukh i	3.50	Mangolkote	2.83			Bagnan - I	0.12	Pursura	0.48
		Manteswar	2.93			Amta - II	0.14	Chanditala - II	1.00
		Raina - II	4.00			Amta - I	0.15	Arambag	1.46
		Galsi - I	4.08			Shyampur - I	0.16	Singur	1.47
		Bardhaman - I	5.62			Udaynarayan pur	0.19	Chinsurah - Magra	3.64
		Raina - I	5.80			Domjur	0.42	Jangipara	4.61
		Galsi - II	6.83			Bagnan - II	0.48	Tarakeswar	5.04
		Bhatar	9.74			Jagatballavpu r	1.04	Haripal	6.70
		Kalna - I	10.13					Balagarh	9.23
		Bardhaman - II	11.93					Polba - Dadpur	11.47
		Ausgram - I	13.05					Dhaniakhali	14.26
		Ausgram - II	14.42					Pandua	15.36
		Jamalpur	15.18						
		Memari - I	15.78						
		Kalna - II	17.29						
		Memari - II	18.42						
Average	2.50		8.59		8.60		0.26		5.01

Annexure- 8: Block wise ST population percentage in project district

Annexure- 9: Environmental and Social Screening Report

S. No.	Environmental & Social Features	Name of Establishment/ Description	Status / Availability within 3 km	Left/ Right	Lat	Long	Location Name
Physical		· · · · ·					
Environment							
	Natural Drain	Akhabari Khal	1.14 Km	Left	22.908	87.935	Pursura Block
		Raner Khal	2.5 Km	Left	22.981	87.985	Jamalpur
		Kable Khal	0 Km	Right	22.86	87.89	Block
							Arambag
		T ')('	1.5.17	D' 1.	22040124741124	05050144 1085	Block
	Standing water bodies (ponds, lakes, etc.)	Tajpur Munsi Pukur	1.5 Km	Right	22°49'24.74"N	87°53'44.10"E	
	Flowing water bodies	Harinkhloa	0 Km	Left	22.888	87.911	Pursura Block
	(rivers, rivulets, streams, canals, etc.)	Nuna	0 Km	Right	22.989	87.944	Jamalpur & Raina-II Block
	Ground water sources						
	(open wells, bore wells,						
	etc.)						
	Meandering River						
	Erosion prone stretches						
	Areas with high slope	Not Available	Not	Not	Not Available	Not Available	Not Available
	(higher than 15 percent)		Available	Available			
	Landforms (hills,	Not Available	Not	Not	Not Available	Not Available	Not Available
	valleys)		Available	Available			
	Sand Mine						
	Coal Mine	Not Available	Not	Not	Not Available	Not Available	Not Available
Biological			Available	Available			
Environment							
	National Park / Wildlife Sanctuary	Garchumuk Deer Park	55.1	Right	22°20'58.29"N	88° 4'19.91"E	
	Reserved Forests	Chandur Forest	15	Right	22°54'38.43"N	87°46'6.09"E	
		Golakderyama	45.34		22°42'10.75"N	87°28'18.74"E	
		Forest					
		Dhamkura Scrub Forest	42.99	Left	22°45'11.81"N	87°29'10.39"E	
		Amlagora Forest Range	56.6	Left	22°49'59.70"N	87°20'55.58"E	
		Chondrakona	55.52	Left	22°50'21.33"N	87°21'10.01"E	
		Forest Bhuban Danga	20.83	Left	23° 0'24.82"N	87°44'7.99"E	
	Community Forest	Forest					
	Large Trees / Woodland		1				1
	Sacred Groves		1				1
	Presence of endangered		1				
	species / habitat areas						
	Migratory routes						
	Ecologically sensitive						
	areas						
Human Environment							
2.1 in onnent	Settlements/Habitations	Bara Bainan	1.52	Right	23° 0'30.63"N	87°56'9.43"E	
		Chack Narshinpur	0.74	Right	22°59'42.98"N	87°56'22.72"E	
		Singarpur	0	Right	22°59'56.98"N	87°56'55.79"E	
		Narshingpur	0	Right	22°59'32.71"N		
		Atapur	0	Right	22°59'6.15"N	87°56'44.96"E	
		Hodilpur	0	Right	22°57'53.06"N	87°56'16.11"E	
		Fatepur	2.07	Right	22°56'55.75"N		
		Purbbaharipur	1.09	Right	22°56'29.92"N		
		Bachhanari	1.21	Right	22°55'51.52"N	87°54'58.65"E	
		Tala	2.7	Right	22°56'12.48"N	87°54'6.08"E	
		Malaypur	1.33	Right	22°54'35.88"N	87°53'56.83"E	
		Chak Benshe	0	On middle		87°54'54.59"E	
		Banamalipir	0.50	of the	22°53'58.44"N	87°54'18.89"E	
		Amgaon	0.30	river bed	22°50'3.01"N	87°54'10.10"E	
		Chhandra	0.79	Right	22°50'2.80"N	87°53'52.92"E	

Screening report of Mundeswari River

S. No.	Environmental & Social Features	Name of Establishment/ Description	Status / Availability within 3 km	Left/ Right	Lat	Long	Location Name
		Shyamgram	0.88	Right	22°50'28.77"N	87°53'30.81"E	
		Dakshin Rasulpur	2.46	Right	22°50'44.32"N	87°52'33.09"E	
		Sarati	2.5	Right	22°51'15.86"N	87°52'15.31"E	
		Madhurpur	1.26	Right	22°51'53.87"N	87°52'55.07"E	
		Mazaffarpur	0	Right	22°51'59.85"N	87°53'34.83"E	
		Ashanpur	1.62	Right	22°52'36.53"N		
		Keshabpur	0.26	Right	22°53'9.74"N	87°53'56.87"E	
		Kadipur	0.23	Right	22°49'41.18"N	87°54'36.85"E	
		Saota	0.90	Right	22°50'8.41"N	87°54'58.64"E	
		Rautara	2.46	Left	22°50'9.82"N	87°55'51.52"E	
		Golami Chak	0.34	Left	22°50'34.69"N	87°54'19.07"E	
		Saidpur	2.8	Left	22°50'32.95"N		
		Masinan	2.42	Left	22°50'56.87"N	87°55'29.90"E	
		Purba Krishnapur	1	Left	22°51'33.70"N		
		Paschimpara	3.8	Left	22°52'18.02"N	87°55'51.49"E	
		Harinakhali	3.6	Left	22°52'38.77"N		
		Baitha	0.95	Left	22°53'26.51"N	87°55'20.66"E	
		Krishnabati	1.20	Left	22°53'48.99"N		
		Muidipur	0	Left	23° 0'10.65"N	87°57'37.75"E	
		Nandanpur	1.30	Left	22°59'50.25"N	87°58'28.87"E	
		Reshalatpur	0.90	Left	22°59'28.63"N	87°57'37.52"E	
		Sahapur	1.28	Left	22°57'2.98"N	87°57'6.63"E	
		Bonogram	1.85	*	22°56'49.71"N		
		Fulbagan	0.85		22°56'38.65"N		
		Soaluk	1.55		22°55'31.67"N	87°56'42.82"E	
	Sensitive Receptors	Bouluk	1.55		22 33 31.07 11	07 50 12.02 E	
	School	Dakhin Rosulpur	2.67 Km	Right	22°50'56.08"N	87°52'21.16"E	Daksin
	School	High School	1.40	Right	22°53'29.57"N	87°53'28.70"E	
		Kabikankan	1.40	Rigin	22 33 29.37 IN	67 55 26.70 E	Kaulpul
		Mukundram					
		Mahavidalaya					
	Hospital	wanavidalaya					
	Drinking water sources						
	Utility lines like						
	electricity lines, pipelines						
	for gas, etc						
	Physical cultural						
	<u>resources – ,</u>						
	Protected monuments						
	Historical sites, etc.						
	Physical cultural						
	resources –						
	Mandir						
	Masque						
	Burning Ghat						
	Bedi						
	Agricultural land						
	Defence Installations /						
	Airports						
	National highway	IZ 1 '1 1 D 1	1.05	D' 1/	00051154 50101	0705216 20115	
	State highway / Roads	Kabikankan Road	1.05	Right	22°51'56.52"N	87°53'6.29"E	
		Kabikankan-	0.60	Right	22°54'21.45"N	87°54'20.20"E	
		Mukundpur Road	0.85	Left	23° 0'15.17"N	87°58'10.02"E	
		Ahilyabai Holkar	2.19	Left	22°53'19.66"N		
		Road	0.40	Left	22°51'39.88"N		
		Champadanga -	0.50	Left	22°51'39.88"N	87°54'2.70"E	
		Jamalpur Road					
		Khusigaunj Road					
		Keshabpur Road					
	Heavy polluting Industry	Nirmola Industry		Right	22°44'59.75"N	88° 0'40.47"E	
	Water or Waste water	Kolaghat Water	40.83	Left	22°27'46.47"N	87°52'44.35"E	
	Treatment Plant	Treatment Plant					
		Barunda water treatment plant	39.57	Left	22°27'4.70"N	87°54'55.22"E	
		Aquamyle Mineral Water Plant	39.37	Left	22°27'54.94"N	87°58'48.12"E	

S. No.	Environmental & Social Features	Name of Establishment/ Description	Status / Availability within 3 km	Left/ Right	Lat	Long
Physical						
Environment	Natural Drain	Kamaria Khal	0.27	Right	22.687	88.003
	Standing water bodies	Dighhi	1.65		22°35'38.99"N	88° 0'40.43"E
	(ponds, lakes, etc.)					
	Flowing water bodies	Maja Damodar	1.77	Left	22.661	87.972
	(rivers, rivulets, streams, canals, etc.)	Madaria Khal	0 & 3	Right	22.582	87.997
	Ground water sources (open					
	wells, bore wells, etc.)					
	Meandering River					
	Erosion prone stretches Areas with high slope					
	(higher than 15 percent)					
	Landforms (hills, valleys)					
	Sand Mine					
	Coal Mine					
Biological Environment						
Envir Onnellt	National Park / Wildlife	Garchumuk Deer	22.5	South /	22°20'58.29"N	88° 4'19.91"E
	Sanctuary	Park		Right		
	Reserved Forests	Golakderyama Forest		Left	22°42'10.75"N	87°28'18.74"E
		Dhamkura Scrub	50.24	Left	22°45'11.81"N	87°29'10.39"E
		Forest Amlagora Forest	65.91	Left	22°49'59.70"N	87°20'55.58"E
		Range	05.71	LUIT	22 49 59.70 IN	07 20 35.50 L
		Chondrakona Forest	65.53		22°50'21.33"N	87°21'10.01"E
		Bhuban Danga Forest	45.53	Left	23° 0'24.82"N	87°44'7.99"E
	Community Forest Large Trees / Woodland					
	Sacred Groves					
	Presence of endangered					
	species / habitat areas					
	Migratory routes					
Human	Ecologically sensitive areas					
Environment						
	Settlements/Habitations	Rajapur	2.4	Left	22°41'44.97"N	87°58'37.44"E
		Sonagachhi	0.64	Left	22°41'39.59"N	87°59'38.53"E
		Jonka Kumirmora	1.18 2.02	Left Left	22°41'21.23"N 22°41'12.91"N	87°59'18.37"E 87°58'45.74"E
		Jagaldaha	1.02	Left	22°40'59.82"N	87°59'45.58"E
		Joynagar	0.35	Left	22°40'57.24"N	87°59'20.99"E
		Purpat	2.25	Left	22°40'37.60"N	87°58'35.01"E
		Naryanpur Chak Ray Chak	0.53 2.9	Left Left	22°40'16.58"N 22°40'4.75"N	87°59'27.48"E 87°57'50.69"E
		Kanupat	2.9	Left	22°40'5.16"N	87°58'26.19"E
		monsuka	0.52	Left	22°39'50.08"N	87°59'41.11"E
		Debipur	2.38	Left	22°39'48.79"N	87°57'54.78"E
		Kumarchak Garh Bhawanipur	0.47 1.50	Left Left	22°39'22.70"N 22°39'11.12"N	87°59'1.36"E 87°58'8.43"E
		Pathiagori	0.22	Left	22°39'4.46"N	87°58'54.55"E
		Sonatala	2.86	Left	22°39'5.62"N	87°57'19.57"E
		Kansona	0.15	Left	22°38'42.26"N	87°58'55.21"E
		Bhawanipur Bidhichandrapur	1.19 2.81	Left Left	22°38'36.26"N 22°38'17.29"N	87°57'53.19"E 87°56'58.29"E
		Chitrasenpur	1.29	Left	22°38'17.29 N 22°38'18.17"N	87°58'8.49"E
		Bajeprotap	0.15	Left	22°38'4.96"N	87°58'45.67"E
		Raghunathpur	1.81	Left	22°37'44.54"N	87°57'15.69"E
		Ranjaybar Pratapnaryanpur	2.66 0.18	Left Left	22°37'39.00"N 22°37'35.10"N	87°56'44.33"E 87°58'17.65"E
		Shaoraberia	1.66	Left	22°37'35.10 N 22°36'55.98"N	87°57'19.95"E
		Hanidhara	0.58	Left	22°36'44.52"N	87°58'6.60"E
		Binalakrishnabati	0.66	Left	22°36'19.40"N	87°57'59.26"E
		Nischintapur Thaliya	1.44 0.59	Left Left	22°35'57.59"N	87°57'24.51"E
		Mainan	0.59 1.9	Left	22°35'47.18"N 22°35'27.04"N	87°57'59.20"E 87°58'44.04"E

Screening report of Damodar Left and Right Embankment

S. No.	Environmental & Social Features	Name of Establishment/ Description	Status / Availability within 3 km	Left/ Right	Lat	Long
		Khorop	1.24	Left	22°34'49.06"N	87°59'6.53"E
		Kalbansh	2.54	Left	22°34'32.66"N	87°58'25.65"E
		Betai	0.67	Left	22°34'33.12"N	87°59'27.52"E
		Bargazipur	2.57	Left	22°34'10.90"N	87°57'59.14"E
		Jayanti	0.46	Left	22°34'12.39"N	87°59'36.89"E
		Paschim Gazipur	2.81	Left	22°33'40.10"N	87°59'1.38"E
		Nawapara	0.63	Left	22°33'14.83"N	87°57'48.41"E
		Sirol Mahishamuri	2.77		22°32'56.81"N	87°59'1.32"E
		Khasnan	0.71	Disht	22022125 4C"N	97950145 55"E
		Knasnan Purba Gazipur	0.43 0.93	Right Right	22°32'25.46"N 22°32'46.66"N	87°59'45.55"E 88° 0'3.46"E
		Ranapara	0.55	Right	22°33'18.85"N	87°59'45.65"E
		Deora	0.54	Right	22°33'45.89"N	87°59'58.66"E
		Guzarpur	2.5	Right	22°33'47.45"N	88° 1'9.05"E
		Amta	1.03	Right	22°34'16.09"N	88° 0'32.26"E
		Serajbati	0.63	Right	22°34'45.22"N	88° 0'12.13"E
		Damodar Nadirchar	0.10	Right	22°34'58.56"N	87°59'52.44"E
		Madaria	0.76	Right	22°35'16.89"N	88° 0'11.99"E
		Jotkalyan	2.48	Right	22°35'6.78"N	88° 1'13.42"E
		Mallagram	2.7	Right	22°35'25.34"N	88° 1'10.93"E
		Sameshwar	0.85	Right	22°35'53.69"N	87°59'40.77"E
		Kalitala	0.60	Right	22°35'58.38"N	87°59'1.00"E
		Kotalpara	2.95	Right	22°36'19.07"N	87 39 1.00 E 88° 0'35.87"E
		Rashpur	0.39	Right	22°36'6.67"N	87°58'38.36"E
		Kumaria	1.84	Right	22°36'37.35"N	87°59'41.14"E
		Putkhali	2.9	Right	22°36'42.98"N	88° 0'20.87"E
		Bhojan	0.85	Right	22°36'58.28"N	87°58'48.68"E
		Sarpai	1.79	Right	22°37'19.26"N	87°59'24.04"E
		Khaira	2.96	Right	22°37'26.13"N	88° 0'12.14"E
		Begua	0.51	Right	22°37'35.15"N	87°58'52.80"E
		Purba Bajepratap	0.37	Right	22°38'8.15"N	87°59'10.10"E
		Balichak	0.48	Right	22°38'40.22"N	87°59'19.13"E
		Peruhareshpur	2.9	Right	22°38'46.29"N	88° 0'51.64"E
		Dhurkhali	1.6	Right	22°38'51.35"N	88° 0'2.68"E
		Krishnachak	1.89	Right	22°39'2.09"N	88° 0'21.11"E
		Thakuranichak	0.63	Right	22°39'12.88"N	87°59'45.35"E
		Narikelberia	0.41	Right	22°39'42.43"N	88° 0'27.10"E
		Nazarkhan	1.66	Right	22°39'48.27"N	88° 1'2.74"E
		Khila	1.23	Right	22°40'6.88"N	88° 0'29.52"E
		Nayachak	0.35	Right	22°40'8.96"N	88° 0'1.01"E
		Benupalchak	2.07	Right	22°40'20.36"N	88° 1'7.03"E
		gourangachak	0.24	Right	22°40'35.73"N	88° 0'5.45"E
		boruipur	1.16	Right	22°40'38.94"N	88° 0'38.19"E
		Shibnarayanachak	1.90	Right	22°40'38.74"N	88° 1'4.69"E
		dongajal	0.90	Right	22°41'2.63"N	88° 0'31.50"E
	Sensitive Receptors					
	School	Indira Gandhi	2.32	Right	22°39'16.01"N	87°57'42.36"E
		Memorial B.ED	2.4	Left	22°33'48.68"N	87°58'38.67"E
		College	3.74	Left	22°36'20.92"N	87°56'21.10"E
		Gazipur Girls	3.72	Right	22°40'41.11"N	88° 2'7.08"E
		Joypur Panchana roy	1	Left	22°43'12.39"N	87°59'16.34"E
		College	0.33	Right	22°34'31.11"N	88° 0'5.57"E
		Puras-Kanpur	1.7	Right	22°34'23.27"N	88° 0'53.38"E
		Haridas Nandi			22°34'30.17"N	88° 0'4.66"E
		Mahavidyalaya			22°34'22.64"N	88° 0'53.03"E
		Udaynarayanpur	2.87	Right	22°38'45.88"N	88° 0'46.41"E
		Madhabilata				
		Mahavidyalaya				
		Ramsaday College				
		Amta Pitambar high	1			
		school				
		Harishpur Board				
		Pimary School				
	Hospital	Senha Nurshing	1.4	Right	22°34'6.86"N	88° 0'45.71"E
		Home		Ŭ		
	Drinking water sources					
	Utility lines like electricity					
	lines, pipelines for gas, etc					
	Physical cultural					
		1	1	1	1	1
	resources – ,					

S. No.	Environmental & Social Features	Name of Establishment/ Description	Status / Availability within 3 km	Left/ Right	Lat	Long
	Historical sites, etc.					
	<u>Physical cultural</u> resources –					
	Mandir					
	Masque	Barasat Masjid	2.42	Right	22°38'55.75"N	87°57'33.50"E
	Burning Ghat					
	Bedi					
	Agricultural land					
	Defence Installations / Airports					
	National highway	NH 6	7.26	Right	22°28'18.02"N	88° 0'10.76"E
	State highway	Bagnan - Amta Road Amta- Udayanarayanpur Road udayanaryanapur Road	1.38 1.9	right Left Both Right & Left	22°33'17.71"N 22°35'8.07"N 22°39'22.03"N / 22°41'14.46"N	88° 0'9.83"E 87°58'13.03"E 88° 1'0.22"E / 87°58'52.23"E
	Heavy polluting Industry	Nirmola Industry		Right	22°44'59.75"N	88° 0'40.47"E
	Water or Waste water Treatment Plant	Kolaghat Water Treatment Plant	13.51	Left	22°27'46.47"N	87°52'44.35"E
		Barunda water treatment plant	12.61	Left	22°27'4.70"N	87°54'55.22"E
		Aquamyle Mineral Water Plant	7.49	Left	22°27'54.94"N	87°58'48.12"E

S. No.	Environmental & Social Features	Name of Establishment/ Description	Status / Availability within 3 km	Left/ Right	Lat	Long
Physical		•				
Environment	N. ID.	A11 1 1771 1	0	D: 1/	22.94	07.050
	Natural Drain	Akhabari Khal Khanakhul Khal	0 1.36	Right Right	22.84 22.678	87.959 87.888
	Standing water bodies					
	(ponds, lakes, etc.)					
	Flowing water bodies (rivers,	D1 Canals	2 2	Left	22.831	87.976
	rivulets, streams, canals, etc.)	Amta River Champadanga	2 0.86	Left Left	22.805 22.857	87.969 87.946
		Hurhura	1.5	Left	22.665	87.940 87.902
		Harinkhola-2	0, 2.4, 2	Right	22.717	87.917
		Mundeswari	3, 1.29	Right	22.768	87.932
	Ground water sources (open					
	wells, bore wells, etc.)					
	Meandering River Erosion prone stretches					
	Areas with high slope (higher					
	than 15 percent)					
	Landforms (hills, valleys)					
	Sand Mine					
	Coal Mine	Not Available	Not	Not	Not Available	Not Available
Biological			Available	Available		
Environment						
	National Park / Wildlife	Chiladangi Park	1.7	Right	22°48'19.89"N	87°56'39.39"E
	Sanctuary	Garchumuk Deer Park	39.3	Right	22°20'58.29"N	88° 4'19.91"E
	Reserved Forests	Chandur Forest		Right	22°54'39.95"N	87°46'5.59"E
		Golakderyama Forest		Left	22°42'10.75"N	87°28'18.74"E
		Dhamkura Scrub	47.18	Left	22°45'11.81"N	87°29'10.39"E
		Forest Amlagora Forest	61.9	Left	22°49'59.70"N	87°20'55.58"E
		Range	01.9	Len	22 4) 5).70 N	07 20 55.50 E
		Chondrakona Forest	61.1	Left	22°50'21.33"N	87°21'10.01"E
		Bhuban Danga Forest	27.69	Left	23° 0'24.82"N	87°44'7.99"E
	Community Forest					
	Large Trees / Woodland					
	Sacred Groves Presence of endangered					
	species / habitat areas					
	Migratory routes					
	Ecologically sensitive areas					
Human						
Environment						
	Settlements/Habitations	Jungle Para	1.6	Right	22°51'41.39"N	87°57'6.91"E
		Nimdangi Saidpur	3 2.89	Right Right	22°51'29.41"N 22°50'33.29"N	87°55'56.44"E 87°55'53.71"E
		Rautara	2.59	Right	22°50'8.98"N	87°55'51.39"E
		Shrirampur	0.40	Right	22°49'32.36"N	87°56'58.17"E
		Hati	2.28	Right	22°49'26.39"N	87°55'51.86"E
		Samaspur	3.59	Right	22°49'9.68"N	87°55'30.08"E
		Parul Balarampur	2.08 1.32	Right Right	22°48'59.64"N 22°49'0.43"N	87°56'13.94"E 87°56'40.72"E
		Sundarush	1.52 0	Right	22°49'0.43 N 22°48'44.48"N	87°57'19.85"E
		Chiladangi	1.60	Right	22°48'17.16"N	87°56'23.04"E
		Harua	2.20	Right	22°48'6.20"N	87°56'4.96"E
		Gopimohanpur	3.00	Right	22°48'0.07"N	87°55'34.17"E
		Ghoi Diguri Neota	2.34	Right Right	22°47'17.58"N 22°46'40.78"N	87°56'9.20"E
		Neota Panthahari	1.48 0.25	Right Right	22°46'40.78"N 22°45'58.32"N	87°56'40.05"E 87°56'49.25"E
		Udna	2.28	Right	22°45'51.95"N	87°55'34.22"E
		Balipur	0.96	Right	22°45'20.23"N	87°56'18.47"E
		Kanakpur	1.78	Right	22°45'3.79"N	87°55'47.29"E
		Purbba Radhanagar	1.90	Right	22°44'25.98"N	87°55'51.93"E
		Daspur Chhatrashali	0.44	Right	22°44'5.21"N	87°56'26.97"E
		Chhatrashali Garbere	2.29 0.58	Right Right	22°43'42.47"N 22°43'35.13"N	87°55'16.25"E 87°56'15.88"E
		Arunda	1.85	Right	22°43'35.43"N	87°56'15.90"E
	1	Bandaipur	0.34	Right	22°42'55.16"N	87°56'22.45"E

Environmental Screening of Uppper Rampur Khal

S. No.	Environmental & Social Features	Name of Establishment/ Description	Status / Availability within 3 km	Left/ Right	Lat	Long
		Kabilpur	1.96	Right	22°41'54.47"N	87°53'48.47"E
		Jayram Chak	2.88	Right	22°41'58.93"N	87°52'59.46"E
		Sola Asta	0.62	Right	22°41'36.19"N	87°54'31.17"E
		Uttar Sudam Chak	1.38	Right	22°41'17.00"N	87°53'52.58"E
		Jugikundu	1.19	Right	22°41'16.26"N	87°54'9.32"E
		Malancha	0.39	Right	22°41'17.46"N	87°54'36.51"E
		Balaichak	0.51	Left	22°41'15.69"N	87°55'5.49"E
		Subalchak	0.81	Left	22°41'7.72"N	87°55'38.22"E
		Kakraipota	1.58	Left	22°41'13.41"N	87°56'9.87"E
		Nabinchak	1.19	Left	22°40'45.83"N	87°55'20.78"H
		Ambagan	1.74	Left	22°40'43.21"N	87°55'40.72"H
		Chinra	1.43	Left	22°40'18.92"N	87°55'8.03"E
		Uttar Manasri	2.94	Left	22°40'9.04"N	87°56'9.49"E
		Santoschak	2.80	Left	22°40'57.44"N	87°56'49.40"I
		Ramsharan Chak	0.9	Left	22°41'46.52"N	87°55'50.45"1
		Harishpur	1.04	Left	22°41'37.97"N	87°56'51.51"H
		Pancharul	0.64	Left	22°42'1.98"N	87°56'40.28"I
			2.08	Left	22°42'2.74"N	
		Uttar Harishpur Khorda Etarai		Left		87°57'33.32"1
			0.36		22°42'52.75"N	87°56'46.59"1
		Etarai	1.66	Left	22°42'45.55"N	87°57'33.34"I
		Sibpur	2.86	Left	22°42'41.45"N	87°58'12.85"I
		Goja	1.29	Left	22°43'22.96"N	87°57'20.10"I
		Piarapur	0.82	Left	22°43'49.69"N	87°57'6.65"E
		Harali	0.43	Left	22°44'42.15"N	87°57'6.11"E
		Sultanpur	1.24	Left	22°44'6.07"N	87°57'37.65"I
		Pratap Chak	2.63	Left	22°44'2.12"N	87°58'26.48"I
		Sitapur	2.41	Left	22°44'30.92"N	87°58'14.16"1
		Khempur	2.55	Left	22°44'54.39"N	87°58'17.41"I
		Dakshin Rampur	1.54	Left	22°45'5.40"N	87°57'42.33"
		Pursura	0.20	Left	22°50'10.81"N	87°57'37.55"
		Harihar	0.33	Left	22°49'54.10"N	87°57'32.93"]
		Champadanga	1.46	Left	22°50'16.33"N	87°58'25.45"1
		Moktarpur	2.42	Left	22°50'33.24"N	87°59'5.84"E
		Fatehpur	1.90		22°48'1.70"N	87°57'54.89"I
		Binogram	1.98		22°48'27.46"N	87°58'29.27"I
		Bhawanipur	0.86		22°46'57.79"N	87°57'55.40"I
		Kotalpara	1.48		22°46'52.48"N	87°58'17.29"1
		Par Bhurshitta	1.05		22°46'30.99"N	87°58'8.47"E
		Dihbhurust	2.07		22°46'15.74"N	87°58'48.00"1
		Ashanda	1.57		22°45'53.43"N	87°58'12.76"H
	Sensitive Receptors	Astialiua	1.57		22 43 33.43 IN	07 30 12.70 1
	School	Vidyasagar Institute of	0.83	Left	22°50'30.38"N	87°58'6.77"E
	501001		0.85	Len	22 30 30.38 IN	0/ J00.// E
		Education Technology				
		and Research, College,				
		Pursura, West Bengal				
			1.80	Left	22°49'34.40"N	87°58'37.08"]
		Rabindra				
		Mahavidalaya	ļ			l
	Hospital	Natibpur Hospital	2.75	Left	22°39'25.36"N	87°53'18.39"1
	Drinking water sources					
	Utility lines like electricity					
	lines, pipelines for gas, etc					1
	Physical cultural resources		1			
						1
	Protected monuments		ł	1		1
	Historical sites, etc.		1			+
			<u> </u>			
	Physical cultural resources					
						<u> </u>
	Mandir	D 1 V V V V V		D. L.		05054100 5
	Masque	Purbapara Majsid	5.36	Right	22°38'58.54"N	87°51'33.51"I
	Burning Ghat					
	Bedi					
	Agricultural land					
	Defence Installations /					
	Airports					1
	National highway	Ahiliyabai-holkar	0,3	Both Left &	22°50'22.45"N	87°57'42.13"
	inauonai nignway					
		Road	1.18	Right	22°50'32.41"N	87°58'22.05"]
		Champadanga road		Left		L
	State highway	Purusura - Amanpur	0.20, 1.10	Left	22°50'45.94"N	87°58'12.67"
		Road	1.9	Left	22°50'20.18"N	87°58'18.29"
		Itouu	0, 3			87°56'24.90"

S. No.	Environmental & Social Features	Name of Establishment/ Description	Status / Availability within 3 km	Left/ Right	Lat	Long
		State Highway 15 Samanta road				
	Heavy polluting Industry	Nirmola Industry	5.8	Right	22°44'59.75"N	88° 0'40.47"E
	Water or Waste water Treatment Plant	Kolaghat Water Treatment Plant	24.09	Right	22°27'46.47"N	87°52'44.35"E
		Barunda water treatment plant	22.39	Right	22°27'4.70"N	87°54'55.22"E
		Aquamyle Mineral Water Plant	22.8	Right	22°27'54.94"N	87°58'48.12"E

S. No.	ntal Screening of Hurhurd Environmental & Social Features	Name of Establishment/ Description	Status / Availability within 3 km	Left/ Right	Lat	Long
Physical						
Environment	Natural Drain	Upper Rampur Channel	1.0	Right	22.68	87.906
	Standing water bodies (ponds,	Opper Kampur Channel	1.0	Right	22.08	87.900
	lakes, etc.)					
	Flowing water bodies (rivers,	Rupnaryan Upper	1.8	Right	22.57	87.85
	rivulets, streams, canals, etc.)	Mundeswari Kata Khal	0.69 1.9	Right	22.62 22.651	87.87 87.884
		Maja Damodar	2.28	Right Right	22.597	87.884 87.891
	Ground water sources (open wells, bore wells, etc.)		2.20	Right	22.371	07.071
	Meandering River					
	Erosion prone stretches					
	Areas with high slope (higher than 15 percent)					
	Landforms (hills, valleys)					
	Sand Mine					
	Coal Mine	Not Available	Not Available	Not Available	Not Available	Not Available
Biological						
Environment	National Park / Wildlife Sanctuary	Garchumuk Deer Park	30.16	Right	22°20'58.29"N	88° 4'19.91"E
	Reserved Forests	Golakderyama Forest	42	Left	22°42'10.75"N	87°28'18.74"E
		Dhamkura Scrub Forest	42.5		22°45'11.81"N	87°29'10.39"E
		Amlagora Forest Range	59.2		22°49'59.70"N	87°20'55.58"E
		Chondrakona Forest	58.5		22°50'21.33"N	87°21'10.01"E
	Community Forest	Bhuban Danga Forest	41.2	Left	23° 0'24.82"N	87°44'7.99"E
	Large Trees / Woodland					
	Sacred Groves					
	Presence of endangered species /					
	habitat areas					
	Migratory routes Ecologically sensitive areas					
Human	Ecologically sensitive areas					
Environment						
	Settlements/Habitations	Jayarampur	2.64	Right	22°40'32.49"N	87°52'15.09"E
		Natibpur Chinra	1.16 1.83	Right Left	22°39'45.19"N 22°40'18.90"N	87°53'30.56"E 87°55'8.08"E
		Mostafpur	0.33	Left	22°39'2.99"N	87°54'24.49"E
		Palashpai	0.73	Left	22°37'53.59"N	87°54'19.23"E
		Chanpanagari	1.43	Left	22°37'50.94"N	87°54'51.86"E
		Boalia	2.56	Left	22°37'43.49"N	87°55'38.28"E
		Katashia Jhikhira	2.09 2.22	Left Left	22°38'16.08"N 22°37'22.00"N	87°55'47.26"E 87°55'3.68"E
		Ghardubra	2.22	Left	22°37'10.75"N	87°54'36.80"E
		Mansuka	0.16	Left	22°37'30.63"N	87°52'42.11"E
		Bhairabpur	1.4	Left	22°37'31.14"N	87°53'35.01"E
		chingrajola	2.88	Left	22°36'57.35"N	87°54'26.27"E
		Hayatpur Mahishnala Damkunda	1.28 0.04	Left Left	22°36'53.88"N 22°36'28.91"N	87°53'12.95"E 87°52'22.39"E
		Shibgachhia	2.4	Left	22°36'11.16"N	87°53'30.42"E
		Uttar Bhatora	00	Left	22°35'26.92"N	87°52'2.17"E
		Solbaga	0.9	Left	22°35'27.07"N	87°52'37.09"E
		Kamar Khola	2.67	Left	22°35'1.20"N	87°53'34.75"E
		Kasmali Nignan	1.8 2.10	Left Left	22°34'23.78"N 22°33'24.82"N	87°53'13.29"E 87°53'34.79"E
		Takipara	.20	Left	22°32'57.67"N	87°52'55.35"E
		Ajangachhi	0.79	Left	22°32'52.23"N	87°53'17.01"E
		Balpai	0.48	Right	22°39'2.68"N	87°53'48.38"E
		Harischak	2.7	Right	22°38'45.51"N	87°52'15.58"E
		Sabalsinghpur Dakshin Sudam Chak	2.7 1.50	Right Right	22°38'39.96"N 22°37'56.78"N	87°51'26.83"E 87°51'44.80"E
		Khunechak	1.30	Right	22°38'25.39"N	87°53'26.58"E
		Narendrapur	0.32	Right	22°38'3.61"N	87°53'26.18"E
		Sasapota	0.8	Right	22°37'30.01"N	87°51'58.20"E
		Hanua	2.18	Right	22°37'19.31"N	87°51'13.42"E

Environmental Screening of Hurhura Khal


S. No.	Environmental & Social	Name of Establishment/	Status /	Left/	Lat	Long
	Features	Description	Availability	Right		
			within 3 km			
		Kamdeb Chak	.052	Right	22°36'57.92"N	87°52'6.02"E
		Joariachak	0.89	Right	22°36'47.58"N	87°51'49.02"E
		Manikdwip	1.80	Right	22°36'28.00"N	87°51'11.83"E
		Marokhana	0.91	Right	22°36'25.42"N	87°51'39.82"E
		Kaijuri	2.58	Right	22°35'47.81"N	87°50'33.70"E
		Benai	2.4	Right	22°34'21.30"N	87°50'33.93"E
		Dakshin Bhatora	1.4	right	22°34'0.25"N	87°51'9.08"E
		Ghoraberia	0.38	right	22°34'0.74"N	87°51'45.22"E
		Kulia	0.16	Right	22°33'34.70"N	87°52'6.65"E
		Mirgram	0.56	Right	22°32'56.97"N	87°52'19.52"E
		Hatgachha	1.86		22°33'1.80"N	87°51'22.57"E
	Sensitive Receptors	16				
	School	Indira Gandhi Memorial	6.9	Right	22°39'15.97"N	87°57'42.12"E
		BED college	6.63	Right	22°36'20.92"N	87°56'21.10"E
		Joypur Panchana roy	6.44	Left	22°34'12.39"N	87°48'21.23"E
		College				
		Chaipat SPB				
		Mahavidalaya				
	Hospital	Natibpur Hospital	1.49	Right	22°39'25.75"N	87°53'18.86"E
	Drinking water sources					
	Utility lines like electricity lines,					
	pipelines for gas, etc					
	Physical cultural resources -,					
	Protected monuments					
	Historical sites, etc.					
	Physical cultural resources –					
	Mandir					
	Masque	Purba Para Majsid	2.89	Right	22°38'59.26"N	87°51'34.74"E
		Bitulaha	5	Right	22°36'8.32"N	87°55'14.27"E
	Burning Ghat					
	Bedi					
	Agricultural land					
	Defence Installations / Airports					
	National highway	NH 6	10.75	south	22°27'57.17"N	87°57'28.36"E
	State highway					
	Heavy polluting Industry	Nirmola Industry	13.9	Right	22°44'59.75"N	88° 0'40.47"E
	Water or Waste water Treatment	Kolaghat Water Treatment		Right	22°27'46.47"N	87°52'44.35"E
	Plant	Plant				
		Barunda water treatment plant	10.3	Right	22°27'4.70"N	87°54'55.22"E
		Aquamyle Mineral Water Plant	15.2	Right	22°27'54.94"N	87°58'48.12"E

All 41 canals proposed for desiltation are divided into two cluster. Cluster wise LULC map is given below.

S. No.	Environmental & Social Features	Name of Establishment/ Description	Status / Availability within 3 km radius	Left/ Right	Lat	Long
Physical Environment						
Environment	Natural Drain					
	Standing water bodies					
	(ponds, lakes, etc.)					
	Flowing water bodies	Gheshopatti	0.37 km from Mahisamori	Left	22.554	87.955
	(rivers, rivulets, streams,	Khal	Khal	Both Left &	22.514	87.955
	canals, etc.)	Gaighata Khal	Passing between Bankura	Right	22.541	87.911
		short-cut	Khal and Birampur Khal	Left	22.504	87.961
		Channel	0.52 from Maja Damodar	Left		
	G 1 4	Amta Channel	0 Km from Bankura Khal			
	Ground water sources (open wells, bore wells,					
	etc.)					
	Meandering River					
	Erosion prone stretches					
	Areas with high slope					
	(higher than 15 percent)					
	Landforms (hills,					
	valleys)					
	Sand Mine					
	Coal Mine	Not Available	Not Available	Not	Not Available	Not Available
				Available		
Biological						
Environment	National Park / Wildlife	Not Available	Not Available	Not	Not Available	Not Available
	Sanctuary	Not Available	Not Available	Available	Not Available	Not Available
	Reserved Forests	Not Available	Not Available	Not	Not Available	Not Available
	Reserved Forests	Not Available	Not Available	Available	Not Available	Not Available
	Community Forest	Not Available	Not Available	Not	Not Available	Not Available
				Available		
	Large Trees / Woodland	Not Available	Not Available	Not	Not Available	Not Available
	_			Available		
	Sacred Groves	Not Available	Not Available	Not	Not Available	Not Available
				Available		
	Presence of endangered	Not Available	Not Available	Not	Not Available	Not Available
	species / habitat areas	NT-4 A	Not Available	Available	NT-4 A	NT-4 A
	Migratory routes	Not Available	Not Available	Not Available	Not Available	Not Available
	Ecologically sensitive	Not Available	Not Available	Not	Not Available	Not Available
	areas	Not Available	Not Available	Available	Not Available	Not Available
Human	areas			Tranable		
Environment						
	Settlements/Habitations	Birampu	0.17 km from birampur khal	Left	22°29'23.86"N	87°54'40.74"E
		Sabsit	1.14 km from birampur khal	Right	22°29'24.99"N	
		Bagur	1.96 km from birampur khal	Right	22°29'30.54"N	
		Amrajol	1.59 km from birampur khal	Left	22°30'1.65"N	87°54'19.02"E
		Kalyanpur	0.88 km from birampur khal	Left	22°30'10.98"N	
		brahmangram	0.92 km from birampur khal	Right	22°30'13.74"N	
		Manku	3 km from birampur khal	Left	22°30'54.80"N	87°53'52.22"E
		Chakur	0.38 km from birampur khal	Left	22°30'50.70"N	
		Deulgram	2.12 km from birampur khal	Left	22°31'11.50"N	
		Adul Kajiharia	1.55 km from birampur khal	Left	22°31'9.01"N	87°55'1.12"E
		Kajiberia Malia	2.97 km from birampur khal 2.12 km from birampur khal	Left Left	22°31'29.82"N 22°31'38.47"N	
		Bholsar	1.66 km from birampur khal	Left	22°31'38.47 N 22°31'38.99"N	
		Kulepairi	0.55 km from birampur khal	Left	22°31'39.14"N	
		Kasrakatai	2.91 km from birampur khal	Left	22°31'54.15"N	
	1	Bankura	0.36 km from bankura khal	Right	22°30'57.63"N	
		Pansila	0.32 km from bankura khal	Left	22°31'18.43"N	
		Sital Chak	0.75 km from bankura khal	Right	22°31'19.33"N	
		Sarda	1.37 km from bankura khal	Right	22°31'35.15"N	
		Tajpur	0.87 km from mahisamori	Right	22°32'19.45"N	87°58'48.14"E
		1	khal	1	1	1

Environmental Screening of Cluster 1 (For dredging of 41 canal)


S. No.	Environmental & Social Features	Name of Establishment/ Description		Left/ Right	Lat	Long
		Kusberia	0.81 km from mahisamori khal	Right	22°32'39.62"N	87°57'37.50"E
		Sirol	0.26 km from mahisamori khal	Left	22°33'14.52"N	87°57'48.42"E
		Mahishhamuri	0.31 km from mahisamori khal	Left	22°32'56.56"N	87°59'2.11"E
		Purbba Khalan	2.4 km from mahisamori khal	Right	22°32'38.87"N	87°56'44.77"E
		Nignan	0.1 km from Khorigeria Khal	right	22°33'25.09"N	87°53'34.83"E
		Khari Geria	0.53 Km from Khorigeria Khal	right	22°33'19.91"N	87°54'5.42"E
		Kasmali	0.2 from Kashmati khal	Left	22°34'23.17"N	87°53'13.17"E
		Jhamtia	0.88 from maja damodar	Right	22°34'24.20"N	87°54'41.19"E
		Chak janardan	0.27 kmfrom sabgachtala khala	Left	22°35'56.11"N	87°55'11.79"E
		Ghanshyam Chak	0.13 from maja damodar	Right	22°36'4.65"N	87°55'40.94"E
		Jaypur	0.36 from maja damodar	Right	22°35'18.82"N	87°55'42.68"E
		Khajur Daha	0.71 km from sabgachtala khal	Left	22°33'57.73"N	87°55'29.67"E
	Sensitive Receptors					
	School	Bainan Girl's	1.15 Km from Bankura Khal	Right	22°30'7.12"N	87°56'54.16"E
		High School Bainan Baman Das High School (H.S) Joypur Panchanan Roy	0.60 Km from Bakura Khal 0.68 from sabgachtla khal	Right Right	22°30'27.07"N 22°36'19.86"N	87°56'56.29"E 87°56'20.06"E
	Hospital	College				
	Drinking water sources					
	Utility lines like					
	electricity lines, pipelines for gas, etc					
	<u>Physical cultural</u> resources – ,					
	Protected monuments	Not Available	Not Available	Not Available	Not Available	Not Available
	Historical sites, etc.	Not Available	Not Available	Not Available	Not Available	Not Available
	Physical cultural					
	resources –					
	Mandir					
	Masque	Masjid a Alamin Hajrat Buropir Saheb Majar Sanglagna Masjid Baitullah	2.5 Km from Birampur Khal 0.50 km from Birampur khal 0.29 km from sabgachtla khal	Left	22°29'51.09"N 22°30'11.19"N 22°36'10.45"N	87°54'56.34"E
	Burning Ghat					
	Bedi					
	Agricultural land					
	Defence Installations / Airports	Not Available	Not Available	Not Available	Not Available	Not Available
	National highway	Not Available	Not Available	Not Available	Not Available	Not Available
	State highway / Roads	Mankur road Joypore Road Bagnan Amta Road	2.74 Km from Birampur Khal and also intersecting the Birramur khal 0.4 from Birampur Khal 2.6 km from bankura khal	Right Right right	22.505 22.504 22.516	87.921 87.925 87.971
	Heavy polluting Industry	Not Available	Not Available	Not Available	Not Available	Not Available
	Water or Waste water Treatment Plant	Not Available	Not Available	Not Available	Not Available	Not Available



S. No.	Environmental & Social Features	Name of Establishment/ Description	Status / Availability within 3 km radius	Left/ Right	Lat	Long
Physical	Natural Drain					
Environment						
	Standing water bodies (ponds, lakes, etc.)					
	Flowing water bodies (rivers, rivulets, streams, canals, etc.)	Amta Channel	Passes through santoeshpur Khal, Kultipara Khal, Sasaberia Khal Tetua Khal, Naipukur Khal, Godakhali khal, boalia	Both Left & Right	22.433	88.027
		Medinipur Khal	Khal from 0 to 1 Km 0.37 from santoshpur Khal	Right	22.451	88.006
	Ground water sources (open wells, bore wells, etc.)					
	Meandering River					
	Erosion prone stretches Areas with high slope (higher than 15 percent)					
	Landforms (hills, valleys)					
	Sand Mine					
	Coal Mine	Not Available	Not Available	Not Available	Not Available	Not Available
Biological Environment	National Park / Wildlife Sanctuary	Not Available	Not Available	Not Available	Not Available	Not Available
	Reserved Forests	Not Available	Not Available	Not Available	Not Available	Not Available
	Community Forest	Not Available	Not Available	Not Available	Not Available	Not Available
	Large Trees / Woodland	Not Available	Not Available	Not Available	Not Available	Not Available
	Sacred Groves	Not Available	Not Available	Not Available	Not Available	Not Available
	Presence of endangered species / habitat areas	Not Available	Not Available	Not Available	Not Available	Not Available
	Migratory routes	Not Available	Not Available	Not Available	Not Available	Not Available
	Ecologically sensitive areas	Not Available	Not Available	Not Available	Not Available	Not Available
Human Environment	Settlements/Habitations	Khalor	1.25 from Madhabpur Khal	Left	22°27'28.91"N	87°58'27.11"E
		Rasti	0.27 from santoshpur khal	Left	22°27'12.56"N	87°57'51.16"E
		Ramchandrapur	0.45 from Madhabpur Khal	Left	22°27'25.06"N	87°59'10.08"E
		Paikpari	0.10 from santoshpur khal	Left	22°27'13.88"N	87°59'27.27"E
		Antila	0.59 from santoshpur khal	Left	22°26'41.62"N	87°58'26.42"E
		Gunandapur	0.97 from kultipara khal	Left	22°26'41.30"N	87°58'52.35"E
		Sanstoshpur Kultipara	0.29 from kultipara khal 0.27 from kultipara khal	Left Left	22°26'52.48"N 22°26'36.31"N	87°59'27.94"E 87°59'58.31"E
		Batul	2.11 from kultipara khal	Left	22°26'8.71"N	87°58'43.47"E
		Kanalpur	1.08 from kultipara khal	Left	22°25'58.68"N	87°59'36.56"E
		Mirjapur	0.65 from Tetua khal	Left	22°25'36.80"N	87°59'10.10"E
		Mugkalyan Rabibhag	1.12 from Tetua khal 0.15 from Rabibhag khal	Left Left	22°25'10.39"N 22°25'54.15"N	87°58'48.02"E 88° 0'51.83"E
		Rupasgari	1.12 from Tetua khal	Left	22°25'11.18"N	87°59'59.02"E
		Panchani Guzrat	1.06 from Nalpur Khal	Left	22°24'55.29"N	88° 0'47.23"E
		Madanmohanpur	0.10 from Nalpur Khal	Left	22°24'33.42"N	87°59'53.93"E
		Chhayani Guzrat	0.39 from Nalpur Khal	Left	22°24'33.91"N	88° 0'56.19"E

Environmental Screening of Cluster 2 (Dredging of 41 Canal)

S. No.	Environmental & Social Features	Name of Establishment/ Description	Status / Availability within 3 km radius	Left/ Right	Lat	Long
		Duaniguzrat	0.55 from Nalpur Khal	Left	22°24'7.48"N	88° 1'26.55"E
		Basudebpur	1.19 from Nalpur Khal	Left	22°23'50.62"N	88° 0'11.47"E
		Raynagar	1.38 from Nalpur Khal	Left	22°23'40.08"N	88° 0'38.30"E
		Naoda	1.82 from Nalpur Khal	Left	22°23'24.71"N	88° 1'9.12"E
		Bauria	0.47 from Boalia Khal	Right	22°23'42.68"N	
		Amtala	0.10 from Boalia Khal	Right	22°24'3.71"N	88° 3'16.97"E
					22 24 5.71 N	
		Beraberia	1.12 from Boalia Khal	Right	22°24'8.42"N	88° 2'19.63"E
		Gadaipur	0.05 from Godakhali Khal	Right	22°24'51.70"N	88° 2'2.47"E
		Samruk	0.05 from Godakhali Khal	Right	22°24'52.18"N	88° 3'12.07"E
		Dahuka Nischindipur	0.69 from Godakhali Khal	Right	22°24'57.07"N	88° 2'32.27"E
		Hatgachha	0.70 from Godakhali Khal	Right	22°25'10.98"N	88° 2'59.80"E
		Mongrajpur	0.72 from Godakhali Khal	Right	22°25'17.49"N	88° 2'6.15"E
		Bar Mongrajpur	0.71 from kharia Moyanpur Khal	Right	22°25'33.56"N	88° 1'43.86"E
		Kharia	0.17 from kharia Moyanpur Khal	Right	22°25'52.70"N	88° 2'4.21"E
		Kansona	0.06 from kharia Moyanpur Khal	Right	22°25'50.26"N	88° 2'32.80"E
		Mayanapur	0.50 from Sasaberia Khal	Right	22°26'22.04"N	88° 1'48.61"E
		Lalitgagari	0.95 from Sasaberia Khal	Right	22°26'22.68"N	88° 2'41.75"E
		Panchberia Barberia Balarampur	0.39 from Sasaberia Khal	Right	22°26'54.29"N	88° 2'15.09"E
		Barmouberia	0.08 from Sasaberia Khal	Right	22°27'15.72"N	88° 2'6.32"E
		Uttar Ramchandrapur	0.88 from Sasaberia Khal	Right	22°27'26.96"N	88° 2'32.84"E
		Jayrampur	1.12 from Sasaberia Khal	Right	22°26'53.82"N	88° 1'4.75"E
		Prasadpur	0.63 from kultipara khal	Right	22°26'58.61"N	88° 0'33.87"E
		Janbar	0.76 from mahadevpur	Right	22°27'46.65"N	88° 0'11.59"E
	Sensitive Receptors	Janoai	0.70 Hom manade vpur	Right	22 27 40.05 11	00 011.37 E
	· · ·	D C 11	1266 M 1 1	T C	00007107 4 4UNI	07050116 25115
	School	Bagnan College	1.36 from Mahadevpur	Left	22°27'27.44"N	87°58'16.35"E
	Hospital					
	Drinking water sources					
	Utility lines like electricity					
	lines, pipelines for gas, etc					
	Physical cultural					
	resources – ,					
	Protected monuments	Not Available	Not Available	Not	Not Available	Not Available
	Historical sites, etc.	Not Available	Not Available	Available Not	Not Available	Not Available
				Available		
	Physical cultural					
	<u>resources –</u>					
	Mandir	Uttar Benapur Soni Mandir	3.4 from Nupurkhal	Left	22°24'22.03"N	87°57'17.00"E
	Masque					
	Burning Ghat				1	
	Bedi	l	1	1	1	
		ł	+	ł	+	
	Agricultural land	NT / A 11 1 1	NT / A 1111	NT /	NT / A 11 1 1	NT / A 11 1 1
	Defence Installations /	Not Available	Not Available	Not	Not Available	Not Available
	Airports			Available		
	National highway	Not Available	Not Available	Not Available	Not Available	Not Available
	State highway / Roads	Bagnan Road Boaliya Road	2.34 from kultipara khal 0.49 from Godakhali	Left Right	22.44 22.415	87.973 88.045
	Heavy polluting Industry	Not Available	khal Not Available	Not	Not Available	Not Available
				Available		
	Water or Waste water Treatment Plant	Not Available	Not Available	Not Available	Not Available	Not Available



Annexure- 10: Environmental & Social features within 500m, 3km and 10 Km. periphery

Type of	Utility / Structure	Within 50	0 m radius	of Mundesv	vari River	Within	3 Km radius o	ri River	Within 10 Km. radius of Mundeswari River				
Structure	•	Left / Right	Distance	Lat	Long	Left / Right	Distance	Lat	Long	Left / Right	Distance	Lat	Long
Masque	Jasar Majid					Left	1.01	22.800321	87.911037				
Temple	Shiv Temple					Left	2.01	22.807356	87.896796				
Post Office	Ragpur Post Office					Left	1	22.812442	87.896669				
Sangha	Sri Ramkrishna Sarada					Left	930 Meter	22.828094	87.897401				
	Vivekanada Sangha												
Temple	Gobra Kali Mandir					Left	1.81		87.897137				
Temple	Khanachandi Maa Mandir					Left	2.36	22.815336	87.872579				
Masque	Masque	Left	111.56 m	22.836077	87.902838								
Bank	State Bank of india, Harinkhola Branch	Left	366.3 m	22.836639	87.899519								
Temple	Damodar temple					Left	1.66	22.830599	87.894976				
Temple	Kali Mandir					Left	1.15	22.83513	87.88903				
Bank	State Bank of india, Kable Branch					Left	2.6	22.840014	87.875816				
Masque	Shyamgram Jannatul					Left	1.02	22.844762	87.88931				
Temple	Ramkrishna Matha Siriti					Left	2.61	22.856299	87.868851				
Temple	Durga Temple	Left	282.8 m	22.860471	87.893327								
Post Office	Purbakrishna Post Office	Right	104.22 m	22.856851	87.897067								
Railway Station	Mayapur Railway Station					Left	2.47	22.868355	87.867678				
Post Office	Madhurpur Post Office					Left	736.31 Meter	22.86776	87.885129				
School	Madhurpur high School					Left	645.45 Meter	22.867847	87.8858				
Temple	Barabainan Kali Mandir					Left	980.82 m	22.992953	87.935991				
Temple	Singerpur Mahadev Temple	Left	146.96 m	22.985896	87.941458								
Bank	Bandhan Bank					Left	2.5	22.992368	87.920037				
Bank	State bank of India Bataspur Branch					Left	2.97	22.977435	87.911704				
Temple	Maa Mangala Chandi Mandir					Left	2.69	22.972894	87.914799				

Environmental features within 500m, 3km and 10 km. buffer area of Mundeswari river

Type of	Utility / Structure			of Mundesv	vari River		3 Km radius o	f Mundeswa	ri River	Within 10 K		of Mundes	wari River
Structure		Left / Right		Lat	Long	Left / Right	Distance	Lat	Long	Left / Right	Distance	Lat	Long
Masque	Narasinghapur Jame Majisd	Left	205.83 m	22.984083	87.940969								
School	Aacharya Sukumar Sen Mahavidyalaya Gotan					Left	1.82	22.969107	87.922322				
Masque	Gotan Bazar Jame Masjid					Left	2.46	22.969170,	87.916394				
Post Office	Gotan Post office					Left	2.1	22.96494	87.918931				
Temple	Pataleswar Temple					Left	2.61	22.963511	87.9135				
Temple	Gotan purbapalli sarbojonin durga mandir					Left	2.04	22.962479	87.918894				
Temple	Gotan Kali Mandir					Left	2.62	22.958588,	87.91243				
Temple	Haldipur Maa Kali Temple	Left	33.55 m	22.96751	87.939583								
Market Place	Daminya (k.k.) Market					Left	2.11	22.942163	87.911199				
Bank	Paschis Gramin Bank					Left	797.42 m	22.928373	87.915459				
Temple	Malaypur Bagmara Kali Temple					Left	2.27	22.917946	87.89507				
Temple	Maa Durga Mandir					Left	1.69	22.911505	87.897073				
Market Place	Malayour Bazar					Left	762.2 m	22.906008	87.904196				
Bank	Paschim Banga Gramin Bank					Left	860.03 m	22.902573	87.902357				
Masque	Chakbenshia masjid					Left	274.27 m	22.905533	87.909043				
GP office	Moloypur-II Gram Panchayat					Left	1.18	22.890154	87.89347				
Temple	Maa Kali Mandir					Left	680.05 m	22.888978	87.899				
Temple	Keshabpur Majumdar Barir Mandir					Left	736.24 m	22.891942	87.89839				
Post office	Sonargora Post Office					Right	836.11 m	23.002156	87.968022				
Temple	Muidipur Kali Mandir						772.98 m	22.993236	87.960438				
Temple	Par Ujir Pur Kali Mandir					Right	1.47	23.002488	87.946849				
Post Office	Amarpur Branch Post Office					Right	2.34	22.980207	87.973581				
Mosque	Mathsheali Jame Masjid	Right	257.21 m										
Temple	Temple					Right	2.64	22.936543	87.968134				
Temple	Soaluk Radha Gopinath Temple					Right	2.79	22.926131	87.959555				

Type of	Utility / Structure	Within 500	Within 500 m radius of Mundeswari RiverLeft / RightDistanceLatLong			Within 3	3 Km radius o	f Mundeswa	ri River	Within 10 Km. radius of Mundeswari River				
Structure		Left / Right	Distance	Lat	Long	Left / Right	Distance	Lat	Long	Left / Right	Distance	Lat	Long	
Mosque	Mosque					Right	1.94	22.918749	87.945648					
Mosque	Kelepara Notun Masjid					Right	2.46	22.915336	87.947106					
Temple	Dulalbati Tarun Sangha Durga Mandir					Right	1.13	22.911923	87.933503					
Bank	Canara Bank					Right	1.34	22.895434	87.930134					
Temple	Kali Mandir					Right	1.17	22.888899	87.925695					
Temple	Mandal Para Kali Temple					Right	2.89	22.879586,	87.93835					
Electical Substation	Panchanan Tala Electrical Substation					Right	2.66	22.894359,	87.942537					
Playground	Football Play ground									Right	3.22	22.837304	87.93868	
Bank	State Bank of India Chiladangi Branch					Right	2.1	22.809834,	87.937503					
Temple	Harua Mela Tala Temple					Right	1.12	22.803617	87.931504					



Figure 1: Environmental & social features within and outside of 3 km. influence zone of Mundeswari River

Type of	Utility / Structure	Left /	Within 5	00 m radius o	f Damodar	Withi	n 3 Km. radius	of Damodar	Within 10 Km. r	adius of D	amodar
Structure		Right	Distance	Lat	Long	Distance	Lat	Long	Distance	Lat	Long
Bank	syndicate Bank	Left				2.98 km	22.535136,	87.959162			
							87.959162				
Temple	Shyambhu Shiva Mandir	Left				1.79 Km	22.540566,	87.974372			
Temple	Radha Gobindo Mandir	Left				2.77 Km	22.548323,	87.964257			
Mosque	Masjid Madrasa	Left				2.24km	22.549075,	87.968539			
Temple	Dakshinpara Kalimandir	Left				1.52 km	22.551412,	87.975823			
Post Office	Nowpara Post Office	Left	209.40 m	22.558367,	87.986909						
Bank	Paschim Banga Grameen Bank	Right	256.06 m	22.534012,	87.988998						
Mosque	Khansan Jame Masjid	Right	378.07 m	22.542390,	87.995433						
Playground	Ranapara Football ground	Right	244.13 m	22.556599,	87.99254						
Playground	Kusberya Kali Mata Playground	Left				2.39 km	22.541778,	87.96782			
Market	Sonamui Bazar	Right				1.74 km	22.536744,	88.007678			
Mosque	Karim Molla Sahed Masjid	Right				902.97	22.534947,	87.998314			
-		Ũ				km					
Mosque	Tentuliapara Mosjid	Right				2.23 km	22.533861,0	88.01084			
Temple	Sonamui Radhamadhob mandir	Right				1.08 km	22.539140,	88.002246			
Mosque	Purba Gazipur Jumma Masjid	Right				1.65 km	22.547205,	88.007781			
Park	Damodar Publick Park	Left	54.03 m	22.723106,	87.988942						
Police Station	Udaynarayanpur police station	Left				1.04 km	22.721461,	87.98037			
Hospital	Udaynarayanpur state general hospital	Left	282.64 m	22.720745,	87.988136						
Maath	Shibpur friends union club maath	Left				2.47 km	22.718254,	87.968905			
Temple	Shibpur baroaritala mandir	Left				2.30 km	22.712993,	87.972941			
School	School	Left				899.25 m					
Playground	Chakgarah jiban smriti vidya mandir	Left				1.31 km	22.699068,	87.983388			
	playground										
Temple	Rajapur sitala mata mandir	Left				1.78 km	22.699494,	87.978162			
Temple	Singti barowari kali mandir	Left				2.91 km	22.693909,	87.971945			
Bank	Singti co-operative bank	Left				3.00 km	22.691528,	87.971278			
School	kumirmorah primary school	Left				2.59 km	22.688751,	87.975315			
Post Office	Joka Post office	Left				1.16 km	22.685901,	87.984446			
Post Office	Sonagachi post office	Left	432.29 m	22.691956,	87.99629						
School	sonagachi kailash primary school	Left				531.34 m	22.691834,	87.995403			1
Playground	North paliarah playground	Right	238.78 m	22.687489,	88.003209		,				
Temple	Temple	Left				2.40 km	22.671850,	87.973583			1
Libaray	Kanupat Harendra Libaray	Left				2.27 km	22.669085,	87.974465			1
Mosque	Purpat jamma masjid	Left				1.95 km	22.676296,	87.97949			1
Temple	Naranarayanchak monsa mondir	Left	406.92 m	22.672662,	87.993177						1

Environmental features within 500m, 3km and 10 Km. radius of Damodar left and Right Embankment

Type of	Utility / Structure	Left /	Within 5	00 m radius of	f Damodar	Withi	n 3 Km. radius	of Damodar	Within 10 Km. radius of Damodar			
Structure		Right	Distance	Lat	Long	Distance	Lat	Long	Distance	Lat	Long	
Temple	Jaynagar hari mandir	Left	95.11 m	22.680483,	87.998022							
Post Office	Monsuka post office	Left	37.84 m	22.666545,	87.995083							
School	High School	Left	32.65 m	22.665562,	87.996938							
Mosque	Jumma Masjid	Left				1.42 kkm	22.657055,	87.975799				
Bank	Garhbhawanipur Bandhan bank DSC	Left				2.41 km	22.656487,	87.965714				
Bank	SBI Garhbhawanipur	Left				1.79 km	22.652378,	87.966869				
Bank	Allahabad Bank	Left				1.41 km	22.647963,	87.969856				
Temple	Sonatala Kalitala	Left				2.10 km	22.648385,	87.963087				
Mosque	Sonatala Masjid	Left				2.50 km	22.645898,	87.959239				
Temple	Gosh Para Durga Mandir	Left				1.68 km	22.645954,	87.967259				
Park	Kansona park	Right	53.06 m	22.643879,	87.984285							
Post Office	Balichak Post Office	Right	374.26 m	22.645532,	87.988094							
Playground	Barda Football ground	Left	112.71 m	22.623140,	87.96943							
Playground	Saroaberia Playground	Left	419.63 m	22.620457,	87.965496							
Temple	Sitaram Mandir	Left				1.47 km	22.626070,	87.958283				
Temple	Saroaberia shanti Ashram	Left				1.23 km	22.623978,	87.959373				
Temple	Hanidhara Hori Sabha	Left				796.06 m	22.612629,	87.965641				
Temple	Ganga Debi Tola	Left	156.06 m	22.612046,	87.971899							
Mosque	Ronjoybar Jammu Masjid	Left				1.94 km	22.623086,	87.951313				
Temple	Panchannanda Tala	Left				765.66 m	22.607074,	87.967631				
Temple	Kali Mandir	Left				1.07 km	22.602378,	87.961494				
Post Office	Thalia Post Office	Left	87.01 m	22.600911,	87.970698							
Temple	Hanidhara shib mandir	Left				678.75 m	22.609706,	87.968281				
Playground	Thalia Union Club Playground	Left	390.73 m	22.597415,	87.967775							
Temple	Murlidhar Temple	Left				760.14 m	22.595589,	87.966062				
Playground	Rashpur Play ground	Right	248.25 m	22.597296,	87.974773							
School	Rashpur high School	Right	391.68 m	22.598753,	87.97568							
Park	Eco Park	Right	188.69 m	22.587755,	87.997218							
Bank	UCO Bank	Left				954.06 m	22.584476,	87.986685				
Temple	Betali Samsan Kali Mandir	Left	111.74 m	22.574274,	87.996911							
Temple	Kali Temple	Left				1.61 km	22.585902,	87.980037				
School	Khroop High School	Left				1.11 km	22.579010,	87.986079				
Playground	Kalbansh Playground	Left				2.09 km	22.579292,	87.976853				
Playground	Bargazipur Playground	Left				2.86 km	22.573348,	87.970049				
Temple	Jagolgori Kali Mandir	Left				1.15 km	22.575792,	87.986617				
Post Office	Pashpur Post Office	Right				1.24 km	22.705152,	88.00413				
Temple	Ranjanapur Shitala Monosa Matar Mandir	Right				850.38 m	22.689661,	88.009511				
Temple	Kheypteswari Mandir	Right				523.87 m	22.683926,	88.00501			1	

Type of	Utility / Structure	Left /	Within 5)0 m radius of	f Damodar	Withi	n 3 Km. radius (of Damodar	Within 10 Km. radius of Damodar			
Structure		Right	Distance	Lat	Long	Distance	Lat	Long	Distance	Lat	Long	
Temple	Allahabad Bank	Right	136.06 m	22.679471,	88.001008							
Temple	Gangamata Mandir	Right	322.54 m	22.677871,	88.00279							
Temple	Annapurna Basanti Mandir	Right				1.93 km	22.679640,	88.018524				
Post Office	Khila Post Office	Right				903.38 m	22.666709,	88.0051				
Bank	Khila Branch, Allahabad Bank	Right				587.25 m	22.672137,	88.004231				
Temple	Monsha Tala Mandir	Right				791.21 m	22.663065,	88.010386				
Temple	Durga Mandir	Right				2.25 km	22.669231,	88.018283				
Maath	Ananda Matha	Right				1.82 km	22.591811,	88.011079				
Temple	Ram Mandir	Right				1.73 km	22.588933,	88.012252				
Temple	Kali Mandir	Right				1.43 km	22.586036,	88.010645				
Panchayat	Sirajbati Panchayat Office	Right				1.42 km	22.584033,	88.010543				
Office		Ũ										
Bank	Amta Branch, SBI	Right				1.06 km	22.580546,	88.008068				
Post Office	Amta Post office	Right				502.65 m	22.579485,	88.002963				
Police Station	Amta Police station	Right	442.89 m	22.578020,	88.002101							
Collage	RamsadayCollage	Right	349.27 m	22.575546,	88.000847							
Bank	United Bank of india	Right				601.46 m	22.577690,	88.003376				
Bank	Axis Bank	Right				1.20 km	22.576819,	88.009858				
Hospital	Amta Rural Hospital	Right				1.62 km	22.575217,	88.014074				
Railway Station	Amta Station	Right				2.19 km	22.574390,	88.019427				
School	Amta Nityananda high School	Right				820.45 m	22.574249,	88.006511				
Mosque	Nutan Masjid	Right				2.80 km	22.570118,	88.026112				
Post Office	Deora Post Office	Right	52.80 m	22.564076,	87.995242							
Mosque	Deora Adi Masjid	Right	192.74 m	22.561888,	87.994625							
Temple	Nagmatha Temple	Right	273.17 m	22.558141,	87.992894							
Temple	Ranapara Baba Panchanand Tola Mandir	Right	364.58 m	22.555851,	87.993999							
Mosque	Ranapara Masjid Tala	Right	252.36 m	22.553345,	87.993383			1			1	
School	Purba Gazipur GKBR High School	Right		, , , , , , , , , , , , , , , , , , ,		624.52 m	22.546109,	87.99774			1	
Market	sonamui Bazar	Right				1.68 km	22.537237,	88.008039			1	
School	Sonamui FN High School	Right				1.57 km	22.539058,	88.006912			1	
School	Gazhipur girls high school	Left				1.65 km	22°33'53.16"N	87°58'36.16"E			1	



Figure 2: Environmental & social features within and outside of 3 km. influence zone of Damodar Left & Right Embankment

Type of Structure	Utility / Structure	Left / Right	Within 500 m radios			Within 3 Km radios			Within 10 Km radios		
			Distance	Lat	Long	Distance	Lat	Long	Distance	Lat	Long
Temple	Graharaj Mandir	Left				2.75 km	22.685198,	87.863334			
Temple	Kali Mandir	Left				2.58 km	22.678207,	87.865131			
Mosque	Jayrampur Masjid	Left				1.77 km	22.669893,	87.870603			
hospital	Natibpur Block Primary Health Center	Right	345.16 m	22.665979,	87.891689						
Post office	Natibpur post office	Right	94.32	22.665537,	87.888398						
Bank	ADB SBI Branch, Jayrampur	Left				1.75 km	22.681307,	87.872373			
Playground	Jayrampur School Play ground	Left				1.56 km	22.680797,	87.87374			
School	Natibpur Budheb Vidyalaya	Right				700.86 m	22.665412,	87.89448			
Playground	Mostafapur National Play grund	Right				1.34 km	22.667505,	87.90253			
Playground	Football Ground	Right				1.56 km	22.663319,	87.902194			
Temple	Bankaroy Mandir	Right				1.66 km	22.666523,	87.904424			
Bus Stand	Chabbishpur Bus Stand	Left				1.67 km	22.710986,	87.924198			
Playground	Playground	Left	77.25 m	22.709993,	87.940354						
Math	Chabbishpur Math	Left	119.10 m	22.691505,	87.920669						
Market	Chabbishpur Market	Left	76.28 m	22.690189,	87.920209						
Temple	Jugikundu Maa Monosa Mandir	Left				1.89 km	22.690512,	87.903335			
Temple	Kali Temple	Left				2.89 km	22.689708,	87.906204			
Temple	Pirtala	Right				502.80 m	22.699612,	87.943276			
Post office	Pancharul Post Office	Right				735.04 m	22.699235,	87.944093			
Temple	Singti Mansa Temple	Right				2.39 km	22.693671,	87.961523			
Temple	shibpour Shitala Mata	Right				2.39 km	22.708577,	87.963366			
Bank	Singti Co-operative bank	Right				2.63 km	22.691407,	87.970877			
Temple	Seetala maa mandir	Right				2.48 km	22.708624,	87.963468			
Temple	Gaza Ramrajatala	Right				2.23 km	22.719887,	87.964342			
Police Station	Udaynarayanpur police Station	Right				3.78 km	22.721417,	87.980404			
Park	Damodar Public Park	Right							4.71 km	22.723476,	87.98856
Playground	Boropara Playground	Right				1.73 km	22.730148,	87.961702			
Temple	Modan Mohan Mandir	Right				1.75 km	22.734432,	87.965088			
Temple	Kali mandir	Right				3.62 km	22.733616,	87.984292			
Temple	Loknath Temple	Right			T	1.55 km	22.739333,	87.964268		1	
Temple	Khempur Shitala Mandir	Right				2.40 km	22.743958,	87.973602			
Post office	Nimdangi Post Office					1.34 km	22.854068,	87.934026			
Bank	SBI, Pursurah branch					1.44 km	22.842747,	87.927858			
Temple	Mahaprabhu Mandir	Right	234.49 m	22.851687,	87.948155		Í				
Office	Pursura BDO Office	Right				1.22 km	22.842162,	87.954068			
Temple	Temple	Left	186.91 m	22.851789,	87.943152		Í				
Post office	Muktarpur Post office	Right		Í		3.00km	22.846876,	87.97604			1

Environmental features within 500m, 3km and 10 Km. Radius of Upper Rampur Khal

Type of	Utility / Structure	Left / Right	Within 500 m radios			Within 3 Km radios			Within 10 Km radios		
Structure			Distance	Lat	Long	Distance	Lat	Long	Distance	Lat	Long
Temple	Durga Mandir	Right				2.30 km	22.853582,	87.969399			
Police Station	Pursurah Police Station	Right				2.52 km	22.838034,	87.965917			
Hospital	Pursuraha PHC	Right	10.28 m	22.825256,	87.954478						
Temple	Vishnu Mandir	Right	11.26 m	22.808056,	87.956271						
Temple	Kali Temple	Right	9.26 m	22.806108,	87.956002						
Post office	Binagram Post office	Right				1.26 km	22.813790,	87.970291			
Temple	Gopinath Mandir	Right				1.22 km	22.815976,	87.969973			
Temple	Dhormo Mandir	Right				1.02 km	22.818600,	87.97182			
Temple	RadhaKrishna Mandir	Left	360.73 m	22.807522,	87.953003						
Temple	Dakshin Kali mandir	Left				1.25 km	22.805675,	87.943411			
Bank	Chiladangi Branchi, SBI	Left				1.87 km	22.808737,				
Mosque	Fatepur jama Moseque	Left				645.87 m	22.797705,	87.967286			



Figure 3: Environmental & social features within and outside of 3 km. influence zone of Upper Rampur Left Embankment

Type of	Utility / Structure	Left / Right	With	in 500 m radios	;	Within	3 Km. radios		Within 10 K	m. rad	ios
Structure		-	Distance	Lat	Long	Distance	Lat	Long	Distance	Lat	Long
Bank	State bank of india, Joyrampur	Left				1.82	22.681665,	87.87282			
	ADB Branch										
Temple	Sitapur Samsan kali Mandir	Left				2.62	22.678296,	87.86491			
Mosque	Jayrmapur Jama Majisd	Left				1.68	22.670211,	87.86989			
Post Office	Natibpur Post office	Left				843.46 m	22.665331,	87.8884			
Mosque	Par Harishchak Masjid	Left				419.43 m	22.659083,	87.87933			
Temple	Ma Jagatguri Temple	Left				554.26 m	22.656128,	87.86937			
Hospital	Natibpur Primary Health Center	Left				485.5 m	22.666169,	87.8919			
Temple	Thakuranichak baroari kali mandir	Right				1.51	22.668920,	87.91062			
Temple	Bankaroy mandir	Right				706.21 m	22.666869,	87.90515			
Playground	Footbal Play Ground	Right				1.62	22.663373,	87.90261			
School	Mostafapur Gandhi high School	Right	103.36 m	22.658481,	87.90203						
Post Office	Balpai Post Office	Left	224.23 m	22.654384,	87.89903						
Temple	Balpai Ghosh bari durga puja	Left	445.76 m	22.648654,	87.89929						
Library	Balpai daulatchalk Sadharan	Left				853.09 m	22.645886,	87.89597			
-	Pathagar										
Temple	Balapi kali mandir	Left				1.22	22.646391,	87.89236			
School	Harishchak KHD Prathmick	Left				2.03	22.651454, 8				
	Bidayalaya										
School	Harishchak high school	Left					22.650620,	87.87503			
Temple	Harishchak Ganga Mandir	Left				2.95	22.644824,	87.87525			
Mosque	Khunachak Jama Masjid	Left				1.37	22.642384,	87.89654			
Temple	Narendrapur Shitala Mansha	Left				1.04	22.637621,	87.89344			
-	Mandir										
Bank	Marokhana Samity Bank	Left				2.05	22.612100,	87.85183			
Post Office	Marokhana Post Office	Left				1.98	22.612100,	87.85183			
School	Uttar Bhatora high school	Left				758.36 m	22.596876,	87.85999			
Playground	Gongatola Ball Ground	Left				1.46	22.597147,	87.85342			
Playground	Kaijuri Play ground	Left				1.85	22.597039,	87.85043			
Temple	Uttar Bhatora Boro Baba Mandir	Left					22.595612,	87.85414			
Temple	Mansa mandir	Left				1.22	22.593578,	87.85591			
Temple	Meta Para Kali Mandir	Left			1	949.86 m	22.580999,	87.85595			
Panchayet	Bhatora Gram Panchayat	Left				749.62 m	22.579636,	87.85825			
Temple	Maa Kali Temple	Left				929.5 m	22.563555,	87.85819			
Post Office	Bhatora Post office	Left					22.562893,	87.85538			
Mosque	Mosque	Left				700.34 m	22.562189,	87.86262			
Park	Beral Park, GBC	Left				574.05 m	22.554951,	87.86724			

Environmetal Features within 500m, 3 Km. and 10 Km. Radius of Hurhura Khal

Type of	Utility / Structure	Left / Right			Within 10 Kn	1. radi	os				
Structure			Distance	Lat	Long	Distance	Lat	Long	Distance	Lat	Long
Mosque	Ajangachi Panjatania Jame Masjid	Right	474.11 m	22.544090,	87.8871						
Bank	SBI mini bank	Right	190.11 m	22.544042,	87.88424						
Post Office	Kashmoli Post Office	Right				1.18	22.560335, 87	7.882238			
Temple	Solbaga Shibtala	Right				1.32	22.591491,	87.88083			
Temple	Mansa mandir	Right				1.14	22.611395,	87.88543			
Temple	Kalipada Janas Mandir	Right				2.35	22.614983,	87.89899			
Temple	Chaksalika Setola Mata Mandir	Right				3	22.611319,	87.90308			
Temple	Hayatpur Utturpara Mansha Mandir	Right	391.38 m	22.629464,	87.88511						
Bank	Paschimbamga Gramin Bank, Palaspai Branch	Right	458.5 m	22.633220,	87.90392						
Temple	Trikona Kali mandir	Right	364.63 m	22.639980,	87.90987						
Playground	Boyalia Paschim Para Play ground	Right				2.53	22.63187	87.92834			
School	Boyalia Board primay school	Right				2.82	22.630611,	87.93051			
Playground	Mostafapur Dakshinpara Playground	Right	347.95 m	22.646436,	87.90815						



Figure 4: Environmental & social features within and outside of 3 km. influence zone of Hurhura Left Embankment

Type of Structure	Utility / Structure	Left / Right	Wit	hin 500 m radio)S	Withi	n 3 Km. radios		Within	10 Km. rad	ios
		0	Distance	Lat	Long	Distance	Lat	Long	Distance	Lat	Long
School	Bainan Girl's High School	Right				1.15 Km from Bankura Khal	22°30'7.12"N	87°56'54.16"E			
School	Bainan Baman Das High School (H.S)	Right				0.60 Km from Bakura Khal	22°30'27.07"N	87°56'56.29"E			
School	Joypur Panchanan Roy College	Right				0.68 from sabgachtla khal	22°36'19.86"N	87°56'20.06"E			
Mosque	Hajrat Buropir Saheb Majar Sanglagna	Left	0.50 km from Birampur khal	22°30'11.19"N	87°54'56.34"E						
Mosque	Masjid Baitullah	Left	0.29 km from sabgachtla khal	22°36'10.45"N	87°55'15.61"E						
Mosque	Masjid a Alamin	Right				2.5 Km from Birampur Khal	22°29'51.09"N	87°56'49.05"E			
School	Bagnan College	Left				1.36 from Mahadevpur	22°27'27.44"N	87°58'16.35"E			
Temple	Uttar Benapur Soni Mandir	Left				3.4 from Nupurkhal	22°24'22.03"N	7°57'17.00"E			
Temple	Shitola Mandir	Right				2.68 Km from Ghoraberia Khal	22.602	87.846			
Temple	Kali Mandir	Right				2.38 Km from Ghoraberia Khal	22.6	87.848			
Playground	Kaijuri Play Ground	Right				2.10 Km from Ghoraberia Khal	22.598	87.85			
Temple	Mansa Mandir	Right				1.60 Km from Ghoraberia Khal	22.594	87.855			
Temple	Solbag Shibtala	Right				1.470 Km from Maja Damodar Khal	22.593	87.88			
Temple	Meta Para Kali Mandir	Right	0.300 km from Ghoraberia Khal	22.582	87.855						
Temple	Gurdha Monosa Mandir	Right				0.600 km from Ghoraberia Khal	22.584	87.852			
Post Office	Bhatora Post Office	Left	0.187 km from Kulia Khal	22.564	87.855						
Bank	Axis Bank	Left				1.4 km from Kulia Khal	22.562	87.842			
Bank	SbI	Left				1.64 km from Kulia Khal	22.559	87.839			

Environmental features within 500m, 3km and 10 km. radius of 41 drainage canal proposed for desiltation

Type of Structure	Utility / Structure	Left / Right	With	in 500 m radios		Withi	n 3 Km. radios		Within	10 Km. rad	lios
		U	Distance	Lat	Long	Distance	Lat	Long	Distance	Lat	Long
Temple	Shiv & Sitola Mandir	Left			X	2.4 km from Kulia Khal	22.554	87.829			
Post Office	Kashmoli Post Office	Left	0.109 km from Khorigeria Khal	22.562	87.883						
Park	Beral Park GBC	Left	0.385 km from Chitnantalipara Khal	22.556	87.867						
Temple	Sitola Mandir, Uttar Durgapur Temple	Left				1.83 km from Boalia Khal	22.374	88.041			
Post Office	Uttardurgapur Post office	Left				1.83 km from Boalia Khal	22.373	88.044			
Playground	Durgapur Football ground	Left				2.23 km from Boalia Khal	22.37	88.05			
Post Office	Post Office	Left				1.65 km from Boalia Khal	22.378	88.057			
Market	Ichhapur Market	Left				3.00 km from Boalia Khal	22.371	88.069			
Temple	Radhe Krishna Mandir	Left				3.00 km from Boalia Khal	22.378	88.074			
Mosque	Bhekutal Jame	Left				2.55 km from Boalia Khal	22.389	88.072			
Temple	Dahuka Shri Shri Babu Panchanan Mandir	Left	99 m from godakhali khal	22.411							
Temple	Boalia kali Mandir	Left	200 m from Boalia Khal	22.397	88.045						
Bank	Paschim Banga Gramin Bank	Left	62 m from Boalia Khal	22.398	88.047						
School	Barberia Board Primary School	Left				686 m from Boalia Khal	22.406	88.048			
Math	Bottolar Math	Left	310.88 m from Boalia Khal	22.406	88.052						
Playground	Samruk school field	Left	284.91 m from Boalia Khal	22.41	88.054						
Mosque	Gumukberia	Right				2.12 Km from Boalia Khal	22.412907,	88.074453			
Temple	Sundorpur Ponchonndo Mandir	Right				1.139 km from Boalia Khal	22.399	88.064			
Mosque	Rabeya Jame Masjid	Left				2.92 km from Nalpukhur khal	22.381	88.008			

Type of Structure	Utility / Structure	Left / Right	Witl	hin 500 m radios	i	Within	3 Km. radios		Within	10 Km. rad	lios
		Ũ	Distance	Lat	Long	Distance	Lat	Long	Distance	Lat	Long
Mosque	Kulanandapur Jame	Left				2.88 km from	22.382	88.004			
	Masjid					Nalpukhur Khal					
Market	Bhatughar Market	Left				2.4 km from Nalpukhur Khal	22.385	88.01			
School	Naoda High School	Left				1.4 km from Nalpukhur Khal	22.393	88.019			
Temple	Narayan Mandir	Left				2.06 km from Nalpukhur Khal	22.387	88.029			
Bank	SBI Sitapur Branch	Left				1.6 km from Nalpukhur Khal	22.393	88.03			
Market	Dagra Baro Bazar	Left				1.24 km from Nalpukhur Khal	22.397	88.024			
Mosque	Kazipara	Right				581 m from Rabibhag khal	22.436	88.02			
Mosque	Mosque	Right				638.24 m from Rabibhag Juma	22.435	88.02			
Mosque	Majher para Juma	Right				621.27 m from Rabibhag Khal	22.433	88.019			
Mosque	Rabibhag Juma	Right				680.08 m from Rabibhag Juma	22.43	88.019			
Post Office	Rabibhag Post office	Left	497.99 m from Rabibhag Khal	22.428	88.01						
Temple	Sabitri Temple	Left				1.29 km from Tetua Khal	22.432	87.981			
Temple	Burimar Temple	Left				1.03 km from Tetua Khal	22.432	87.986			
Mosque	Amuria Jam-e-Masjid	Left				1.35 km from Tetua Khal	22.435	87.99			
Temple	Durga Mandir	Left				1.04 km from Tetua Khal	22.422	87.98			
Post Office	Rupasgori Post Office	Right	298.47 m from Tetua Khal	22.425	88.003						
Mosque	Mondal Para Jumma Maszid	Left	306.86 m from Kultipara Khal	22.442	87.995						
Mosque	Gohalberiya Jumma Masjid	Left				594.21 m from Kultipara Khal	22.441	87.987			
School	Santoshpur shree gouranga vidyapith	Left	105.61 m from kultipara khal	22.445	87.99						

Type of Structure	Utility / Structure	Left / Right	With	nin 500 m radios		With	in 3 Km. radios		Within	10 Km. rad	lios
		0	Distance	Lat	Long	Distance	Lat	Long	Distance	Lat	Long
Mosque	Santoshpur MD. Para jame mosjid	U	461.81 m from Kultipara Khal	22.449	87.989						
School	Al ameen mission school	Right				649.09 m from kultipara khal	22.449	87.985			
Office	Bagnan-II Bdo office howrah	Left				510.97 m from santoshpur khal	22.446	87.976			
Bank	Bank of Baroda, Antila Branch	Left				968.66 m from santoshpur khal	22.442	87.974			
Temple	Bishnu Mandir	Right	294.13 m from santoshpur khal	22.453	87.972						
Temple	Maa Jagashatri Temple	Right	184.7 m from santoshpur khal	22.453	87.977						
Mosque	Pak Panjata	Right				733.33 m from santoshpur khal	22.457	87.981			
College	Bagnan College	Right				805.86 m from santoshpur khal	22.458	87.971			
Temple	Kolepara Shiv Mandir	Left	123.53 m from santoshpur khal	22.449	87.975						
Temple	Srikrishnapur shib mandir	Right				1.05 km from santoshpur khal	22.459	88.012			
Temple	Shiv mandir	Right				690.15 m from santoshpur khal	22.46	88.006			
Playground	Majherchara Playground	Right	174.52 m from gopalpur khal	22.48	87.96						
Temple	Temple	Right	325.36 m from gopalpur khal	22.478	87.957						
Temple	Maa Jagashatri Temple	Right				739.9 m from gopalpur khal	22.476	87.968			
Mosque	Masjid	Right				792.2 m from gopalpur khal	22.479	87.971			
Mosque	Khadhinam uttor para zamo maszid	Right				990.9 m from gopalpur khal	22.478	87.973			
Temple	Kali Mandir	Right				1.6 km from gopalpur khal	22.481	87.98			
Playground	Playground	Right				2.04 km from gopalpur khal	22.48	87.984			
Mosque	Mosque	Right				1.7 km from gopalpur khal	22.471	87.978			

Type of Structure	Utility / Structure	Left / Right		in 500 m radios		Withir	a 3 Km. radios		Within	10 Km. rad	lios
		Ũ	Distance	Lat	Long	Distance	Lat	Long	Distance	Lat	Long
Bank	SBI, Bagnan branch	C	334.23 m from mellok main khal	22.467	87.961						
Mosque	Bagnan masjid	Right	437.3 m from mellok main khal	22.464	87.959						
Police Station	Bagnan police station	Right				1.01 km from mellok main khal	22.468	87.967			
Hospital	Bagnan rural hospital	Right				729.7 m from mellok mainkhal	22.467	87.964			
Post Office	Bagnan sub post office	Right				1.33 km from mellok main khal	22.465	87.97			
School	Bagnan girls high school	Right				1.48 km from mellok main khal	22.465	87.971			
Railway station	Bagnan Railway station	Right									
Mosque	Mahadebpur imambara	Right				512.36 m from mahadevpur khal	22.466	87.982			
Temple	Chandrapur hari mandir	Right				779.87 m from mahadevpur	22.469	87.993			
Mosque	Jame Masjid Purana	Right				1.83 km from mahadevpur khal	22.479	87.994			
Temple	Temple	Right				1.16 km from gaighata khal	22.557	87.933			
Bank	Bank of Baroda	Right				883.8 m from gaighata khal	22.554	87.933			
Temple	Temple	Left	438.2 m from gaighata khal	22.543	87.931						
Bank	Syndicate Bank	Right				1.02 km from gaighata khal	22.536	87.959			
Temple	Loknath mandir	Right				865.4 m from bankura khal	22.53	87.966			
Post Office	Sarada Post office	Right				943.4 m from bankura khal	22.532	87.967			
Bank	Paschim banga grameen bank	Right				3.00 km from bankura khal	22.532	87.989			
Mosque	Mosque	Right				2.81 km from mahisamori khal	22.529	88.004			
Post Office	Gazipur sub post office	Right				1.78 km from mahisamori khal	22.566	87.9777			

Type of Structure		Left / Right		in 500 m radios	5	Within 3 Km. radios			Within	10 Km. rad	lios
		0	Distance	Lat	Long	Distance	Lat	Long	Distance	Lat	Long
Temple	Dhormo mandir	Right				2.08 km from mahisamori khal	22.567	87.981			
Post Office	Deora post office	Right				2.77 km from mahisamori khal	22.565	87.995			
Market	nowpara bazar	Right				1.5 km from mahisamori khal	22.561	87.983			
Playground	Ranapara football ground	Right				2.1 km from mahisamori khal	22.558	87.993			
Temple	Sashanasway kali mata temple	Right				1.5 km from mahisamori khal	22.551	87.993			
Temple	Shiv mandir	Left				1.59km from mahisamori khal	22.542	88.008			
Temple	Kali Mandir, kali tota	Left				910.10 m from mahisamori khal	22.539	87.998			
Temple	Shyambhu shiva mandir	Left				881.33 m from mahishamuri khal	22.542	87.974			
Mosque	Masjid madrasa	Right	12.5 m from mahisamori khal	22.551	87.968						
Temple	shir Kalimata mandir	Left	322.78 m from gopalpur khal	22.485	87.955						
Bank	Paschim banga gramin bank	Left				605.6 m from gopalpur khal	22.488	87.953			
School	Khajutty Jr. High girls madrash	Left				682.8 m from gopalpur khal	22.486	87.948			
Mosque	Mosque	Left				569.9 m from gopalpur khal	22.488	87.954			
Temple	Shri shri maharja mandir	Right									
Bank	Allahabad bank bakshirhat branch	Right				1.16 km from mankur khal	22.529	87.892			
Bank	SBI bakshi branch	Right				799.53 m from mankur khal	22.525	87.9			
Bank	SBI CSP bholsar	Right				995.06 m from mankur khal	22.525	87.915			
Temple	Mansa Mandir	Right				1.97 km from mankur khal	22.536	87.913			
Mosque	Bholsar gulma para masjid	Right				1.21 km from mankur khal	22.526	87.917			
Temple	Gopal mandir	Left				574.23 m from birarampur khal	22.512	87.922			

Type of Structure	Utility / Structure	Left / Right		in 500 m radios		Within	3 Km. radios		Within	10 Km. rad	lios
		0	Distance	Lat	Long	Distance	Lat	Long	Distance	Lat	Long
Temple	Kali mandir	Left	352.5 m from birarampur khal	22.51	87.923						
Post office	Chakur Post office	Left				690.08 m from birrampur khal	22.51	87.92			
Temple	shitola maa mandir	Left				831.2 m from birampur khal	22.512	87.919			
Mosque	Hajrat saheb masjid	Left				1.49 km from birampur khal	22.506	87.912			
Temple	Shiv temple	Left				1.98 km from birrampur khal	22.5	87.899			
Post Office	Subsit post office	Right				1.55 km from birrampur khal	22.492	87.932			
Market	Bainari Bazar	Right				1.31 km from birampur khal	22.506	87.944			
Temple	Koria Durga Mandir	Right	296.38 m from birampur khal	22.519	87.949						
Mosque	Karia Mallick Mosque	Right	261.4 m from birampur khal	22.517	87.95						
Temple	Sital chak kali matamilan manidir	Right				702 m from birampur khal	22.525	87.964			
Temple	Bandhgol sawsan kali mandir	Left				2.08 km from sabgaohtala khal	22.607	87.904			
Temple	Vimtola kali mandir	Left				2.68 km from sabgaohtala khal	22.61	87.899			
Temple	Chaksalika setola mata mandir	Left				2.4 km from sabgaohtala khal	22.612	87.903			
Library	Amoragori library	Left				841.15 m from sabgaohtala khal	22.608	87.92			
Mosque	Masjid baitullah	Left	396.69 m from sabgaohtala khal	22.604	87.921						
Mosque	Amoragori Rahamanlya Masjid	Left				988.14 m from sabgaohtala khal	22.61	87.926			
Bank	Indian overseas bank joypur branch	Left	418.32 m from sabgaohtala khal	22.606	87.936	-					
Police Station	Joypur police station	Left				619.18 m from sabgaohtala khal	22.607	87.938			
Bank	joypur co-operative bank	Right				791.9 m from sabgaohtala kahl	22.597	87.931			

Type of Structure	Utility / Structure	Left / Right	With	nin 500 m radio	s	Within 3 Km. radios			Within	10 Km. rad	lios
			Distance	Lat	Long	Distance	Lat	Long	Distance	Lat	Long
Temple	Shiv mandir	Right				548.8 m from sabgaohtala khal	22.583	87.933			
Temple	Kali mandir	Right				3 km from sabgaohtala khal	22.603	87.962			
Temple	Durga Mandir	Right				2.98 km from sabgaohtala khal	22.594	87.958			
Playground	Indian union club playground	Right							4.56 km from sabgaohtala khal	22.598	87.967
Playground	Mollarchak play ground	Right							5.43 km from mahisamori khal	22.531468	88.043198
Playground	Garchumuk sports ground	Right							3.45 km from boalia khai	22.357	88.059
Playground	Bacchri football ground	Right							6.69 km from boaila khal	22.343	88.005
Playground	Saira play ground	Left							7.28 km from nalpukhur khal	22.368	87.928

Annexure- 11: Map showing habitations, facilities and CPR having potential of impact

Annexure- 12: Block wise sampling villages where field study was carried out

Name of District	Name of Block	Name of the Panchayat	Name of the Village
Bankura	Bargora	Kharari	Kendra Bedia
Bankura	Patrasayer	Patrasayer	Bagan Para
Bankura	Patrasayer	Patrasayer	Patrasayer
East Burdwan	Galsi-I	Putna Pursa	Khuraj
East Burdwan	Burdwan-I	Belkash-I	Kaligrame
East Burdwan	Burdwan-I	Belkash-I	Matiyal
East Burdwan	Jamalpur	Jarugrame	Mahisgaria
East Burdwan	Jamalpur	Jarugrame	Tilkora
East Burdwan	Memari-I	Amodpur	Bizara
East Burdwan	Memari-I	Nimo-I	Sahapur
East Burdwan	Raina-4	Shamsundar	Shajpur
East Burdwan	katwa-1	saragram	saragram
East Burdwan	Raina-1	Samsundar	Samsundar
East Burdwan	Raina-1	Shamsundar	Gopinathpur
East Burdwan	Raina-1	Shamsundar	Shajpur
East Burdwan	Bhater	Mahata	Bosatpur
East Burdwan	Bhater	Mahachanda	Parhat
East Burdwan	katwa-1	saragram	Jamra
West Burdwan	Kanksa	Molandighi	Malandighi
West Burdwan	Kanksa	Molandighi	Kuldiha
Howrah	Domjur	Uttar Jhapordha	Mahish Nala
Howrah	Domjur	Uttar Jhapordha	Nonakundu
Howrah	AMTA-1	Balichak	Sarpai
Howrah	AMTA-1	Balichak	Sahachake
Howrah	Basgnan-2	Bbpur	Khajadapur
Howrah	Basgnan-2	Bbpur	Baidyanathpur
Howrah	Uluberia-M	Uluberia	Word-32
Howrah	Uluberia-M	Uluberia	Word-25
Howrah	Amta	Balichak GP	Sahachak
Howrah	Shyampur	Shyampur	Shyampur
Howrah	Shyampur	Shyampur	Alpin
Howrah	ULUBERIA _2	Banibon	Bindhabon Pur
Howrah	ULUBERIA _2	Banibon	Rajapur
Howrah	Udaynarayanpur	Pancharul	Kankari
Howrah	UPAYNARAYANPUR	PANCHRAUL	PANCHRAUL
Hooghly	Singur	Singur-II	Athalia
Hooghly	Singur	Singur-II	Ratanpur
Hooghly	Dhaniakhali	Shomospur II	Hajipur
Hooghly	Dhaniakhali	Shomospur II	Kashipur
Hooghly	Khanakul I	Ghoshpur	Kulat
Hooghly	Khanakul I	Ghoshpur	Kulgachiya
Hooghly	Pandua	Shikira Champta	Shikira
Hooghly	Pandua	Shikira Champta	Abira

Name of District	Name of Block	Name of the Panchayat	Name of the Village
Hooghly	Pulbadedpur	Goswami Malipara	Sinet
Hooghly	Pulbadedpur	Goswami Malipara	Talchini
Hooghly	Pursura	Chilidangi	Fatepur
Hooghly	Pursurah	Srirampur	Dhapdhara
Hooghly	Khanakul-II	Jagatpur	Jagatpur
Hooghly	Khanakul-II	Jagatpur	Nandanpur
Hooghly	Tarkeswar	Tarkeswar	Word No-6
Hooghly	Tarkeswar	Tarkeswar	Word No-14

Annexure- 13: Stake-holder consultation







District: Bankura Block: Patrasayer Gram Panchayat: Patrasayer Village: Patrasayer







District: East Burdwan Blocks: (1) Katwa, (2) Bhatar, (3) Raina, (4) Memari, (5) Jamalpur, (6) Burdwan, (7) Galsi



District: Howrah Blocks: (1) Shyampur, (2) Domjur, (3) Bagnan, (4) Uluberia, (5) Uluberia-Municipality, (6) Amta, (7) Udaynarayanpur



Figure 1: Consultation with Line Departments (Fishery, Agriculture, Agri-marketing, Horticulture & WRIDD



Figure 2: Stakeholder consultation on Feasibility study at Bardhaman District



Figure 3: Consultation at Chapadanga Irrigation Division



Figure 4: Community consultation at Buguahana, Burdwan



Figure 5: Community Consultation near River Lift pump house at Dihivursut, Howrah



Figure 6: Consultation with farmers on Damodar Right embankment near Muslim para of Dihivursut, Howrah

Annexure- 14: Letter from Dept. of Environment on Non-requirement of Environment Clearance (EC)

নীরজ সিঙ্ঘল, আই এফ এস মুখ্য পরিবেশ আধিকারিক পরিবেশ বিভাগ পশ্চিমবঙ্গ সরকার প্রাণীসম্পদ ভবন, ৬ষ্ঠ তল, ব্লক : এল বি-২ সেইর - ৩, সন্টলেক, কলকাতা - ৭০০ ১০৬ টেলিফাক্স : (০০৩) ২৩৩৫-৫২৪৬



NIRAJ SINGHAL, IFS

Chief Environment Officer Environment Department Government of West Bengal Pranisampad Bhaban, 5th Floor, Block - LB-2 Sector - III, Salt Lake, Kolkata - 700 106 Tele Fax : 033-2335-5246

E-mail : environmentwb@gmail.com

No. 3161 / EN / O - 44 / 2018

Date:

September, 2018

19th

To

The Additional Chief Secretary, Irrigation & Waterways Department, Jalasampad Bhaban, 3rd Floor, Western Block, Bidhannagar, Salt Inke City, Kolkata – 700 091.

Sir,

This has reference to your letter No. 442- IFC/ JW/P/IFC/4M-06/2018 dated 12/09/2018 whereby it was requested to confirm exemption of Environmental Clearance (EC) for the proposed project 'West Bengal Major Irrigation and Flood Management Project'.

It may be observed that as per appendix - IX of MoEF&CC's Notification SO 141(E) dated 15.01.2016 'Dredging and de-silting of dams, reservoirs, weirs, barrages, river, and canals for the purpose of their maintenance, upkeep and disaster management' is exempted from requirement of EC.

As per amendment of EIA Notification vide MoEF&CC's notification S.O. 3977(E) dated 14.08.2018 – 'change in irrigation technology having environmental benefits (eg. From flood irrigation to Drip irrigation etc.) by an existing project without increase in dam height and submergence will not require EC'.

Yours sincerely, (Niraj Singhal)

Annexure-15 (a): Sediment quality report of Mundeswari River by RRI

Report on the soil samples collected from the bed of Mundeswari River

1. Introduction:

From soil samples from the river bed of the Mundeswari at four sites were collected and sent to QCL, River Research Institute, Mohanpur by Hooghly Irrigation Division, I&W Dte, WB. The samples were sent to laboratory for determining their quality in respect of use at suitable place.

2. Lab Test and Result:

As these were disturbed index properties only could be done on these samples. Visual classification of all the samples sieve analysis on sand samples and Atterberg limit tests on the clay samples were conducted. Results have been presented in Table-1. The particle size distribution curves have been given in Fig-1 and Fig-2.

- 3. Discussion:
 - A. Markunda Ghat- The sample at 1 m below natural ground level (NGL) is yellowish brown fine sand. This sample contains only little mica, however fineness modulus (Criterion for use as construction material) is below 2. The samples at 2,3 and 4 meter are more or less same, yellowish gray silty clay have been very high liquid limit and plasticity index (LL-PL). The silty clays may be said heavy or fat clay. The clays are expected to show high shrink swell behaviour, but at the same time are highly impervious.
 - B. Kelepara- The samples collected from 1,2, 3 and 4 meter below NGL are more or less same, silty clay having index values (L,PI) and belong to CH group.
 - C. Chalkbelia- The samples collected from 1, 2 and 3 meter are fine to medium sand with fineness modulus expected to be not very high. The samples from 4 and 5 meter are silty clay belonging to CH group.
 - D. Deehalpara- The samples of 1,2 and 3 meter are loamy clay belonging to CI group. The samples of 4 and 5 meter depth are clayey to loamy sand.

The sands of these sites yellowish brown fine to medium sand (SP), the fineness modulus i.e. gradation is not good. However the mica content of these sands are low.

The clays of Markunda Ghat, Kelepara are fat clays, expected to show high shrink - swell activity. However, these are highly impervious. The clays of Chalkbelia and Deehalpara are of CH and CI Group but are expected to show low to medium swelling potential. These materials may suitably used as embankment or road construction.

No mines or cities (where chances of disposal or accumulation of toxic or heavy metals are more on vacant land)are nearby the sites. The clays (natural moisture contents indicate medium to stiff consistency) are similar to the older alluvium (distinctly different to the gray Gangetic alluvium) of the other Rarh plain (parts of Birbhum, Bankura, Burdwan, Hooghly, and West Midnapur) sites. These materials may safely be used.

4 D.P. Dolai,

R.O. QCL, RRI

\$13 - Sino C/S by S.S.De Dalal,


12


Dy. Dir (SM&Ch), RRI

Asim Chowdhury, EE(SDP), RRI

Lab SI No.	Site	Chainmeter	Depth.	Description of Soil	Natural Moisture Content of Disturbed Samples	Sieve Analysis	14'T1	Swelling Index	Remarks (Soil Group)
O/S 129/18		7.5 km	1 m	Yellowish Brown Fine Sand		Done			Sp
Q/S 130/18	Markunda	7.5 km	2 m	Yellowish Grey Silty Clay			110, 30		CH
Q/S 131/18	Ghat	7.5 km	3.m	Yellowish Grey Silty Clay					
Q/S 132/18		7.5 km	4 m	Yellowish Grey Silty Clay					
Q/S 133/18	Kelepara	10 km	E I	Yellowish Grey Silty Clay with Bluish Tinge					
Q/S 134/18		10 km	2.88.	Yellowish Grey Silty Clay with Bluish Tinge			75.5, 30.4		₹
0/8/13/18		10 km	3 m	Yellowish Grey Silty Clay with Bluish Tinge					
Q/S 136/18		10 km	4 11	Yellowish Grey Silty Clay with Bluish Tinge	26.60%				
Q/S 137/18	Chalkbelia	12.5 km	1 m	Yellowish Brown Fine to Medium Sand		Done			SP.
0/S 138/18		12.5 km	2 m	Yellowish Brown Fine to Medium Sand					
81/661 5/0		12.5 km	3 m	Brownish Dirty Fine to Medium Sand					
Q/S 140/18		12.5 km	4 m	Yellowish Brown Silty Clay with Kankars			58.8, 21.2	54%	CH Medium Swelling
Q/S 141/18		12.5 km	E ç	Vellowish Brown Silty Clay containing some sand and Kankars with Bluish Tinge					
Q/S 142/18	Dechalpara	16 km	E	Yellowish Grey, Loamy Clay with Kankars					
Q/S 143/18		16 km	2 ш	Brownish Grey, Loamy Clay with Bluish Tinge					
Q/S 144/18		16 km	3 ш	Brownish Grey, Loamy Clay with Bluish Tinge			38.6, 17.2		ō
Q/S 145/18		16 km	43	Brownish Clayey Sand with Bluish Tinge	19.70%				
Q/S 146/18		16 km	5 m	Whitish Loamy sand with Roddish and Bhuish Tinue					

ri Riv . and a second sec CDail Mar ł ALL DA Results






Annexure- 15 (b): Sediment Quality of Mundeswari and other drainage canal by MoEF & WBPCB recognized laboratory

Samples were drawn from Mundeswari river bed and bed of drainage canal.

-	/irotech East	Dut 1	mitod			Electro	X S W	irofech
	O 9001:2008, 14001:200	1			inv			
La	boratory Recognised by V	Vest Bengal P						
lengal	Ambuja Commercial Cor 13, 1050/1, Survey Park, F	nplex.			1 RC	-		
-2	418 8127/8128/8601; Fax	2418 8128; e	mail: eeplko	ol@gmail.c	om, eepli	col2@gm	iil.com	
	018/EEPL/MON/59/20			S. 26 (1)		CD00		20.09.2018
			ANAL	YSIS F	REPO	RT		
Nam	e of Industry		RAN CO	0.0000000	22377114.752	22-12-		
Addr	the second se						a, Lewis	Road, BJB
	anani da i	Nagar, E	hubanes	war - 751	014, Odi	sha	- A. C. 1985.07	
Date	of Sampling	23 08.20)18		2412	1.50.5		1
Loca	tion of Sampling	Code	Samplin	ng Locati	on	- Anton	Competence	
		SQ-1		on point of				
		SQ-2						arinkhola canal
		SQ- 3						hkhola Khal
		5Q-4		ng point o				
Cert	als Collected by	SQ-5	ntative of	ng point of			nd Kashi	iscar Kritti
Sam	ple Collected by	Represe	antanive of	Enviroled	al cast P	VI. LIU.	1	
		RES	SULTS	OF SA	MPLE	3		
Service Service	Kerse some proves	SCHOOL STORES	Interestory			-	Contraction (see	In the Design of the second second
SI. No.	Parameter	191 (91) (191)	SCAL	SO 2	SQ-1-5	50-4	\$2.5	Reference Standard
1	TEXTURE	TANK CARE IS	No. of the second s	A CONTRACTOR OF	No. of Concession, State	1.000.00	and and	NAME AND ADDRESS OF ADDRESS
a)	Gravel		23	24	20	21	20	IS 2720 (Part 4) - 1985
b)	Sand		22	22	23	18	24	15 2720 (Part 4) - 1985
c)	silt		25	26	26	24	25	15 2720 (Part 4) - 1985
4	and		30	28	31	37	31	15 2720 (Part 4)
d)	Clay		30	20	31	-		1985 (\$ 2720 (Part 29) -
2	Bulk Density (gm/cm ³)		1.04	1.02	0.92	1.06	0.94	1975
3	Porosity (%)		39.7	39.9	36.3	39.8	37.1	
4	WATER HOLDING CA		43.2	42.2	44.7	42.4	45.9	15 14765 : 2000
	CHEMICAL CHARACTER	ESTICS						16 0700 (0
1	pH (1:2)		6.8	6.7	6.9	6.6	6.4	15 2720 (Part 26) - 1987
2	Electrical Conductivity (1:5)	(µmhos/cm)	592	657	598	607	585	15 14767: 2000
3	Calcium (%)		0.18	0.24	0.21	0.18	0.23	##:
4	Magnesium (%)		0.17	0.18	0.16	0.17	0.14	An .
5	Fluoride (mg/kg)		37.9	39.9	36.8	39	40.6	**
6	Potassium (mg/kg)		233	321	332	265	238	**
7	Sulphur (mg/kg)		30	19	24	20	31 42	IS 14685 : 1999
8	Phosphorus (mg/kg)		38	42	43	35		IS 2720 (Part 22) -
9	Organic Carbon (%)	100-0	1.7	2.1	2.2	1.7	1.9	1972
10	Copper (mg/Kg)		28.5	26.1	30.3	30.4	24.5	.A*
11	Chromium (mg/Kg)		15.6	16.1	15.9	14.1	14.4	**
12	Zinc (mg/Kg)		34.5	32.1	36.3	36.4	30.5	** **
13	Lead (mg/Kg)		5.4	6.2	4.7	5.1	4.4	ππ ππ
14	Cadmium (mg/Kg)		3.2	2.5	3.4	4.2	3.2	**
15	Arsenic (mg/Kg) Nickei (mg/Kg)		4.5	5.6	4.2	5.8	4.6	
	THE REPORT OF THE PARTY OF THE		111	210	1.44	-14	COMP.	**



An ISO 9001:2008, 14001:2004 & OHSAS:18001:2007 Company

Laboratory Recognised by West Bengal Pollution Control Board Bengal Ambuja Commercial Complex, UN-F 13, 1050/1, Survey Park, Kolkata - 700 075 2 - 2418 8127/8128/8601; Fax - 2418 8128; email: eeplkol@gmail.com, eeplkol2@gmail.com

SI.	Parameter	1 20 100	CODE	- SQ-1-S	Q-5	1.6.17	State State State
Nea	The state of the state of the	SQ-1	5Q-2	SQ 3	504	50-5	Reference Standard
18	Boron (mg/Kg)	<1	<1	<1	<1	<1	**
19	Iron(mg/Kg)	31.7	33.9	34.5	24.6	27.8	**
20	Manganese (mg/Kg)	5.5	5.6	5.9	5	5.7	**
21	Molybdenum (mg/Kg)	3.4	2.2	3.1	2.7	the second second	
22	DDT(mg/kg)	-	the second second		and Contract	2.4	
0.020	e e e tringe regi	1.6	1.8	2.4	1.3	1.1	USEPA Method No.


Contents of this report are meant for your gridance and should not be used for Advertisement, Evidence or Litigation

Methods of Soil Analysis (Part-1) - Physical and Mineralogical Methods (Published by American Society of Agronomy) Methods of Soil Analysis (Part-2) - Chemical and Micro-biological Properties Second Edition (Published by American ** Society of Agronomy)

for ENVIROTECH EAST (P) LTD.

Ban 10 (Asoke Kumar Banerjee) Director

Annexure- 16: River Water Quality (Tested by SWID)



Memo No-

Copy Forwarded for information to:

Dated, Burdwan, the

 The Superintending Engineer (A-I), S.W.I. Circle, Bikash Bhawan, 4th Floor, Salt Lake City, Kolkata-700091

2. The Director, SWID, Nirman Bhawan, 4th Floor, Salt Lake City, Kolkata-700091

Executive Engineer (A-I) Burdwan S.W.I. Division II Burdwan

Government of West Bongal Divisional Chemical & Hydrological Laboratory State Water Investigation Directorate Spandan Complex (1st Floor), G.T. Road Burdwan, Pin: 713101

Report on chemical analysis of water sample received from Assistant Engineer (A-I), SWI, Sub-Division II/C, Chinsurah, Ref Mema No. 57 Dated 20/02/2018 A.E(A-I), Surface Water Sub-Division No. II/D, Chinsurah

SIL No.	Source (River Water)	Location (Muuaa/Block)	H	Specific Conductivity at 25°C in punhus/cm ar pS/cm	Total Hardness as CaCDs in mg/L	Chloride as Cl In mg/L	Total Iron as fe in mg/L	Arsenic us As in mg/L	Finoride as F in mg/L	Total Dissolved Solid in mg/L	Sodium as Na in mg/L
Ł	MEMOLA	Jumprum	6.87	364	170	24	1.14	BDL	0.34	232	31.3
ž.	BENULA	Dakahin Gapalpur / Buhayarh	7.04	564	240	27	0.43	BDL	0.20	360	63.6
X.	GHTA	Rahirranagachi/ Patho dadpar	7.34	542	220	26	0.51	BDL	0.24	346	55.2
4.	KUNA	Obspecificate /Singur	7.17	384	180	23	0.39	BDL	0.14	246	31.4
1	RANA	Harirumpur/Dhaniakait	7.20	372	190	21	1.24	BDL	0.69	230	25.6
5	S84516/477	Jerronall/Mogre	7.06	462	170	30	0.17	BDL	0.45	296	28.9
7.	SRASWATY.	Brithnepur/ Chandilaila R	7.68	2010	520	347	0.33	BDL.	0.10	1288	400
40	MONINESWARI	Souhol/Parmirah	7.44	372	170	23	8.49	BDL	0.39	238	23.7
••	MUNDESWARF	Markhune /Khosakul II	7.84	342	160	21	0.33	BDL	0.12	220	24.4
ni.	DAMODAR	Sabapar/Parsarah	7.70	340	150	24	0.28	BDL	0.39	218	21.7

SI. No.	Source (River Water)	Location (Moursy/Rlock)	Bell	Specific Conductivity at 25°C in jumbos /cm or µ5/cm	Total Bardness as CaCO3 In mg/L	Chioride as Cl in mg/L	Total fron as Fe in mg/L	Arsenic as As in mg/L	Fluoride as F in mg/l.	Total Dissolved Solid in mg/L	Sodium as Na in mg/L
11.	DAMODAN	Katsiljana/ Purnanak	7.65	340	140	21	0.15	BDL	0.49	218	21,1
12.	DARAKESWAR	Pairo/Goghar	7.72	340	160	26	0.53	BDL	0.50	216	23.9
13.	DARAAZSWAR	Dhonyoghri/ Khonaksi II	7.70	339	150	23	0.22	BDI.	0.62	218	22.0
14.	KANA DAMADOR	Dyble/ Dhonishall	7.40	372	180	24	4.28	BDI.	0.72	238	22.3
15	KANA DAMADON	Gasesblott/Jangipara	7.74	324	160	21	0.26	BDL.	0.32	208	22.9
16	GITA	Chawlabil/ Dhosiolath	7.36	420	210	26	2.34	BDL	0.78	270	32.9

In. Q-16061/1-2016-SWM/ 49/2(1)

forwarded for information and necessary action to:

The Assistant Engineer (A-I). Surface Water Sub-Division No. II/C, Chinnurah

- 16062/1-2016-05M/49/4/1(3)
 forwarded for information to:
 I. The Director, SWID, Sech Bhawan(1^{ref} Floor), Salt Laine Gity, Kolhuta-700091.
 The Souter Annual Geologist Geologist Geological Greke, SWID, Bikash Bhawan, Kolkata-700091.
 The Souter Geologist, Geological Div. No. II, SWID, Bardwan.

Chemist 2404 018 DOHL SWID.Barahen

Dated, Burdwan, the 24/04/2010

Sector Chemist Divisional Chemical Bilydrological Laboratory S.W.I.D., Burdwan Dated, Hurdwan, the 24/94/2018

Sentor Chemist Divisional Chemical Allydrological Laboratory S.W.I.D., Burdwan

24 04 2016

Page | 63

Annexure- 17(a): Baseline Environmental Report of Air, River Water, & Noise Quality



Envirotech East Pvt. Limited An ISO 9001:2008, 14001:2004 & OHSAS: 18001:2007 Company

Laboratory Recognised by MoEFCC, Govt. of India Laboratory Recognised by West Bengal Pollution ControlBoard Bengal Ambuja Commercial Complex, UN-F 13, 1050/1, Survey Park, Kolkata – 700 075 CIN NO.: U74210WB1989PTC047403 = -2418 8127/8128/8601; Fax – 2418 8128; email: eeplkol@gmail.com, eeplkol2@gmail.com

No. 2018-19/EEPL/Lab/CTRAN/D2

September 19, 2018

MONITORING REPORT

1	Project	Environment monitoring for Air Quality/ Water Quality/ Soil Quality/ Noise & Vibration
2	Proponent	CTRAN Consulting Limited, Bhubaneswar
3	Scope of Monitoring	Parameters as described in Work Order
4	Information Required	Test Results of Environment Monitoring for attributes Air/Water/Soil/Noise
5	Methodology	Standard Methodology of CPCB / MoEF Guidelines & BIS as applicable
6	Work Volume	Water quality – 3 locations Ambient Air Quality – 5 Locations Soil Quality : 5 Locations Noise – 5 stations

Remarks: The test Results for different samples of Ambient Air, Surface Water, Soil and Noise collected from different locations as per directive received from proponent indicate that the locations are complying with the requirements of Environment with respect to the above parameters of analysis

for ENVIROTECH EAST (P) LTD

Curchample

(Asoke Kumar Banerjee) Director



20.09.2018

Envirotech East Pvt. Limited

An ISO 9001:2008, 14001:2004 & OHSAS:18001:2007 Company Laboratory Recognised by West Bengal Pollution Control Board Bengal Ambuja Commercial Complex, UN-F 13, 1050/1, Survey Park, Kolkata – 700 075

2 - 2418 8127/8128/8601; Fax - 2418 8128; email: ceplkol@gmail.com, eeplkol2@gmail.com

No. 2018/REPL/MON/59/202

MONITORING REPORT

Name of Industry Address	M/s. CITRAN CONSULTING LIMITED BASIX Group Company, A1-A2, Lewis Plaza, Lewis Road, BJB Nagar, Bhubaneswar - 751014, Odisha
Average Temperature (°C)	28
Weather Condition	Cloudy
Rainfall	28
Avg. Relative Humidity (%)	91
Barometric Pressure (mmHg)	750

AMBIENT AIR QUALITY MONITORING RESULT

Date of Monitoring	21.08.20	18	A Louised and	Damodar Can	al
Location Name	Bifurcat	ion point of	Mundeswari and	Damoual can	
RESULTS : Parameters		Unit	Pollutants Concentration	NAAQ Standards	Reference Standard
Particulate Matter (size < 10 µm or PM)	aum)	µg/m ³	46	100	IS 5182 (Part 23)
Particulate Matter		µg/m ³	20	60	0.9
(size < 2.5 µm or PM	(2.5 µm)	µg/m'	$< 4 \mu g/m^3$	80	IS 5182 (Part 2)
Sulphur Dioxide (as S			19	80	1S 5182 (Part 6)
Nitrogen Dioxide (as	NO ₂)	μg/m ³ μg/m ³	11	100	* Method No. 411
Ozone (as O ₃)		µg/m ³	< 0.01 µg/m ³	1.0	1S 5182 (Part 22)
Lead (as Pb)		and Streetweet	0.4	02	893
Carbon Monoxide (as	(CO)	mg/m	<2 µg/m ³	400	* Method No. 401
Ammonia (as NH3)		µg/m'	the second se		IS 5182 (Part 11)
Benzene (as CoHo)		µg/m'	< 0.08 µg/m ³		IS 5182 (Part 12)
Benzo (a) Pyrene (Ba	P)	ng/m	< 0.1 ng/m	inster -	13,3132 (1 dit 12) #*
Arsenic (as As)		ng/m*	< 0.5 ng/m ³		
Nickel (as Ni)		ng/m	< 2 ng/m ³		

ND - Not Detected, BDL - Below Detectable Limit;

Note - As per National Ambient Air Quality Standard dated November 2009, Annual Average of Benzene (as C6H6), Benzo (a) Pyrene (BaP), Arsenic (as As) and Nickel (as Ni) are 05, 01, 06 and 20 ng/m3 respectively

* Methods of Air sampling and analysis (Third Edition) - James P. Lodge Jr.

** Guidelines for the measurement of ambient Air Pollutants (Volume I) - CPCB *** Guidelines for the measurement of ambient Air Pollutants (Volume II) - CPCB

Sample Collected by: Representative of Envirotech East Pvt. Ltd.

for ENVIROTECH EAST (P) LID 10 (Asoke Kumar Banerjee)

Director

An ISO 9001:2008, 14001:2004 & OHSAS:18001:2007 Company • Laboratory Recognised by West Bengal Pollution Control Board Bengal Ambuja Commercial Complex,

.......

UN-F 13, 1050/1, Survey Park, Kolkata - 700 075

P - 2418 8127/8128/8601; Fax - 2418 8128; email: eeplkol@gmail.com, eeplkol2@gmail.com

No. 2018/EEPL/MON/59/204

20.09.2018

Envirofech

MONITORING REPORT

Name of Industry	M/s. CITRAN CONSULTING LIMITED
Address	BASIX Group Company, A1-A2, Lewis Plaza, Lewis Road, BJB Nagar, Bhubaneswar - 751014, Odisha
Average Temperature (°C)	28
Weather Condition	Cloudy
Rainfall	28
Avg. Relative Humidity (%)	91
Barometric Pressure (mmHg)	750

AMBIENT AIR QUALITY MONITORING RESULT

Date of Monitoring	21.08.2018	star son (art think		
Location Name	Connecting point of	f Mundeswari river	and Harinkho	ola Canal
		RESULTS :		
Parameters	Unit	Pollutants Concentration	NAAQ Standards	Reference Standard
Particulate Matter (size < 10 µm or PM 10	μg/m ³	37	100	IS 5182 (Part 23)
Particulate Matter (size < 2.5 µm or PM 2	µg/m	15	60	6.0
Sulphur Dioxide (as SO	2) μg/m ³	$< 4 \mu g/m^3$	80	IS 5182 (Part 2)
Nitrogen Dioxide (as No	O ₂) μg/m ³	17	80	1S 5182 (Part 6)
Ozone (as O ₃)	μg/m ³	09	100	* Method No. 411
Lead (as Pb)	µg/m³	< 0.01 µg/m ³	1.0	IS 5182 (Part 22)
Carbon Monoxide (as C	O) mg/m ³	0.3	02	***
Ammonia (as NH3)	µg/m³	< 2 µg/m ³	400	* Method No. 401
Benzene (as C6H6)	μg/m ¹	< 0.08 µg/m ³	-	IS 5182 (Part 11)
Benzo (a) Pyrene (BaP)	ng/m ³	< 0,1 ng/m ³	•	IS 5182 (Part 12)
Arsenic (as As)	ng/m ³	< 0.5 ng/m ³	영화 속 문 문	**
Nickel (as Ni)	ng/m ³	$< 2 \text{ ng/m}^3$		\$¥

ND - Not Detected, BDL - Below Detectable Limit,

Note - As per National Ambient Air Quality Standard dated November 2009, Annual Average of Benzene (as C₆H₆), Benzo (a) Pyrene (BaP), Arsenic (as As) and Nickel (as Ni) are 05, 01, 06 and 20 ng/m³ respectively

* Methods of Air sampling and analysis (Third Edition) - James P. Lodge Jr.

** Guidelines for the measurement of ambient Air Pollutants (Volume I) - CPCB

*** Guidelines for the measurement of ambient Air Pollutants (Volume II) - CPCB

Sample Collected by: Representative of Envirotech East Pvt. Ltd.

for ENVIROTECH EAST (P) LTD (Asoke Kumar Banerjee) Director

An ISO 9001:2008, 14001:2004 & OHSAS:18001:2007 Company Laboratory Recognised by West Bengal Pollution Control Board Bengal Ambuja Commercial Complex,

UN-F 13, 1050/1, Survey Park, Kolkata - 700 075 2 - 2418 8127/8128/8601; Fax - 2418 8128; email: sepikol@gmail.com, sepikol2@gmail.com

No. 2018/EEPL/MON/59/205

20.09 2018

Envirotech

MONITORING REPORT

Name of Industry	M/s. CITRAN CONSULTING LIMITED
Address	BASIX Group Company, A1-A2, Lewis Plaza, Lewis Road, BJB Nagar, Bhubaneswar - 751014, Odisha
Average Temperature (°C)	28
Weather Condition	Cloudy
Rainfall	28
Avg. Relative Humidity (%)	91
Barometric Pressure (mmHg)	750

AMBIENT AIR QUALITY MONITORING RESULT

Date of Monitoring	21.08.2	018	to take	Siles -	
Location Name	Connec	ting point o	of Upper Rampur a	nd Harinkhola	Khal
RESULTS :					
Parameters		Unit	Pollutants Concentration	NAAQ Standards	Reference Standard
Particulate Matter (size < 10 µm or PM p	₀ μm)	µg/m ³	41	100	IS 5182 (Part 23)
Particulate Matter (size < 2.5 µm or PM	7.5µm)	µg/m ³	17	60	**
Sulphur Dioxide (as So	100	µg/m ³	< 4 µg/m ³	80	IS 5182 (Part 2)
Nitrogen Dioxide (as N	NO ₂)	µg/m ³	21	80	IS 5182 (Part 6)
Ozone (as O ₁)		μg/m ³	08	100	* Method No. 411
Lead (as Pb)		µg/m ³	< 0.01 µg/m ³	1.0	IS 5182 (Part 22)
Carbon Monoxide (as)	(0)	mg/m*	0.5	02	***
Ammonia (as NII3)		µg/m ³	< 2 µg/m ³	400	* Method No. 401
Benzene (as C6H6)		µg/m³	< 0.08 µg/m ³	1.1	1S 5182 (Part 11)
Benzo (a) Pyrene (BaP)	ng/m ³	< 0.1 ng/m ³		IS 5182 (Part 12)
Arsenic (as As)		ng/m ³	< 0.5 ng/m ²	a la composition	**
Nickel (as Ni)		ng/m	< 2 ng/m		**

ND - Not Detected, BDL - Below Detectable Limit;

Note - As per National Ambient Air Quality Standard dated November 2009, Annual Average of Benzene (as C6H6), Benzo (a) Pyrene (BaP), Arsenic (as As) and Nickel (as Ni) are 05, 01, 06 and 20 ng/m3 respectively * Methods of Air sampling and analysis (Third Edition) - James P. Lodge Jr.

** Guidelines for the measurement of ambient Air Pollutants (Volume I) - CPCB

*** Guidelines for the measurement of ambient Air Pollutants (Volume II) - CPCB

Sample Collected by: Representative of Envirotech East Pvt. Ltd.

for ENVIROTECH EAST (P) LTD.

(Asoke Kumar Banerjee) Director

An ISO 9001:2008, 14001:2004 & OHSAS:18001:2007 Company

 Laboratory Recognised by West Bengal Pollution Control Board Bengal Ambuja Commercial Complex,

UN-F 13, 1050/1, Survey Park, Kolkata - 700 075

🖀 - 2418 8127/8128/8601; Fax - 2418 8128; email: ceplkol@gmail.com, ceplkol2@gmail.com

No. 2018/EEPL/MON/59/206

20.09.2018

Envirotech

MONITORING REPORT

Name of Industry	M/s. CITRAN CONSULTING LIMITED
Address	BASIX Group Company, A1-A2, Lewis Plaza, Lewis Road, BJB Nagar, Bhubaneswar - 751014, Odisha
Average Temperature (°C)	28
Weather Condition	Cloudy
Rainfall	28
Avg. Relative Humidity (%)	91
Barometric Pressure (mmHg)	750

AMBIENT AIR QUALITY MONITORING RESULT

Date of Monitoring	21.08.2018					
Location Name	Connecting point of Kamaria, Raner and Madaria khal					
RESULTS :						
Parameters		Unit	Pollutants Concentration	NAAQ Standards	Reference Standard	
Particulate Matter (size < 10 µm or PM)	oμm)	µg/m ³	34	100	IS 5182 (Part 23)	
Particulate Matter (size < 2.5 µm or PM		μg/m ³	13	60	**	
Sulphur Dioxide (as S	O ₂)	µg/m ³	< 4 µg/m ¹	80	IS 5182 (Part 2)	
Nitrogen Dioxide (as)	NO ₂)	µg/m ³	15	80	IS 5182 (Part 6)	
Ozone (as O1)		µg/m'	7	100	* Method No. 411	
Lead (as Pb)		µg/m³	< 0.01 µg/m ³	1.0	IS 5182 (Part 22)	
Carbon Monoxide (as CO)		mg/m ³	0.4	02	***	
Ammonia (as NH3)		µg/m ³	<2 µg/m ³	400	* Method No. 401	
Benzene (as C6H6)		µg/m ³	< 0.08 µg/m ³		IS 5182 (Part 11)	
Benzo (a) Pyrene (Bal	?)	ng/m ³	$< 0.1 \text{ ng/m}^3$	-	IS 5182 (Part 12)	
Arsenic (as As)		ng/m ³	< 0.5 ng/m ³	(C	**	
Nickel (as Ni)		ng/m ³	$< 2 \text{ ng/m}^3$	2 10 × 10	**	

ND - Not Detected, BDL - Below Detectable Limit:

Note - As per National Ambient Air Quality Standard dated November 2009, Annual Average of Benzene (as C₆H₅), Benzo (a) Pyrene (BaP), Arsenic (as As) and Nickel (as Ni) are 05, 01, 06 and 20 ng/m³ respectively

* Methods of Air sampling and analysis (Third Edition) - James P. Lodge Jr.

** Guidelines for the measurement of ambient Air Pollutants (Volume I) - CPCB

*** Guidelines for the measurement of ambient Air Pollutants (Volume II) - CPCB

Sample Collected by: Representative of Envirotech East Pvt. Ltd.

for ENVIROTECH EAST (P) LTD. maBamy U

(Asoke Kumar Banerjee) Director

Envirotech	East Pvt.	Limited
------------	-----------	---------

An ISO 9001:2008, 14001:2004 & OHSAS:18001:2007 Company Laboratory Recognised by West Beugal Pollution Control Board Bengal Ambuja Commercial Complex, UN-F 13, 1050/1, Survey Park, Kolkata – 700 075

2 - 2418 8127/8128/8601; Fax - 2418 8128; email: eepikol@gmail.com, eepikol2@gmail.com

No. 2018/EEPL/MON/59/207

20.09.2018

Envirotech

MONITORING REPORT

Name of Industry	M/s. CITRAN CONSULTING LIMITED
Address	BASIX Group Company, A1-A2, Lewis Plaza, Lewis Road BJB Nagar, Bhubaneswar - 751014, Odisha
Average Temperature (°C)	28
Weather Condition	Cloudy
Rainfall	28
Avg. Relative Humidity (%)	91
Barometric Pressure (mmHg)	750

AMBIENT AIR QUALITY MONITORING RESULT

Date of Monitoring	21.08,20	18				
Location Name	connecting point of Maja Damodar and Kashmoli Khal					
RESULTS :				mini co al crozencia	To Paradaul	
Parameters		Unit	Pollutants Concentration	NAAQ Standards	Reference Standard	
Particulate Matter (size < 10 µm or PM)	o um)	µg/m³	38	100	1S 5182 (Part 23)	
Particulate Matter (size < 2.5 µm or PM		µg/m³	16	60	**	
Sulphur Dioxide (as S	01)	µg/m ³	$<4 \mu g/m^3$	80	IS 5182 (Part 2)	
Nitrogen Dioxide (as	the second se	µg/m ³	17	80	IS 5182 (Part 6)	
Ozone (as O ₃)	11021	µg/m ³	8	100	* Method No. 411	
Lead (as Pb)		µg/m3	< 0.01 µg/m ³	1.0	IS 5182 (Part 22)	
		mg/m ³	0.3	02	***	
Carbon Monoxide (as CO) Ammonia (as NH3)		µg/m'	<2 µg/m ¹	400	* Method No. 401	
Benzene (as C ₆ H ₆)		µg/m ³	< 0.08 µg/m ³		IS 5182 (Part 11)	
Benzo (a) Pyrene (Ba	(9)	ng/m*	$< 0.1 \text{ ng/m}^3$	145	IS 5182 (Part 12)	
Arsenic (as As)		ng/m ³	$< 0.5 \text{ ng/m}^3$		**	
Nickel (as Ni)		ng/m*	< 2 ng/m ³	4	**	

ND - Not Detected, BDL - Below Detectable Limit, Note - As per National Ambient Air Quality Standard dated November 2009, Annual Average of Benzene (as C6H6), Benzo (a) Pyrene (BaP), Arsenic (as As) and Nickel (as Ni) are 05, 01, 06 and 20 ng/m³ respectively

* Methods of Air sampling and analysis (Third Edition) - James P. Lodge Jr.

** Guidelines for the measurement of ambient Air Pollutants (Volume I) - CPCB *** Guidelines for the measurement of ambient Air Pollutants (Volume 11) - CPCB

Sample Collected by: Representative of Envirotech East Pvt. Ltd.

for ENVIROTECH EAST (P) LTD.

U (Asoke Kumar Banerjee Director



An ISO 9001:2008, 14001:2004 & OHSAS: 18001:2007 Company Laboratory Recognised by MoEFCC, Govt. of India Laboratory Recognised by West Bengal Pollution Control Board Bengal Ambuja Commercial Complex, UN-F 13, 1050/1, Survey Park, Kolkata – 700 075 CIN NO. : U74210WB1989PTC047403 T = 2418 8127/8128/8601; Fax – 2418 8128; email: eeplkol@gmail.com, eeplkol2@gmail.com

Water Analysis Report

Code	Sampling Location	Date of sampling	
SW 1	Connecting point of Upper Rampur and Harinkhola Khal		
SW 2	21-08-2018 to 23.08.2018		
SW 3	connecting point of Maja Damodar and Khorigeria khal	- 23.08.2018	

S1. No.	Parameter	Unit	CODE : SW1 - SW3		
			SW1	SW2	SW3
1	pH		6.7	6.6	6.9
2	Conductivity	µmhos/cm	423	502	408
З	Dissolved Oxygen	mg/L	6.4	6.2	6.5
4	Biochemical Oxygen Demand (3 days at 27°C)	mg/L	3	5	3
5	Tot al Coliforms	MPN/100 ml	2442	3214	2229
6	Total Dissolved Solids	mg/L	248	287	234
7	Chloride (as C1)	mg/L	74	102	85
8	Sulphate (as SO4)	mg/L	17	22	13
9	Nitrate (as NO ₃)	mg/L	1,9	2.6	1.4
10	Fluoride (as F)	mg/L	0.32	0.25	0.21
11	Calcium (as Ca)	mg/L	29	35	25
12	Magnessium (as Mg)	mg/L	10	13	15
13	Sodium (as Na)	mg/L	45	50	35
14	Iron (as Fe)	mg/L	0.11	80,0	0.07
15	Zinc (as Zn)	mg/L	<0.05	<0.05	<0.05
16	Arsenic (as As)	mg/L	<0.002	<0.002	<0.002
17	Lead (as Pb)	mg/L	<0.05	<0.05	<0.05
18	Cadmium (as Cd)	mg/L	<0.01	<0.01	<0.01

for ENVIROTECH EAST (P) LTD

x Romen file C 0 (Asoke Kumar Banerjee) Director

Envirotech East Pvt. Limited

An ISO 9001:2008, 14001:2004 & OHSAS:18001:2007 Company An ISO 9001:2008, 14001:2004 & OHSAS:18001:2007 Company Laboratory Recognised by West Bengal Pollation Control board Bengal Ambuja Commercial Complex, UN-F 13, 1050/1, Survey Park, Kolkata – 700 075 CIN NO. : U74210WB1989FTC647403 ☎ – 2418 8127/8128/8601; Fax – 2418 8128; email: eeplkol@gmail.com, eeplkol2@gmail.com

No. 2018/EEPL/MON/59/209

20.09.2018

Envirotech

NOISE LEVEL MONITORING


Laune or meaning	M/s. CITRAN CONSULTING LIMITED
Address	BASIX Group Company, A1-A2, Lewis Plaza, Lewis Road, BJB Nagar, Bhubaneswar - 751014, Odisha
Date of Monitoring	23.08.2018

CODE	SAMPLING LOCATION	EQUIVALENT NOISE LEVEL, Log in dB(A)
CODE		DAY TIME (Avg.)
N-1	Bifurcation point of Mundeswari and Damodar Canal	47
N- 2	Connecting point of Mundeswari river and Harinkhola Canal	54
N- 3	Connecting point of Upper Rampur and Harinkhola Khal	51
N- 4	Connecting point of Kamaria, Raner and Madaria Khal	49
N- 5	Connecting point of Maja Damodar and Kashmoli Khal	55

for ENVIROTECH EAST (P) LTD.

mat 1200 (Asoke Kumar Banerjee) Director

Annexure- 17(b): Map showing Baseline Environmental Monitoring location



Sampling Plan

Location	Symbol Shown in Map	Location Description	Sample of	Sample collection description	No. of Sample
Location 1		Bifurcation point of	Air		1
	Ű	Mundeswari and Damodar (Amta) Canal	Soil	Sample drawn from Mundeswari river bed	1
			Noise		1
Location 2	0	Connecting point of	Air		1
	¥	Mundeswari river and Harinkhola canal	Soil	Sample drawn from Mundeswari river bed	1
	100,000		Noise		1
Location 3		Connecting point of Upper	Air		1
	×	Rampur and Harinkhola Khal	Soil	Sample drawn from bed of canal at this point	1
			Noise		1
			Canal Water	Canal water shall be collected from this point	1
Location 4		Connecting point of Kamaria,	Air		1
		Raner and Madaria khal	Soil	Sample drawn from bed of canal at this point	1
			Noise		1
			Canal Water	Canal water shall be collected from this point	1
Location 5	\cap	Either from connecting point	Air	·	1
	\cup	of Maja Damodar and	Soil		1
		Kashmoli khal or connecting	Noise		1
		point of Maja Damodar and Khorigeria khal	Canal Water	Canal water shall be collected from this point	1
Total (5 Lo	cation)			·	18

Annexure- 18: Photo graphs of ESIA study

BOTH SIDE ENCROACHMENT ON OF DAMODAR LEFT EMBANKMENT



Figure 5: Double floored pucca house located on country side crest line of Damodar left embankment at Santoshnagar



Figure 7: Sameswar Agriculture Co-operative bank located at country side toe line of Damodar Left Embankment at Sameswar



Figure 9: Burning ghat located on set back zone of Damodar left embankment at Dayal Mansha tala



Figure 6: Soni mandir located on country side crest line of Damodar left embankment at Santosh Nagar



Figure 8: Abandoned building foundation located on country side toe line of Damodar left embankment at Rashpur



Figure 10: Campus of Dayal Mansha tala burning ghat campus





Figure 15: Burning ghat located on country side crest line at Bhona

Figure 16: Semi-pucca house located on river side toe line of Damodar Left embankment near Baliachak





Figure 17: Cultivation on setback zone of Damodar left embankment near Bagoya

Figure 18: Sugarcane cultivation on setback of Damodar left embankment zone at Balichak



Figure 19: Burning ghat located on setback zone of Damodar left embankment near Kalyan chak



Figure 20: Kali mandir located on setback zone of Damodar left embankment at Simchak.

Table 1: Both side Encroachment on Damodar Right Embankment

Both side Encroachment on Damodar Right Embankment



Figure 21: Household toilet constructed within setback zone of Damodar Right embankment near Tokapur River Lift point



Figure 22: View of Damodar Right embankment near Tokapur Purba (East) Muslimpara Para



Figure 23: House located within setback zone of Damodar Right embankment near Tokapur River Lift point



Figure 24: DGPS survey in process on Damodar Right Embankmnt near Tokapur Tokapur Purba (East) Muslimpara Para



Figure 25: Bokpota Eco park located adjacent to country side toe line of Damodar right embankment at Bokpota



Figure 26: Site office with labour camp of Mackintosh Burn Limited on setback zone of Damodar Right Embankment for construction of river over bridge at Bokpota



Figure 27: Bedi located on river side crest line of Damodar Right embankment at Shibani para



Figure 29: Abandoned house located on setback zone of Damodar Right embankment near Akna Omkarnath Ashram



Figure 28: Omkarnath ashram located on setback zone of Damodar right embankment at Akna



Figure 30: Semi pucca house located adjacent to right site embankment of damodar river near Samanta Para of Joynagar



Figure 31: Burning ghat located on setback zone of Damodar Right embankment near Akna Omkarnath Ashram

Figure 32: Semi pucca house located on setback zone of Damodar Right embankment near Samanta Para of Jaynagar

Table 2: Both side encroachment on Upper Rampur khal





 Table 3: Encroachment over Left embankment of Hurhura Channel



Table 4: Sacred Grove on Left Embankment of Upper Rampur Khal



Figure 33: Sacred grove (300 years old Baniyan Tree) on upper rampur left Eambankment at Bhut Bhanga More (No project activity is proposed in this area)

Table 5: Canal Water Pollution on Upper Rampur Khal





Figure 36: Canal Water Pollution in Upper Rampur Khal



Figure 37: Canal Water Pollution in Upper Rampur Khal



 Table 6: Scenario of Mundeswari River in the Month of September, 2018
 Page 2018

Figure 39: View of Mundeswari River in the month of September, 2018



Figure 40: View of Mundeswari River near Markunda Village in the month of September, 2018




Figure 41: Mundeswari river at Aruna Bera (Up to which dredging is proposed)



Table 7: Monsoon Agricultural Practice in Howrah District



Figure 43: Spraying of pesticide during monsoon cultivation near feri ghat at Dihivut (on country side of Damodar Right embankment)



Figure 44: Cultivation of Taro root during monsoon season near feri ghat at Dihivut (on country side of Damodar Right embankment)



Figure 45: Monsoon cultivation of paddy on breach affected -2017 (5 feet sand deposited on almost 33 Acre agli land)country side, located opposite side of River Lift pump house at Dihivut



Figure 46: Monsoon paddy cultivation on Damodar Right setback zone near River Lift pump house at Dihivut



Figure 47: Uncultivated river side agri-land of Damodar right embankment during monsoon due to heavy sand deposition



Figure 48: Pesticide Spray machine (near Muslim para at Dihivut - Damodar Right embankment)



Figure 49: Uncultivated (during monsoon) setback zone of Damodar right embankment located near Ghola Karmakar para



Figure 50: Pig Grazing by women during monsoon on setback zone of Damodar Right Embankment nearby River Lift pump house at Dihivut



Figure 51: Pesticide use by farmers - near to Muslim para of Dihivut (Damodar Right embankment)



Figure 52: DGPS survey in process on Damodar Right Embankmnt near Tokapur Tokapur Purba (East) Muslimpara Para

Table 8: Picture on Inundation and breaching



Figure 53: Ring band protection with Gunny bag at breach point (during 2017) of Damodar Right Embankment near Tokapur River Lift point



Figure 54: Cattle washing on river side inundated area of Damodar Right embankment near Tokapur Purba (East) Muslimpara Para



Figure 55: Inundated agri land located on setback zone of Damodar Right embankment near Tokapur Purba (East) Muslimpara Para



Figure 56: Wave breaker (country side) provided on spill zone located on Damodar Right Embankment at Shibani para



Figure 57: Breach point (2017) of Damodar Right dwarf embankment located near Tokapur River Lift point

Figure 58: Bathing ghat on Damodar Right embankment at Tokapur Purba (East) Muslimpara Para

Annexure- 19: MoM on ESMP Consultation & sharing workshop

<u>Minutes of meeting on "Consultation and Sharing Workshop on Environmental and Social</u> <u>Management Plan (ESMP) of West Bengal Major Irrigation and Flood Management Project</u> (WBMIFMP)"

This meeting was held on Friday 16th November 2018 at Coference Hall, 12th Floor of "Subhannya", SGO Complex, Salt Lake City, Kolkata-700064, with the Welcomes Addressed by Mr. Subir kumar Laha, Chief Engineer and Project Director, SPMU-WBMIFMP, IW&D, Government of West Bengal. He welcomed the delegates from IWD, Line departments, Local Self-governance Institute, ESIA & FS consultant, NGOs representatives, Sand mining & construction company, farmers, educational institute. CE&PD has narrated project objectives with background and objective of "Consultation and Sharing Workshop on Environmental and Social Management Plan (ESMP)". ESIA consulting team was asked to present proposed ESMP specially designed for this WBMIFMP project.

Mr. Kader Mirdha (Consultant) on behalf of CTRAN Consulting has presented the project activity specific ESMP through Power Point Presentation with support by Mr. Saroj Nayak (Vice President) of the CTRAN and IWD officials. Mr. Subrata Chottopadhaya (APD- SPMU) has described project activities under Irrigation Management components. Baseline findings of environmental and social features were described elaborately. The house has silently observed anticipated impact due to project intervention and proposed management plan to mitigate adverse environmental & social impacts. Entire presentation and consultation were carried out in local Bengali language.

SN	Name of the	Institution /	Issue Raised	Reply/ Addressed in ESMP
	Participants			
1.	Mr. Rajarshi	Environmental		Responsibility of afforestation is given to
	Chakrabarty	Officer	ESMP with suggestion to	
		Environmental		plantation will be done alongside of
		Dept., GoWB	1 2	earther embankment where there is no
				PCC block lining. However, contractor
				will prepare site specific plan in
				consultation with local people and IWD
			Afforestation location with	00
			suitable species shall be	
			specified in plan. He also	
			enquires about	
			implementation mechanism of	
_			afforestation plan.	
2	Dr. Prakash	Research		Official of Biodiversity board were
	Pradhan	Assistant,		consulted on 26 th October, 2018 at there
				office located at 5 th Floor, Animal
		•	impact on flora and fauna	
		GoWB		They have suggestes to consider impact
				on Fishing Cat, Mongoose, Asian Small
			to promote indegenious trees,	
				Turtles/Terrapins, Jungle Cat, Jackal,
				Monitor Lizard, etc., in addition to
			the project activity plan.	several species of birds including the White avad Pachard
			During de-siltation of cannel,	
			the fish breeds may be	
			affected, whether the ESMP	

Table 9: Participants Feedback on the work-shop programme

SN	Name of the Participants	Institution / Organization	Issue Raised	Reply/ Addressed in ESMP
	1 di ticipanto	organization	has provision to address any such impact.	Impact on these endangered/ threattend species are idenfied and mitigation plan is proposed accordingly.
				Desiltation activities are proposed to be implemented during day time. Vibration arrangement to be made by contractor to allow species to come out from cave and migrate to nearby bush.
				Mixed plantation with locally grown tree species is proposed for afforestation. Improved varities of locally grown high value crop will be promoted under this project.
				Developing community seeds bank is not part of this irrigation project. Community seeds bank may be promoted under other project of Agri-marketing department.
				Desiltation activities will be carried out only during non-monsoon period. However, consultation with Dept. of Fishery has revailed non-presence of any such natural breeding point on Mundeswari river as it remains almost dry even during monsoon period, until the discharge is more than 40,000 cusec.
3	Priya Hazra		seedling in Damodar river during monsoon shall be examined properly. In general, Dolphin gets badly injured	Portion of Mundeswari river where desiltation is prposed remains dry even during monsoon period except water in few pockets.
				Moreover, dry desiltation will be adopted only during non-monsoon period.
4	Monoj Porel	ordinator, Itarai Asha Deep Foundation, NGO- Udaynarayanpur- II	women trafficking, sexual harassment in the work place during project implementation. Management plan need to consider this such activities in advance. One of project blocks in Howrah district has been affected by Arsenic. The safe drinking water facilities shall be provided to all community and workers.	However, contractor will provided safe drinking water to all of its workers.
5	Rupchand Bera	Savapati, Amti- II, Howrah Dist.	not come down to DPMU/ SPMU office each time. He	Bottom level of PRI system i.e Gram Panchayat is given 1 st tier responsibility for greavance redressal. This is very common practice in West Bengal.

SN	Name of the	Institution /	Issue Raised	Reply/ Addressed in ESMP
	Participants	Organization		
				GP member may resolve any greavance
				in consultation with other PRI members
			nodal point.	at higher level.
6.	Mr.			The CE & PD did not agreeed with layer
	Sudarshan			wise desiltation activity. He further
	Gupta	1		added saying, matter was already
		Pvt Ltd.		discussed during project formulation
				stage and discurred owing to non techno-
			be segregated in this way at	economic feasible option.
			source itself. Soil mixed sand	
			material will be used in filling	
				discussed during meeting with interested
				bidding contractor. If contractors can
				come up with feasible techno-economic
				solution, matter will be considered and
			plan to public in advance.	included in bidding condition.
				5 – 19 km. chainage of Mundeswari
				River will be desilted in 1 st phase and
				remaining portion in 2^{nd} phase.
7.	Mrs. Salma	Secretary,	Adivasi population leaving in	Canal resectioning, slope lining and
	Murmu	Shibnibas Adivasi		renovation of existing irrigation
		Women		structures are proposed to improve
		Development	receive sufficient irrigation	
		Society (NGO),		5
		Sonamukhi,		Irrigation devision has nothing to do with
		Bankura		elephant attack. Matter may be placed
			firm.	before forest department.
8.	Dr. Kamal	Core Support	He critically reviewed the	
	Alam		proposed project interventions	
			and appreciates the ESMP.	
		& Education		
		Trust		
9.	Banibrata	Fisherman,		Entire stretch can't be PCC block lined
	Hait	Khanakul-II,		with available fund. Critically afftected
		Hooghly		portions are selected for PCC block
			be concrete lining of entire	lining.
			embankment.	

Participants list

unitation and Sharing Workshop on Environmental and Social Impact Assessment (ESIA) and Management Plan	of West Bengal Major Irrigation and Flood Management Project (WBMIFMP)
nd Sharing	of West Bengal Major Irrigation and

Organised By: SPMU- WBMIFMP, Irrigation & Waterways Department, Govt. of West Bengal Facilitated By: CTRAN Consulting Limited (www.ctranconsulting.com)

Time: 11:30 AM 16th November, 2018 Date:

Conference Hall at 12th Floor of "Subhamya", SGO Complex, Salt Lake, Kolkata- 700064, Salt Lake. Venue:

CILL COL

1	Attendance sneet				C. L. M.	a mail M	Sionature
SI. No.	Name of Participant	Institution Name/ Department	Designation 3	Type of Participant (NGO/ SHG/ FPO/ HPC/ Fishermant Farmer' Sand Miner/Contractor/ Gott. Service/ Educational Institute/Consultant)	Contact No	e-man ro	
4	Schir Keimer Leke	ISW.D.	CERPD.		9431416427	1	tel
2.	D.K. Maili	EPTISA	DTL	Consultant 7831185139	7831185139		X
3.	Mayunakaha	River Rescared Instate a.B.	Dy Directory Chydrauliy		3432100700	Cout. service. 3432100700 ochelminute Mandrage	The welling
4.	Pynamal Kn. Chosh	Franal Kn. Chosh CreAN Consulting	Paris and coordinates	Consultant	9932116130	genarul 19 Ogravi	Cont
5.	Amitova Handal.	ETRAN EGNSWITHING	FPO Corralination	eonsuldant	7681233475	9681232475 amitana. dalequini	i detert
9.	Sudaushan Euple	Suchaushan bouples Lokenath Estate &	Manchelder Sand Miner	Sad Miner	t98151750b	90512151367 sater in blokenath Marty	Nutz
7.	Provanta Ler. Maily		By. DLE LAD,	Gart. Service	99296918968	dydd rohannah @ guni	Andrew
8	RERHA MONDAL.	ADA (J.	S.R.O IL ADM & DI SILRO OFFICE, HOOGH	GOVT. SERMICE	JE Plateth	ditrolucyli @	\$1.11. 11 428
∞ċ	RERHA MONDAL.	ADH (1.K) OFFICE , HODGALLY	S.R.C IL , ADM & S. L. J. ADM &		T. SERNICE		The Followski

Dignature	M. Perel.	Station Juri Hage	2102 .11. 01	V	Hospia	A star	Ruis 8	Per Per	guttered	J.	- 2 mind.	Lan-
e-mail ID	Harris askadort	C	98123-266426 march . com in	861702741 schopchial Estav	haznabuyate gmail cem	9073362594 appendixed@	34 34 39257 > amer & Banker	environnetab	Shrenkennte Road.	Sbreth 10 B gui.	9932734238 rde specie 208 2014.	Tort depà 9830706653 honoride
Contact No	9732986113	8348536653	96749671861 03453-266426	17/20-2/198	gaco435243	407362594	943432259A	23355220	to hoolsoft	91239	9932734238	9830706653
Type of Participant (NGO/ SHG: FPO/ FPC/ Fishermanl Farmer/ Sand Miner/ Contractor God. Service/ Educational Institute/ Consultant)	NGO	Farmer	1000 N	NGO	NGIO	Govt.	N.a. 6 - We a	Gent	Awt-	Geory.	Govt.	Car
Dcsignation	Co- 00 denator.	Farmer	Secretary, (NGO)	member	Project Associate	Assistant Engineer (Cuil)	(is work)	E miran mut	Revended Asnt.	Add - Pris. Pivecter-II	AAH Devector of AN Streedtone (PS)	Ex. Engl Hrigh
Institution Name/ Department	Harree Asha Deep	FD.0.	lalpara Samily -Burdwan	KAI FR PUR WELFERE SOCIETY	WWF India, WBSO	Housed Durn P.W. D.	anturn signer 5 202	Equinament Dept	W. C. Brdwing Band	ELVID G UND I	Rold. Develor of A gridual CC W.B.	
Name of Participant	MONOT POREL	7 DAW KUMARHHZAN F D. O.	11. MDNAZRULISLAM NULAMERAN Nulambate Hospin Khad Unrayan 20. Muranan, Dist	salente doin	Riya Hazra	14. Subbra Khan	Salina murrin organisation	Rajonshi Chabour 1 Eminiment Dupt	Freed hadron	18. 5 . chattapady	19. L. K. Mande	J. Bulla
SI. No.	.6	10.	II.	12.	. 13.	I4.	15.	16.	17.	18.	19.	20.

c-mail ID Signature	FF1		51 agragati moto tal 5. Bli was	agregati molv lall 2 mo. 1. 20m austrog. ali 2013 C	agraques moto ball 5 2 mo. 1. com 2 anstragal 2019 c	R mail com 5.0	Rmail. com 5.12 Rmail. com 2.12 austrogradi 2070 D. austrogradi 2070 D.	anstrayati 2010 5.12 Amail. com austrayati 2010 2 Alex tegan G 21 sas	agragatimetral 5.1 2 mic.il. com austrajati 200 - 1 austrajati 200 - 1 tefan G - 7 5a imer L 19653 - 1 diganta maily Jo	agragati noil. com 2 moil. com	agragation com 2 mail com 2 mail com 2 mail com 2 mail com 4 part 200 1 1 Janie - 19653 2 1 2	agragation com 2 mail com 2 mail com 2 mail com 2 mail com 1 parter C 1 2 Ca 2 mail com 2 mail com 2 mail mail lim 2 mail mail com 2 mail mail com
Type OL FARTICIPATIL (NGOV CONTACTING SHC/ FPO/ FPC/ FRETMARY Farmer/ Sand Minet Contractor/ Gont. Service/ Isducational Institute Consultant)	7474861643	9474802651 2.		the reast eat	terosion .	ter 2021 ent	6069956096 54021222266 5402122666	2069956096 6069956096 5665858666 560275752666	202899966446	288642824649 20589966499 20589966499 2058936966499 2058936966499 2058936966499 2058936966499 2058936966499 2058936966499 2058936966499 2058936966499 2058936966499 2058936966499 2058936966499 2058936966499 2058936966499 2058936966499 20589369664996649 205893696649966499 205893696649966499 20589369664996649966499 20589568645649 20589568956649966499 20589568956845 20589568956649966499 205895689566499664956	 615718+546 606926664b 60692666b 60692666b	 401924525240 60692660393 60692660393 60692660393 6069266036 6069266036 6069266036 60693666039 606337566603 60633756603 60633756
SHCJ: FPO/: FPC/: Fishermard: Farmer/ Sand Miner/ Contractor/ Govt. Service/ Fiducational Institute/ Consultant)	SHON	SHG		Gout. compleyee	Gove employe Social Suvice	Gover employe Special Service	Gover employe Special Service Sand michel	Gover employe Boeier Service Sand minim	50 Sa Sa	5 5 3a	2 S 22 S 20	2 N 5 30 20
LCSIBuatmin	Po. Or is limeter	S e		SR. O. II	She I Savepahi	SR. e. I. Savapahi	She I Savapahi Hoodill	SR er II Savepahi HoodWY	SR. e. I. Savapahi Hosoluu U U By PD CCUI)-N	SR. e. I. Savapahi Hoodur M. PD (Clui)-N Anu, MAMERNY HOOShly	SR. e. I. S. averpahi Hosolur Hosolur Hosshly Hosshly	SR. O. I. S. C. I. S. C. I. M. P. C. C. W. J. N. Hooshy Hooshy Hooshy Hooshy Hooshy Hooshy
Institution Name/ Department		Agrozoli walnew Sangler Programuk B.S.S. Ltd.	And to Jane -	Purhar bardhamme	Finder Der Quenner Severpalt Andre-II Housen	Andra II Hocore	Savan Producement Savan Producement Andra-11 Housan	Savapal- Bavapal- Andr-II Horand Andr-II Horand Savami'd- Letehold	Finder To And The And	Savarant Personan Savarant Hocard Andr-II Hocard Savani'va- Cerehold	Finder Territoria	Finder Territ Personal Andra II Horand Andra II Horand Bard Mi 4 Cereho Ad Cereho Ad Califor Antionnet & Eduction Fritt
Name of Participant	21. Parton Ram	superya Dhwa	Sh. Asvaz 41.	1	Rup clair Ren.	Eur chuid Rein. Sk statier Aasai	24. Kup churd Rec. 25. Sk Abir Hossi	Kup chund Been. Sk Addir Hosson Topan Lamaula Navvel Mouelal	24. Kup churd Ben Swapet 25. Sk Addir Arsia Andra 26. Topan Lamaute Savami 27. Navrul Mourled Cereh 28. Aigenter Naity ISWD	Wy churd Bers. Sk Atalin Arsia Topan Lamarka Narred Mourled Narred Mourled Figenda Naity	24. Kup chand Been. 25. St Addir Hosser. 26. Topan Lamauta 26. Topan Lamauta 28. Aiganta Mouelal Ninvuel Mouelal 28. Aiganta Maily 29. Breamta Kumaa 29. Breamta Kumaa	Kup chund Bene. Sk Atalin Arsian Jopan Lamaula Navrul Mourial Navrul Mourial Navrul Mourial Navrul Mourial Seconda Nauria
SI. No.	21. /a	22.	23		24. X				24. K	24. K	24. 25. 25. 25. 25. 26. 7 26. 7 26. 26. 27. 29. 6 29. 6 29. 6	24. K 25. 7 26. 7 26. 7 28. A 28. A 29. A 30. B 31. 4

	Department	Designation	Type 0. La the provident of the providence of th			
33. Sorry Nouger	CTRAN CONSUMINY	UP		Latocetenb	Kory. Curry est.	Auge in Joris
34. Tarn Kr Ballow	19 w lete	DPD-V	Govt. Inuice	6626 19 2220		& a will
35. Ludip Halden		PPP(civi)-I	Gout . Scennice	TS90818846	muds pop TS808188 th	Letteddar 18
36. Bouibrale	BLOCK = KHANAKUL-	ML-	FISHER MAN	9734373358	9734373358 avitratrale @	1111 minutes
37. Biparciut and Addi P. D.	Add. P.D.	Am I mum	Client	94330 (354		Variation 18 fields
38. Kadu Mecella CTRAN	CTRAN Consulting	consultant	consultant	833 7-232 284	8337332889 Rader midde	- Amp
39.						
40.						
41.						
42.						
43.						
44.						

Annexure- 20 (a): MoM with Sand Miners Regarding Utilization of Desilted Material



Proceeding of meeting held at the chamber of the Additional District Magistrate and District Land & Land Reforms Officer, Hooghly on 05.09.2018 in connection with utilization of bed materials which will be obtained from desiltation from Mundeswari River, Hooghly

12 Mar 12 20 10 10 10 10

		Members	Present		
SL No.	Name	Designation	SI. No.	Name	Designation
1	Dr. Rajat Nanda	ADM & DL & LRO, Hooghly	11	Sk, Abdus Sattar	Mahaprabhu Enterprise
2		Executive Engineer, Irrigation & Waterways, Hooghly	12	Sk. Mosaraf Hossain	New Madina Marbel
3	Mrinal Roy	Superiantendent Engineer & Addl. Project Director- II, I & W Dte.	13	Sita Ram Sannte	Alam Enterprise
4		Additional Project Director-IV, DPMU-II, WBMIFMP	14	Arup Kumar Ghosh	Unik Brick Field
5	Somenath Ghosh	A.E/Mundeswari(I) Sub- Division	15	Sk. Md. Alinawaz	Serina Construction
6	Sri Sudarshan Gupta	Lokenath Estate & Export Pvt. Ltd.	16	Sk. Abdus Sattar	
7	Kajal Ghosh		17	Tapan Kr. Samanta	EXCELL MOVERS
8	Sk. Abdur Sattar		18	Sk. Nizam Uddin	Apanjan Supplier
9	Prasanta Kumar Hait		19	Dipak Maiti	Consultant EPTISA(I) Ltd.
10	Tanmoy Kumar Roy				

The Additional District Magistrate and District Land & Land Reforms Officer, Hooghly took the chair and the meeting started. At the onset Executive Engineer, Irrigation brief the details of the project i.e. desiltation or excavation from the Mundeswari River bed. He said that the work of excavation will be conducted in two phases. He further briefed that the work of delineation of the zone of mining in the Mouza Map is being conducted jointly by the team of Irrigation & Land and Land Reforms Department.

In the 1st phase which will take approximate 1(one) year time and will cover region of 12 KM. 35 Lakhs cubic meter of sand (river bed material) will be desilted. This meeting has been necessited for chalking out disposal plan of the materials that will be excavated. The Lessees (sand mining) and the prospective sand miners were given offer to dispose the excavated materials from the project site or from a suitable location that will be decided by the Irrigation and Waterways Department and which will fall within 5(five) KM of the site of excavation.

Contd.....2

2

The sand miners opined for extraction of bed materials by themselves to segregate the bed materials according to classification and grain size, i.e. either sand or mixture of sand, silt and clay for effective and use. It was opined by the IWD officials that such a condition may affect the work plan and also the specification of the work and therefore, may not be acceptable to the IWD. The preferred option would be to do the excavation by the IWD agencies and transportation of the excavated materials by the sand miners from site. IWD officials assured to address the concerns of the Sand miners, keeping in view the need of ;end use of the excavated materials, to the extent feasible. This proposable of the IWD was finally accepted.

The lease holder and prospective miners were asked to submit formal proposals by Monday i.e. 10.09.2018 in writing. While submitting their willingness, they will cover the following points;-

- a) The minimum amount of sand/river bed materials the sand miner will be able to and will dispose monthly.
- b) The point or site from which the sand miner will collect the sand and the route they will follow.
- c) Infrastructural support that will be required by the sand miner for disposition of the excavated material.
- d) Any other note of interrogation.

It was made clear from the chair that as is usual the sand miner will get the sand on pre payment of Royalty & Cess alongwith other contributions as usual in case of mining. The said payment will be realized at the end of BL & LRO concerned.

It was further decided that after receipt of proposals from the sand miners the next course of action will be decided.

The meeting ended thanks from the chair.

Additional District Magistrate & District Land & Land Reforms Officer, Hooghly

Memo No.IX-08/Earth Extr. Mundeswari/ 5101/1(3) /MM.

Date- 10-9-18

Copy forwarded to:-

- The District Magistrate, Hooghly for kind information.
- 2) The Executive Engineer, Hooghly Irrigation & Waterways Division, Hooghly.
- 3) The Additional Project Director IV, DPMU-II, WBMIFMP.

Additional District Magistrate & District Land & Land Reforms Officer, Hooghly

Annexure- 20 (b): Proposal by Sand Miners Regarding Utilization of Desilted Material

To 11.09.2018 ADM & DL & LRO, Hooghly, Dist-hooghly

Sub: disposal of excavated river bed material of the river mundeswari proposed to be executed in year 2019 dist Hooghly

Ref: 1. Mail dated 04.09.18. Memo No. IX-08/Earth Extr. Mundeswari/4971/MM dated 04.09.18 2. Mail dated 11.09.18. Memo No. IX-08/Earth Extr. Mundeswari/5101/1(3)/MM dated 10.09.18

Respected sir,

As per information received from office of ADM & DL & LRO, HOOGHLY in a meeting held on 05.09.18, the river mundeswari will be excavated in year 2019, covering a span of 19 km, width 150mt and depth 3m.

Lokenath Estate & Export Pvt. Ltd., a private limited company having registered office at 582, D.H.Road, Behala, Kolkata-700034, carrying out business of supplier of building raw material to leading construction and real estate companies like Larsen & Toubro Limited, Simplex Project Limited, Simplex Infrastructure Limited, Ideal real Estate, Diamond group, DTC group, RVNL Metro rail under construction in kolkta and many others , Fly Ash Brick Manufacturing at Aamtala dist:24 Parganas South, Sand minning at Mouza Chandur Dist Hooghly,Sand Minning Mouza Hatsimul, Srirampur, Haripur Dist Purba Bardhaman.

Lokenath Estate & Export Pvt. Ltd. is keenly interested in procuring the job of disposal of river bed material, expecting the plan of material disposal would be for a period of one year approximately and expected quantity of materials 35,00,000 m³ consisting of sand silt soil pebbles and other materials.

So material to be disposed for filling purpose in a period of 12 months which comes to about $2,91,666m^3$ /month which would be $9,722m^3$ /day. Expecting height of stored heap of 5m, daily $1,944m^2$ or 0.480 acres of land would be required for stock of materials, and for stock of 30 days land required would be 14 acres or 44 bighas approximately.

In view of the large scale job of disposal of excavated riverbed material, Lokenath Estate & Export Pvt. Ltd. intends to execute the job in association with the following firms:-

a) Excel Movers, having registered office at Village-Masinan, P.S- Pursurah, P.O.- Sodepur, Hooghly-712 415, doing business of supplier of building raw Materials, transportation, minning of Sand at Mouza- Chahbense Dist.- Hooghly, And also sand minning at Mouza- Srirampur, Hatsimul, Dist.- Purba Burdwan.

b) Prasanta Kumar Hait, having registered office at Village- Dehibatpur, P.O.- Alati, P.S.- Pursurah, Dist.- Hooghly, Pin Code- 712 414, doing business of lifting Sand from River, selling of Sand, drezzing in river, Government Contractor, Sand minning at Mouza- Baikunthapur, Dist.- Hooghly.

c) Uttam Samanta, having registered office at, Village- Masinan, P.S.- Purusrah, P.O.- Sodepur,

Hooghly- 712 415, doing business of transportation, supplier of building raw material and minning sand at Mouza- Narasinhapur, Dist.- Purba Burdwan.

d) Sudarshan Gupta, having registered office at 582, Diamond Harbour Road, Behala,Kolkata- 700 034, doing business of transportation, supplier of building raw materials, Sand minning at Mouza-Becharhat, Srirampur, Hatsimul, Dist.- Purba Burdwan.

In this disposal of river bed material some of the major problems would be dealt with as follows:-

1. Daily around 850 truck load material has to be disposed. Each dumper expecting to do 10 trips, so around 85 trucks will be required. We keeping in mind unforeseen circumstances will be recruiting 120 dumpers from transporters.

2. In order to load dumpers and trucks effectively and smoothly we need loading pokhland. We would ne requiring about 12 pokhlands of model 210 Komatsu. We are already running 6 such machines currently. We have already finalized discussion for recruiting 12 such pokhlands.

3. Land would be required minimum 50 bighas for ease of activities & securities. Land can be made available alongs side the currently passage of following river which are sketch as river in mouza map but over years river has shrunk to much leaser width. Apart from this, land would be acquired by general public at a higher rate even its available beyond the distance of 5km. We have finalized dealing with land owners in adjoining mouzas near mundeswari river excavation site, the details of which are as follows:

MOUZA	BANK	ACRE	BIGHA	DISTANCE
(Approx.)				
1. MAYAPUR	WEST	21.66	65	5 KM
2. MALAYPUR	WEST	16.33	49	3 KM
3. ALATI	EAST	7.33	22	4 KM
4. DEULPARA	EAST	10.00	30	5 KM
5. BAIKUNTHAPUR	EAST	11.66	35	5 KM
6. SOALUK	EAST	10.00	30	2 KM
7. BACHANARI	WEST	6.00	18	3 KM
8. KESHABPUR	WEST	5.00	15	5 KM
9. ARUNBERA	EAST	7.33	22	4 KM
10. DAKSHIN RASULPUR	WEST	6.00	18	5 KM
11. FATEPUR	WEST	5.00	15	3 KM
12. GOLAMICHAK	EAST	6.66	20	5 KM
		112.97	339	

4. One of the biggest problem would be accessible approach metallic roads to excavated sites along side the river. Such roads will bear the load of 1000 trips of loaded trucks daily which will further damage the road. So road with huge extra strength need to be built by government. Damaged roads to be repaired immediately by government otherwise smooth flow of trucks will be hampered. In case of break down of lorry passage will be block disrupting communication so wider road would be required.

On 05.09.18 at the meeting at office of ADM & DL & LRO, Hooghly, a total of 7 roads were demarcated in mouza map for transportation of riverbed material. We will be using all these roads for transportation of riverbed material. In addition to it, we have identified another approach road to riverbed which is owned privately and have convinced the owners to allow us for transportation of riverbed material. This private road also needs to be developed into metallic road by government for smooth flow of dumpers.

We would be glad to collect material from riverbed itself provided strong approach passage to excavation site is made available to us.

5. If strong 4G internet service can be made available along the path of excavation in riverbed and adjoining 5km region, it would not only help us in smooth disposal of excavated riverbed material but will also help the agency excavating the riverbed. Global Companies that would compete for the tender would be happy to compete for the tender if strong internet facility is available in the zone. It will create a stronghold of the management with real time exploration possible remotely at regional and head offices. Real time exploration will help in faster decision making and fasten the problem solving processes with aid quick aid from officers at regional and head offices during the hectic workload of excavation and disposal of riverbed material.

6. We intend to transport the riverbed material from excavation site to a storage place within 5Km from excavating river. Then we would store the riverbed material at these storage sites until disposed off finally. We also need to pay rent to landowners until riverbed material is disposed. We also need to bear cost of logistics and transportation and other overheads.

So we need to be well aware of money we would be paid by government for transportation of material from riverbed to storage site within 5Km in amount of money per cubic meter of riverbed material transported to storage site, along with terms and conditions of payment. We also need to know the amount of money government would be paying us for disposal of materials from storage sites in amount of money per cubic meter of material disposed along with terms and conditions of payment.

Contact Person: Sudarshan Gupta 09051451367

Yours Faithfully, Brijnandan Gupta Director Lokenath Estate & Export Pvt Ltd 08420494499

Annexure- 21: MoM with Brick Kiln Owners Regarding Utilization of Desilted Material



Proceeding of meeting held at the chamber of the Additional District Magistrate and District Land & Land Reforms Officer, Hooghly on 09.08.2018 in connection with utilization of earth of silt to be excavated from Mundeswari River in dredging process in block Jamalpur, District- Purba Bardhaman and block Arambagh and Pursurah, District- Hooghly.

The following members were present in the meeting :

- 1) ADM & DL & LRO, Hooghly
- 3) Deputy DL & LRO-I, Hooghly
- 5) Office-in-Charge, M.M. Section
- 2) Executive Engineer, Hooghly Irrigation Division
- 4) Deputy DL & LRO-II, Hooghly
- 6) Representatives of Brick Field Owners Association

ADM & DL & LRO, Hooghly took the chair and invited discussion. Executive Engineer Hooghly District, Irrigation Department narrated the details before the members of the different Brick Field Owners Association. He explained that huge silt will be removed from the bed of Mundeswari River and same will be deposited in selected places within 0-5 KM distance from the both banks of river. Some selected roads will be developed for frequent to and fro movement of trucks which also may be used by brick field owner, for plying and loading their trucks. After narrating in details Executive Engineer invited Brick Field Association members to inform him the approximate number of brick fields interested to collect the silt, total yearly requirement of earth by them so that an assessment of their tentative need of earth be made.

On the other hand, members of the Brick Field Owners Association clarified that they are in dire need of brick earth and they are agreed to fetch the excavated earth if that earth be suitable for manufacture of bricks and contain less proportion of sand. They expressed the need of testing the suitability of the soil for brick manufacturing by way of boring in at least three places within the project area. After that they would be able to give tentative estimation of the earth to be consumed by the brick field.

Executive Engineer agreed to hold the boring from their end in presence of the Brick Field Owners Association members so that the issue may be amicably settled.

ADM & DL & LRO, Hooghly requested both the Executive Engineer and the members of the Brick Field Owners Association to settle the issue at the earliest possible. ADM & DL & LRO, Hooghly also requested the Executive Engineer to provide the copy of the map of respective area of excavation and connecting roads therein and also a copy of the report relating to soil testing after boring.

As there is no further issue to discuss the meeting ended with thanks to and from the Chair.

Kı

Additional District Magistrate & District Land & Land Reforms Officer, Hooghly Contd.....2 Memo No.1X-08/Earth Extr. Mundeswari/ 4716/(9) /MM.

Copy forwarded to:-

- 1) The District Magistrate, Hooghly for kind information.
- 2) The Executive Engineer, Hooghly Irrigation & Waterways Division, Hooghly.
- The Secretary, Bengal Brick Field Owners' Association, 23-A, Netaji Subhas Road (3rd floor), Kolkata-700001.
- The Secretary, Pandua Thana Brick Field Owners' Association, 20,Bose para Lane, Serampore, Mahesh,Hooghly.
- The Secretary, Kalna Road Brick Field Owners' Association, Pandua-Kalna Road, P.O & P.S.Pandua, Hooghly.
- The Secretary, Hooghly District Brick Manufacturers' Association, G.T Road, Taldanga, Chandannagore, Hooghly
- The Secretary, Ballykhal Brick Field Owners' Association, Ramsita Mandir P.O. -Makhla Hooghly
- The Secretary, Bhadrakali-Kotrang-Konnagore Brick Field Owners' Association, 9,G.T Road, (West) Konnagore, Hooghly-712235.
- The President / Secretary, Arambagh Sub-Division Brick Field Owners' Association, Gourhati More(RN-24), Arambagh, Hooghly.

Additional District Magistrate & District Land & Land Reforms Officer, Hooghly

Annexure- 22: List of Activity Require Regulatory Clearance

Contractor as well as owner has to obtain certain kind of prior permission for different activity to be carried out during project implementation. List of activity for which permission need to be obtained from different govt agency are listed below


SI.	Clearance Required	Applicable	Issuing	Requirement	Responsibility
No.	-	Regulation	Authority	-	
1	Consent to Establish (CtE) and Operate (CtO)	Water (Prevention and Control of Pollution) Act, 1974 and Air (Prevention and Control of Pollution) Act, 1981	WBSPCB	Consent shall be obtained before commencement of construction work for the plant and machinery (Hot Mix, WMM, Batching, Crusher, and Diesel Generator greater than 15 KVA) required for the project.	Contractor
2	Tree Cutting	West Bengal Trees (Protection and Conservation in Non-Forest Areas) Act, 2006 and Rules, 2007	Department (State DFO)	Permission shall be obtained before felling of tree.	Respective DPMU
3	Establishment of Camp		Local GP or authority	Permission for establishing labour camps	Contractor
4	Storing and dumping of waste materil		authority	Temporary storing or dumping of waste material (C&D waste, Desilted material)	Contractor
5	Pollution Under Control Certificate	Motor Vehicles Act, 1988	State Transport Authority	Vehicles and machineries shall comply with the Motors Vehicle act and submit pollution under control (PUC) certificate	Contractor

Table 10: Regulatory clearance to be obtained before commencement of different activity

Inland Surface Water (Class C)		Inland Surface Water (Class C) Ground Water A		A	mbient Air Quality (AAQ)	Soil Quality Testing	
	(IS: 2296-1982)	()	BIS 10500 : 1991)		(NAAQS)- 2009		
Sl.	Parameters	Sl.	Parameters	Sl.	Parameters	Sl.	Parameters
No.		No.		No.		No	
1	pH Value	1	Colour	1	PM10	1	pН
2	Dissolved Oxygen	2	Odour	2	PM _{2.5}	2	Electrical Conductivity
3	Biochemical Oxygen Demand (3 days at 27 ⁰ C)	3	Turbidity	3	Sulphur Dioxide (SO2)	3	Organic Carbon
4	Total Coliforms (TC)	4	рН	4	Nitrogen Dioxide (NO2)	4	Texture
5	Colour	5	Total Hardness	5	Ozone (O3)	5	Phosphorous as P
6	Fluoride (as F)	6	Iron (as Fe)	6	Lead (Pb)	6	Potassium as K
7	Cadmium (as Cd)	7	Chloride (as Cl)	7	Carbon Monoxide (CO)	7	Sulphur as S
8	Chloride (as Cl)	8	Residual Free Chlorine	8	Ammonia (NH3)	8	Calcium as Ca
9	Chromium (Cr 6+)	9	Dissolved Oxygen (DO)	9	Benzene (C6H6)	9	Magnesium as Mg
10	Total Desolved Solid (TDS)	10	Calcium (as Ca)	10	Benzo(a)Pyrene (BaP)	10	Chromium as Cr
11	Sulphates (SO4)	11	Copper (as Cu)	11	Arsenic (As)	11	Lead as Pb
12	Lead (as Pb)	12	Manganese (as Mn)	12	Nickel (Ni)	12	Zinc as Zn
13	Coppur (Cu)	13	Sulphate (as SO4)			13	Cadmium as Cd
14	Arsenic (as As)	14	Nitrate (as NO3)			14	Arsenic as As
15	Iron (as Fe)	15	Fluoride (as F)			15	Fluoride as F
16	Phenolic Compound (C6H5OH)	16	Cadmium (as Cd)			16	Nickel as Ni
17	Zinc (as Zn)	17	Arsenic (as As)			17	Mercury as Hg
18	Anionic detergent (MBAS)	18	Lead (as Pb)			18	Boron as B
19	Oil & Grease	19	Zinc (as Zn)			19	Copper as Cu
20	Nitrate (as NO ₃)	20	Chromium (Cr 6+)			20	Iron as Fe
		21	Boron (as B)			21	Manganese as Mn
						22	Molybednum as M


Annexure- 23: Parameters for Air, Surface & Ground Water, Soil quality Monitoring during Project Implementation


Annexure- 24: Map showing future monitoring location during construction and Operation stage



:	Project Name:	Name of Consultancy Firm :	Drawn By:	B. Das	Drawing Title:-	Drawing No.:	Date:
	Preparation of Feasibility Study, Detailed Engineering Design and	Entico Sonviolos do Indoniorio S.L. (Snoin	Checked By:	D. K. Maiti	Proposed Interventions of Flood	EIPL/MAP/DFSR/08	July-2018
of West Bengal ways Department	Bidding Documents for Irrigation Rejuvenation and Flood Management in the Damodar Command Areas and Lower Damodar Sub-Basin in the State of West Bengal in India (WBMIEMP)	0 (1)			Modernization	EIFL/WAF/DF3R/00	Revised
	Sub-Basin in the State of West Bengal in India (WBMIFMP)	Epuzo Eptisa India Pvt. Ltd.	Approved By:	R. Chakraborty			R0

	December inter Output inter
Name of Client :	Project Name:
Government of West Bengal Irrigation & Waterways Department	Preparation of Feasibility Study, Detailed Engineering Design and Bidding Documents for Irrigation Rejuvenation and Flood Management in the Damodar Command Areas and Lower Damodar Sub-Basin in the State of West Bengal in India (WBMIFPM)





Behula River

	LEGEND			
	Proposed Stabilization of	of Slope		
	DV Gross Command Ar	rea	0	
	District Boundary			
	Block Boundary			
	Irrigation Canals			
	Rivers and Drainage Ch	nannels		
ior	n of Slope	Drawing No.:		Date: July-2018
		EIPL/MAP/[DFSR/07	Revised R0

Annexure- 25 (a): Format for Monthly & Quarterly E&S Monitoring Report on **ESMP** Implementation

(To be filled by separately by 1) Contractor (monthly) and 2) the Jr. Environmental and Social Safeguard Specialist at DPMU level (Quarterly)

Monthly/ Quarterly Report

Reporting Period:

I.	Package Description	
1.1	Contract Package	
1.2	Name of the Contractor	
1.3	Name of the project component	
	and activity	
1.4	Work Completed for the Month	Earth work/ Concrete work/ Masonry / Flood Wall/ PCC
		lining
		Others Specify

II. Est	I. Establishment of Contractors Camp - Yes / No			Yes / No	
1 U	Jsage of Camp -		Plant / Machines/ Labour		
1.	1 If Plant -		Crusher u	nit/ HMP/ WMM / Any Other	
1.2 If Machinery stocking - Yes / No				Yes / No	
Sl.N0	Type of Machinery in	Number	Fitness/ PCB	Remarks – Repaired at camp /	
	Operation		certificate obtained	sent to Garage	
1	Paver				
2	Rollers				
3	Excavators				
4	Dumpers				
5	Vehicles (Tractors/				
	Trucks)				
6	Others (mention)				
7					
8					
9					
10					
11					
	•			·	

	1.3 Labour -			Permanent / Transit
S.No	Particulars	Remarks		
i	Total Number of Labourers employed?	ST:	SC:	Others:
ii	Number of Male labourers?	ST:	SC:	Others:
iii	Number of female labourers?	ST:	SC:	Others:
iv	Number of local labourers?	ST:	SC:	Others:
v	Name the village from where the labour comes from?			
vi	Number of migrant labourers?			
vii	Number of dwelling units in the camp?			

viii	Type of dwellings?	Pucca :Number
		Kutcha :Number
ix	Water Supply provided?	
х	Drinking water supply provided?	Tube well/ Open Well/ Tanker/ supply water etc
xi	Number of Toilets provided?	
xii	Type of Toilet?	Leach pit / Soak Pit / Septic tank
xii	Number of Bath rooms provided?	
xiii	Separate Bath rooms provided for women?	Yes / No
xiv	Washing platforms provided?	
XV	Drainage facility provided?	
xvi	Crèche facility provided?	
xvii	Availability of Health centre?	Nearest
xviii	First Aid Facility Available?	
xix	Health Camp / HIV awareness conducted?	Yes / No
		If yes provide details
XX	Fuel used in the Camp?	Fire wood/ Kerosene/ LPG
xxi	Does the Camp have Workshop for Repair?	Yes / No
xxii	Any Oil Spill taking Place?	Yes / No
xxiii	Oil / Grease traps / solid plat forms provided?	Yes / No

- 1.4.1 Storage of Fuel
- 1.4.2 Type of Fuel Stored?
- 1.4.3 License Obtained?
- 1.6 Any Blasting Material Stored?
- 1.6.1 License Obtained ?

III. Haulage Road

IV.

Existing Road/ Temp Road Created

Temporary/ Permanent

HSD/ Petrol

Yes/ NO

Yes/ NO

Yes/ NO

- 1. Maintenance of Haulage Road done?
 Yes / No

 2. Dust Suppression Measures taken?
 Yes / No

 Quarries Under Operation
 Yes / No
- 1. If Yes, Number of Quarries in Use and locations?
- 2. If No, Name of Vendor, from whom the material Purchased (SPCB Certificate of Vendor to be enclosed)
- 3. Are the Vehicles used for Supplying material were covered ? Yes / No
- V.
 Erosion Control Measures:
 Silt Traps/ Construction in Lean Season / Compaction Taken up

 VI.
 Dump Sites:
 Identified Yes / No

 VI.
 Dump Sites:
 Identified Yes / No

 Low lying areas Used Yes/ No
 Disposal Sites identified Yes/ No

 VIII.
 Storage of Material:
 Adj . to Canal / ROW/ Agri. Land / etc.

 1.
 Blockage of Natural drains
 Yes / No

IX. Dust Control Measure:

S.No.	Measure	Remarks
1	Dust control devices are available	Yes/ No
2	Sprinkling of water carried out.	Yes/ No

3	Cover on the vehicles	Yes/ No
4	Cover on stack materials	Yes/ No

X. Noise Control Measure:

S.No.	Measure	Remarks
1	Machines establishes in Habitation	Yes / No
2	Away from Habitations	Yes / No
3	Machines Sent for Maintenance regularly	Yes / No

XI. Safety Measures Taken:

S.No.	Measure	Remarks
1	Whether first aid post established at site?	Yes/No
2	Whether safety helmets given to all workmen at site?	Yes/No
3	Whether safety belts / ribbons used at work site	Yes/No
4	Whether gum boots, tarring unfits, spectacles etc. given to person handling	Yes/No
	bitumen?	

XII. Environmental Monitoring Details

Sl.No	Type of Test	Number of	Date of Test	Remarks
		Locations	(last conducted)	
1	Air Quality			
2	Noise Quality			
3	Ground Water			
4	Surface Water			
5	Soil/ Silt			

Signature of the Contractor/Sr. Environmental SpecialistSignature of the PDName of the SpecialistName of the PDDateDate Verified

Environmental & Social Management Plan (EMP) Implementation Data

(To be filled by separately by 1) Contractor (monthly) and 2) the Jr. Environmental and Social Safeguard Specialist at DPMU level (Quarterly)

1. Details of Statutory Clearance

No	Name of the project component	Name of the Contract Package	Date of Agreement	Date of Completion	Date of Commence ment of	Permission from State Forest Dept*	Labour License Details Validity*		s Insurance undertaken validity*	
	and activity	_			Civil work		From	То	From	То

(Note: * Attach relevant papers)

2. Details of Quarries / Vendors

No	Name of the	Name of the	Quarries	Name of Vendors	Details of Vendors Environmental Clearances Validity*				*	
	project	Contract	Establishe		Sand		Stone Products		Bou	lders
	component and	Package	d (YES/							
	activity		NO)							
					From	То	From	То	From	То

(Note: * Attach relevant papers)

3. Details of Environmental Monitoring / Testing

No	Name of the project component and	Name of the Contract Package	Env. Mo	nitoring / Testing par	rticulars*
	activity		Parameters	No. of locations Samples tested	Date of Testing
			Air Quality		
			Noise Quality		
			Ground Water		
			Surface Water		
			Soil/ Silt		

(Note: Env. Testing should be from the Approved Laboratory as mentioned in the ESIA including ESMP report

* Attach relevant papers)

Signature of the Contractor/ Jr. Environmental Specialist Name Date Signature of the APD Name of the APD Date Verified

Annexure- 25 (b): Format for SPMU's Half Yearly E&S Management Monitoring Report

(This format will also be used for Mid-term and End-term Audit)

Chapter I: Project Background:

- 1.1 Project Overview and Contextual Relevance
- 1.2 Project Development Objectives
- 1.3 Project Components and Activities
- 1.4 Environmental Management Framework
- 1.5 Social Management Framework

Chapter II: Regulatory Requirement and Compliances

2.1 Environmental Regulatory Requirements and Compliances (Project Specific)

- 2.1.1 Consent to Establish and Consent to Operate under Air & Water Pollution
- 2.1.2 Letter of Authorization for handling hazardous Waste (if applicable)
- 2.1.3 Tree cutting permission from DFO
- 2.1.5 Clearance for Disposal of Dredged materials from WBPCB
- 2.1.6 Agreement letter with Pvt. Land owner for borrowing earth (if required)
- 2.1.7 GP Clearance for establishment of Labour Camp and Temporary Disposal of Waste aterial
- 2.1.8 PUC Compliance / Certificate from RTO
- 2.1.9 Authorization / Permission of Material Supplier
- 2.1.10 Any other compliances that are required

2.2 Social Regulatory Requirements and Compliances

- 2.2.1 SIA Notification (if land acquisition is involved)
- 2.2.2 Notification for Land Acquisition (as per LARR Act), if any
- 2.2.3 Labour License
- 2.2.4 Any other compliances that are required

Chapter III: Environmental Performance

- 3.1 Soil Pollution
- 3.2 Water Pollution
- 3.3 Noise Pollution
- 3.4 Waste Management / Sediment Disposal & Management
- 3.5 Pest Management
- 3.6 Management of Flora and Fauna / Local Bio-diversity
- 3.7 Physical Cultural Resources, its Protection and Management

Chapter IV: Social Performance

- 4.1 People's Understanding and Awareness of the Project
- 4.2 Land Acquisition, Rehabilitation and Resettlement (if required)
- 4.3 Gender Inclusion
- 4.4 Tribal Inclusion and Safeguards
- 4.5 Project Impact on Vulnerable Groups
- 4.6 Safety and Security of Workers

Chapter V: Monitoring and Supervision

- 5.1 Monitoring of Environmental Parameters and Measures Taken
- 5.2 Monitoring of Social Parameters and Measures Taken

Chapter VI: Information Disclosure, Consultation, and Participation

Chapter VII: Grievance Redress Mechanism (GRM)

Chapter VIII: Conclusions and recommendations

Annexure I: List of Documents Reviewed and Verified

Annexure II: List of Project Sites Visited and Consultations

Annexure- 26: Terms of Reference (ToR) for Position of Environmental Expert at SPMU and DPMU

Annexure- 26.A ToR for Senior Environmental Specialist

Position: Senior Environmental Specialist **No. of Position**: One

Project Description:

To improve the existing irrigation network, optimizing conjunctive and sustainable use of ground and surface water across in the project area and throughout the year, and to reduce flooding The Government of West Bengal (GoWB) has proposed "West Bengal Major Irrigation and Flood Management Project (WBMIFMP)". The Government of West Bengal (GoWB) has applied for USD 290 million financing from the International Bank for Reconstruction and Development (IBRD) and from the Asian Infrastructure Investment Bank (AIIB) towards the cost of the WBMIFMP.

The project aims at modernization of irrigation system, with special emphasis on conjunctive use of ground and surface water in the Damodar Valley Project Command Area of the State, in the districts of Purba & Paschim Burdwan, Bankura, Hooghly and Howrah and improvement of flood management infrastructure in Lower Damodar Sub-basin, mainly in the districts of Hooghly and Howrah. Prime objective of proposed project is to rejuvenate and rehabilitate existing irrigation network for sustainable development in DVC area and management of floods in Lower Damodar Sub-Basin in West Bengal. Proposed project has mainly four broader objectives namely 1) *Irrigation Modernization, 2) Irrigation Management, 3) Flood Management and 4) Crop Diversification.* Project will also promote conjunctive use of surface and ground water for agriculture. The expected results of the project are to improve irrigation in order to benefit agriculture in the DVCA, and to reduce annual flooding in the Lower Damodar sub-basin area.

Project Duration:

The project duration is for five years.

Project Area:

The project will be implemented in selected locations five districts of West Bengal, namely East & West Bardhaman, Bankura, Hooghly and Howrah.

Scope for Senior Environmental Specialist:

Senior environmental expert will be responsible for providing input and guidance on implementation of environmental management and safeguards to the contractor, DPIU and DPMU/ SPMU and assisting in building environmental management capacity of SPMU, DPMU, DPIU, line departments - Department of Food Processing Industries and Horticulture, Agriculture Marketing Dept., Agriculture Dept. and Fisheries Department.

Specific focus of the assignment

Specifically, the Senior Environmental Specialist will:

- (i) Ensure the necessary national environmental approvals are obtained in a timely manner to advance project implementation;
- (ii) Review of site specific management plan prepared by contractor;
- (iii) Prepare site specific environmental performance criteria;

- (iv) Monitor the update and implementation of project activity specific 'ESMPs;
- Monitor routine environmental monitoring activities as defined in Environmental and Social Monitoring Plan;
- (vi) Monitor project activity sites against any unexpected environmental impacts;
- (vii) Advise Contractor, SPMU, DPMU on environment problems and/ or requirements, and recommend mitigating measures;
- (viii) Prepare environmental monitoring reports on ESMP implementation and compliance and submit it to the World Bank;
- (ix) Take part in project performance monitoring and evaluation activities; and
- (x) Assess and prepare capacity building program on environmental issues at the SPMU,
 DPMU, DPIU, line departments Department of Food Processing Industries and
 Horticulture, Agriculture Marketing Dept., Agriculture Dept. and Fisheries Department.
- (xi) Arrange and participate in safeguard review missions by the World Bank and AIIB.
- (xii) Liaise with the West Bengal State Pollution Control Board, Biodiversity Board, all line departments on project-related environmental issues;

Professional Profile:

- 1. Master degree in environmental science/ management.
- 2. Minimum 15 years of professional experience of working in assessing environmental impact and monitoring environment safeguards.
- 3. Familiarity with the World Bank's, ADB's, IFC's environmental guidelines is preferred.
- 4. Experience in similar irrigation projects and geographic areas are an added advantage.
- 5. Proficiency in both written and spoken English, and knowledge of locally spoken language Bengali are an advantage
- 6. Experience of working in rural areas and willingness to travel to project areas / locations;
- 7. Knowledge on Project Management principles;
- 8. Efficiency in computer Knowledge;
- 9. Having proficient communication Skill in English, including preparation of reports, documents, IEC materials etc. in English;
- 10. Prior experience of working in similar projects will be an added advantage.

Age Limit:

Maximum age limit is 45 years;

Reporting:

The Specialist would report to the Project Director or any person designated as Reporting Authority by the Project Director, WBMIFMP on monthly, quarterly and annual basis.

Work Station:

The Specialist would be based in the WBMIFMP Project office at the State Headquarters and would make at least 10 field visits or field visits as per the requirement in every month to project sites. However, if so wished and found necessary by the Project Director, she / he may be placed at the DPMU level for required period of time, to be specified by the SPMU of WBMIFMP.

Duration of Engagement:

The Specialist would be engaged initially for a period of 1 year on full time and contractual basis. The engagement period may be extended subject to satisfactory performance and mutual consent of the SPMU-WBMIFMP and the Specialist, not exceeding the project period.

Annexure- 26.B ToR for Environmental Specialist

Position: Environmental Specialist (Jurior) **No. of Position**:

Project Description:

To improve the existing irrigation network, optimizing conjunctive and sustainable use of ground and surface water across in the project area and throughout the year, and to reduce flooding The Government of West Bengal (GoWB) has proposed "West Bengal Major Irrigation and Flood Management Project (WBMIFMP)". The Government of West Bengal (GoWB) has applied for USD 290 million financing from the International Bank for Reconstruction and Development (IBRD) and from the Asian Infrastructure Investment Bank (AIIB) towards the cost of the WBMIFMP.

The project aims at modernization of irrigation system, with special emphasis on conjunctive use of ground and surface water in the Damodar Valley Project Command Area of the State, in the districts of Purba & Paschim Burdwan, Bankura, Hooghly and Howrah and improvement of flood management infrastructure in Lower Damodar Sub-basin, mainly in the districts of Hooghly and Howrah. Prime objective of proposed project is to rejuvenate and rehabilitate existing irrigation network for sustainable development in DVC area and management of floods in Lower Damodar Sub-Basin in West Bengal. Proposed project has mainly four broader objectives namely 1) *Irrigation Modernization, 2) Irrigation Management, 3) Flood Management and 4) Crop Diversification.* Project will also promote conjunctive use of surface and ground water for agriculture. The expected results of the project are to improve irrigation in order to benefit agriculture in the DVCA, and to reduce annual flooding in the Lower Damodar sub-basin area.

Project Duration:

The project duration is for five years.

Project Area:

The project will be implemented in selected locations five districts of West Bengal, namely East & West Bardhaman, Bankura, Hooghly and Howrah.

Scope for Senior Environmental Specialist:

Environmental Expert will be responsible for providing input and guidance on implementation of environmental management and safeguards to the contractor, DPIU and DPMU/ SPMU and assisting in building environmental management capacity of SPMU, DPMU, DPIU, line departments - Department of Food Processing Industries and Horticulture, Agriculture Marketing Dept., Agriculture Dept. and Fisheries Department.

Specific focus of the assignment

Specifically, the Junior Environmental Specialist will:

- (i) Ensure the necessary national environmental approvals are obtained in a timely manner to advance project implementation;
- (xiii) Review of site specific management plan prepared by contractor;
- (xiv) Prepare site specific environmental performance criteria;

- (xv) Monitor the update and implementation of project activity specific 'ESMPs;
- (xvi) Monitor routine environmental monitoring activities as defined in Environmental and Social Monitoring Plan;
- (xvii) Monitor project activity sites against any unexpected environmental impacts;
- (xviii) Advise Contractor, SPMU, DPMU on environment problems and/ or requirements, and recommend mitigating measures;
- (xix) Prepare environmental monitoring reports on ESMP implementation and compliance and submit it to the World Bank;
- (xx) Take part in project performance monitoring and evaluation activities; and
- (xxi) Assess and prepare capacity building program on environmental issues at the SPMU, DPMU, DPIU, line departments - Department of Food Processing Industries and Horticulture, Agriculture Marketing Dept., Agriculture Dept. and Fisheries Department.
- (xxii) Arrange and participate in safeguard review missions by the World Bank and AIIB.
- (xxiii) Liaise with the West Bengal State Pollution Control Board, Biodiversity Board, all line departments on project-related environmental issues;

Professional Profile:

- 11. Master degree in environmental science/ management.
- 12. Minimum 8 years of professional experience of working in assessing environmental impact and monitoring environment safeguards.
- 13. Familiarity with the World Bank's, environmental guidelines is preferred.
- 14. Experience in other linear projects and geographic areas are an added advantage.
- 15. Proficiency in both written and spoken English, and knowledge of locally spoken language Bengali are an advantage
- 16. Experience of working in rural areas and willingness to travel to project areas / locations;
- 17. Knowledge on Project Management principles;
- 18. Efficiency in computer Knowledge;
- 19. Having proficient communication Skill in English, including preparation of reports, documents, IEC materials etc. in English;
- 20. Prior experience of working in similar projects will be an added advantage.

Age Limit:

Maximum age limit is 35 years;

Reporting:

The Specialist would report to the Additional Project Director (APD) at the District Project Management Unit (DPMU) level or any person designated as Reporting Authority by the APD-DPMU, WBMIFMP on monthly, quarterly and annual basis.

Work Station:

The Specialist would be based at the DPMU of WBMIFMP Project office at the District Headquarters and would make at least 15 field visits or field visits as per the requirement in every month to project sites. However, if so wished and found necessary by the APD, she / he may be placed at the DPIU level for required period of time, to be specified by the DPMU of WBMIFMP.

Duration of Engagement:

The Specialist would be engaged initially for a period of 1 year on full time and contractual basis. The engagement period may be extended subject to satisfactory performance and mutual consent of the DPMU / SPMU-WBMIFMP and the Specialist, not exceeding the project period.

Position: Senior Social cum Gender Development Specialist **No. of Position**: One

Project Description:

To improve the existing irrigation network, optimizing conjunctive and sustainable use of ground and surface water across in the project area and throughout the year, and to reduce flooding The Government of West Bengal (GoWB) has proposed "West Bengal Major Irrigation and Flood Management Project (WBMIFMP)". The Government of West Bengal (GoWB) has applied for USD 290 million financing from the International Bank for Reconstruction and Development (IBRD) and from the Asian Infrastructure Investment Bank (AIIB) towards the cost of the WBMIFMP.

The project aims at modernization of irrigation system, with special emphasis on conjunctive use of ground and surface water in the Damodar Valley Project Command Area of the State, in the districts of Purba & Paschim Burdwan, Bankura, Hooghly and Howrah and improvement of flood management infrastructure in Lower Damodar Sub-basin, mainly in the districts of Hooghly and Howrah. Prime objective of proposed project is to rejuvenate and rehabilitate existing irrigation network for sustainable development in DVC area and management of floods in Lower Damodar Sub-Basin in West Bengal. Proposed project has mainly four broader objectives namely 1) *Irrigation Modernization, 2) Irrigation Management, 3) Flood Management and 4) Crop Diversification.* Project will also promote conjunctive use of surface and ground water for agriculture. The expected results of the project are to improve irrigation in order to benefit agriculture in the DVCA, and to reduce annual flooding in the Lower Damodar sub-basin area.

Project Duration:

The project duration is for five years.

Project Area:

The project will be implemented in selected locations five districts of West Bengal, namely Purba& Paschim Bardhaman, Bankura, Hooghly and Howrah.

Need for Social cum Gender Development Specialist:

The Social Cum Gender Development Specialist will be primarily responsible for developing necessary strategy to ensure that the project is achieving its social development objective i.e. equity, inclusiveness and transparency by institutionalizing participatory process. The specialist will guide, mentor, monitor and evaluate the functioning and performance of social mobilization work, establishing systems to achieve the social development objectives of the project and work closely with environment expert and other key stakeholders of the project. One of the prime role of the specialist would be to ensure execution of social safeguards as per the Environment and Social Management Framework (ESMF) / Environment and Social Impact Assessment (ESIA).

Scope of Work:

- 1. Guide the project stakeholders and facilitatecollection and analysis of social, cultural and economic information that are relevant to the project and in line with the ESMF / EIA requirements;
- 2. Support in institutionalising the social safeguard parameters, as per ESMF / EIA in project framed activities;
- 3. Conduct periodic field visits and consult / discuss with the local community organisations / associations of farmers and related other stakeholders, as identified in the project;

- 4. Discuss with contractors and associated Govt. Departments from time to time to ensure that gender balance and inclusive approach is adopted in project activities;
- 5. Facilitate in increasing participation of women in construction and other project activities;
- 6. Coordinate, organise and impart training on social safeguard measures to be taken for different category of stakeholders;
- 7. Prepare, design and conduct workshop/seminar for the project staff and other stakeholders on social development aspects, mapping of indicators and appraising the learning cases;
- 8. Facilitate collection of gender disaggregated data and conduct analyse of project benefits by social, economic and sex (male / female) categories;
- 9. Facilitate documentation of learning cases with regard to social safeguard measures / practices and its wider dissemination;
- 10. Preparation of leaflets / pamphlets / IEC materials for sensitisation of stakeholders and community on the project benefits and its socio-economic dimensions;
- 11. Conduct period review meetings with the stakeholders, including Government Departments to ensure gender inclusion and equity aspects of project activities along with key achievements as per the social indicators.
- 12. Conducting internal monitoring and evaluation of project activities and mapping the progress in line with the social indicators.
- 13. Collate the internal monitoring reports for M&E of the project and preparing internal monitoring reports, covering social management aspects of the project;
- 14. Periodic appraisal of progress in line with the social safeguard to the project director;
- 15. Carrying out other activities as assigned by the PD-SPMU or designated person of SPMU.

Professional Profile:

- 21. Master's degree in Sociology/Anthropology/ Social work.
- 22. At least 15 years of professional experience of working in related field of rural development programme/ Irrigation Improvement Project of Govt. or Non-government organization.
- 23. Fluency in English and workable knowledge of Bengali is an added advantage;
- 24. Experience of working in rural areas and willingness to travel to project areas / locations;
- 25. Knowledge on Project Management principles;
- 26. Efficiency in computer Knowledge;
- 27. Having proficient Communication Skill in English, including preparation of reports, documents, IEC materials etc. in English;
- 28. Prior experience of working in similar projects will be an added advantage.

Age Limit:

Maximum age limit is 55 years;

Reporting:

The Specialist would report to the Project Director or any person designated as Reporting Authority by the Project Director, WBMIFMP on monthly, quarterly and annual basis.

Work Station:

The Specialist would be based in the WBMIFMP Project office at the State Headquarters and would make at least 10 field visits or field visits as per the requirement in every month to project sites. However, if so wished and found necessary by the Project Director, she / he may be placed at the DPMU level for required period of time, to be specified by the SPMU of WBMIFMP.

Duration of Engagement:

The Specialist would be engaged initially for a period of 1 year on full time and contractual basis. The engagement period may be extended subject to satisfactory performance and mutual consent of the SPMU-WBMIFMP and the Specialist, not exceeding the project period.

Position: Social (Juniou) cum Gender Development Specialist **No. of Position**: Two

Project Description:

To improve the existing irrigation network, optimizing conjunctive and sustainable use of ground and surface water across in the project area and throughout the year, and to reduce flooding The Government of West Bengal (GoWB) has proposed "West Bengal Major Irrigation and Flood Management Project (WBMIFMP)". The Government of West Bengal (GoWB) has applied for USD 290 million financing from the International Bank for Reconstruction and Development (IBRD) and from the Asian Infrastructure Investment Bank (AIIB) towards the cost of the WBMIFMP.

The project aims at modernization of irrigation system, with special emphasis on conjunctive use of ground and surface water in the Damodar Valley Project Command Area of the State, in the districts of Purba & Paschim Burdwan, Bankura, Hooghly and Howrah and improvement of flood management infrastructure in Lower Damodar Sub-basin, mainly in the districts of Hooghly and Howrah. Prime objective of proposed project is to rejuvenate and rehabilitate existing irrigation network for sustainable development in DVC area and management of floods in Lower Damodar Sub-Basin in West Bengal. Proposed project has mainly four broader objectives namely 1) *Irrigation Modernization, 2) Irrigation Management, 3) Flood Management and 4) Crop Diversification.* Project will also promote conjunctive use of surface and ground water for agriculture. The expected results of the project are to improve irrigation in order to benefit agriculture in the DVCA, and to reduce annual flooding in the Lower Damodar sub-basin area.

Project Duration:

The project duration is for five years.

Project Area:

The project will be implemented in selected locations five districts of West Bengal, namely Purba& Paschim Bardhaman, Bankura, Hooghly and Howrah.

Need for Social cum Gender Development Specialist:

The Social Cum Gender Development Specialist will be primarily responsible for developing necessary strategy to ensure that the project is achieving its social development objective i.e. equity, inclusiveness and transparency by institutionalizing participatory process. The specialist will guide, mentor, monitor and evaluate the functioning and performance of social mobilization work, establishing systems to achieve the social development objectives of the project and work closely with environment expert and other key stakeholders of the project. One of the prime role of the specialist would be to ensure execution of social safeguards as per the Environment and Social Management Framework (ESMF) / Environment and Social Impact Assessment (ESIA).

Scope of Work:

- 1. Establish regular field contact and rapport building with the local community where the project will be executed;
- 2. Guide the project stakeholders and facilitatecollection and analysis of social, cultural and economic information that are relevant to the project and in line with the ESMF / EIA requirements;

- 3. Support in institutionalising the social safeguard parameters, as per ESMF / EIA in project framed activities;
- 4. Conduct periodic field visits and consult / discuss with the local community organisations / associations of farmers and related other stakeholders, as identified in the project;
- 5. Discuss with contractors and associated Govt. Departments (district level / DPIUs) from time to time to ensure that gender balance and inclusive approach is adopted in project activities;
- 6. Facilitate in increasing participation of women in construction and other project activities;
- 7. Coordinate, organise and impart training on social safeguard measures to be taken for different category of stakeholders;
- 8. Collection of gender disaggregated data and analyse of project benefits by social, economic and sex (male / female) categories;
- 9. Documentation of learning cases with regard to social safeguard measures / practices;
- 10. Preparation of leaflets / pamphlets / IEC materials in Bengali for sensitisation of stakeholders and community on the project benefits and its socio-economic dimensions;
- 11. Conduct period review meetings with the stakeholders, including Government Departments to ensure gender inclusion and equity aspects of project activities along with key achievements as per the social indicators.
- 12. Conducting internal monitoring of project activities and mapping the progress in line with the social indicators.
- 13. Periodic appraisal of progress in line with the social safeguard to the APD-DPMU and Senior Social Cum Gender Development Specialist of the SPMU;
- 14. Carryng out other activities as assigned by the APD-DPMU and Senior Specialist of SPMU.

Professional Profile:

- 1. Master's degree in Sociology/Anthropology/ Social work.
- 2. At least 7 years of professional experience of working in related field of rural development programme/ Irrigation Improvement Project of Govt. or Non-government organization.
- 3. Fluency in Bengali and English;
- 4. Experience of working in rural areas and willingness to travel to project areas / locations;
- 5. Knowledge on Project Management principles;
- 6. Efficiency in computer Knowledge;
- 7. Having proficient Communication Skill, including preparation of reports, documents etc. in Bengali and English;
- 8. Prior experience of working in similar projects will be an added advantage.

Age Limit:

Maximum age limit is 40 years;

Reporting:

The Specialist would report to the Additional Project Director (APD) at the District Project Management Unit (DPMU) level or any person designated as Reporting Authority by the APD-DPMU, WBMIFMP on monthly, quarterly and annual basis.

Work Station:

The Specialist would be based at the DPMU of WBMIFMP Project office at the District Headquarters and would make at least 15 field visits or field visits as per the requirement in every month to project sites. However, if so wished and found necessary by the APD, she / he may be placed at the DPIU level for required period of time, to be specified by the DPMU of WBMIFMP.

Duration of Engagement:

The Specialist would be engaged initially for a period of 1 year on full time and contractual basis. The engagement period may be extended subject to satisfactory performance and mutual consent of the DPMU / SPMU-WBMIFMP and the Specialist, not exceeding the project period.

Annexure- 27: Guidance on Chance Find Procedures

(To be annexed to the EMP for All Construction and Dredging Works)

1. PCR Definition

Physical Cultural Resources (PCR) refer to: "movable or immovable objects, sites, structures or groups of structures having archaeological, paleontological, historical, architectural, religious, aesthetic, or other cultural significance".

2. Procedure upon Discovery

Suspension of Work

If a PCR comes to light during the execution of the works, the contractor shall stop the works. After stopping work, the contractor must immediately report the discovery to the respective APD (III or IV) at DPMU level. The contractor may not be entitled to claim compensation for work suspension during this period. The Resident Engineer may be entitled to suspend work and to request from the contractor some excavations at the contractor's expense if he thinks that a discovery was made and not reported.

Respective APD (III or IV) at DPMU level immediately inform PD at SPMU level regarding the discover. Depending on the magnitude of the PCR, PD at SPMU level should check with the Archaeological Survey of India (ASI) for advice on whether *all works* should be stopped, or only the works immediately involved in the discovery, or, in some cases where large buried structures may be expected, all works may be stopped within a specified distance (for example, 50 meters) of the discovery.

Demarcation of the Discovery Site

With the approval of the respective APD (III or IV) at DPMU level, the contractor is then required to temporarily demarcate, and limit access to, the site.

Non-Suspension of Work

The PD in consultation with the ASI will decide whether the PCR can be removed for the work to continue, for example in cases where the find is one coin.

Chance Find Report

The contractor should then, at the request of the respective APD (III or IV) at DPMU level, and within 7 days, make a *Chance Find Report*, recording:

- Date and time of discovery;
- Location of the discovery;
- Description of the PCR;
- Photo documentation of the PCR;
- Estimated weight and dimensions of the PCR;
- Temporary protection implemented.

The Chance Find Report should be submitted to the PD, ASI and other concerned parties as agreed with the ASI, and in accordance with national legislation. The PD is required to inform the ASI accordingly.

Arrival and Actions of Cultural Authority

The ASI will be requested to arrive at the discovery site within 24 hours, and determine the action to be taken. Such actions may include, but not be limited to:

- Removal of PCR deemed to be of significance;
- Execution of further excavation within a specified distance of the discovery point;
- Extension or reduction of the area demarcated by the contractor.

These actions should be taken within 5 days. The contractor may or may not be entitled to claim compensation for work suspension during this period.

If the ASI fails to arrive within the stipulated period, the PD may have the authority to extend the period by a further stipulated time. If the ASI fails to arrive after the extension period, the PD may have the authority to instruct the contractor to remove the PCR or undertake other mitigating measures and resume work. Such additional works can be charged to the contract. However, the contractor may not be entitled to claim compensation for work suspension during this period.

Further Suspension of Work

During this 5 day period, the ASI may be entitled to request the temporary suspension of the work at or in the vicinity of the discovery site for an additional period of up to, 15 days. The contractor may, or may not be, entitled to claim compensation for work suspension during this period.

Annexure- 28: ESMP Implementation Monitoring Plan by Project Activities

Expected Impact	Mitigation Measures	Monitoring Indicators	Means of Verification	Supervising and Monitoring Entity	Monitoring Frequency
B.1 & B.2 (common a					
	ying Capacity of Main, Branch and Distributaries cana				
I. Restoration of carry	ving capacity (Earth work for re-sectioning) of other M				
	The clearing of vegetation in sections will ensure only areas of the land to be developed at a particular time are exposed to agents of erosion. This will also ensure the	GBH cleared in different phases and area restored;	Physical Verification of Site;	DPIU	Weekly
	cleared areas of the land are not left bare over long periods as development at the cleared areas will be		Report of the Contractor;		
Top soil exposure due to denudation leading	carried out immediately. This will minimize erosion at	Quantum of earth (Cum) generated, percentage utilised and disposed-off.	Water Quality Report		
to soil erosion		Denuded area covered under plantation after construction (% of area)			
		Water quality in the working zone and deviations from the standards / baseline in different periods.			
	Contractor shall take reasonable precaution to prevent his workers from damaging any flora or fauna of the area specially during vegetation clearance.		Physical Verification of Site;	DPIU	Weekly
	Vegetation clearance shall be limited to portions of the canal to be excavated at a particular time. The entire land		Report of the Contractor;		
operation	will not be cleared at a time and this will allow any fauna to migrate to adjoining areas.		Consultation with locals		
			Physical verification of composting site/s		
to improper dumping	The management and disposal of this waste will be as follows (details are provided in the ESMP for waste management):	Usages of weeds along with hyacinths	Physical verification of site; Consultation with local community;	DPIU	Weekly
weeds (mostly water	Local community will be allowed to use the weeds for domestic use such as using it as fuel (shrub stem, root),		Review of quarterly report by contractor;		
unhygienic conditions,	animal fodder or for composting. Identification of temporary storage locations for drying and temporary storage of the aquatic weed waste in				
	consultation with the IWD site engineers and the local government authority. The locations will not be within				

Annexure- 28(a) ESMP Implementation Monitoring Plan for Irrigation Modernization

Expected Impact	Mitigation Measures	Monitoring Indicators	Means of Verification	Supervising and Monitoring Entity	Monitoring Frequency
	100 m of the identified Sensitive Receptors (listed in Table 36 under Section 4.16).				
	The Contract Package ESMP and Contractor's ESMP				
	will list and provide map of the identified locations.				
	Temporary storage of the aquatic weed waste at				
	identified locations for a period not exceeding 10 days.				
	Sale or free lifting of dry/semi-dry aquatic weed waste				
	for onward processing into compost, ropes (for handicrafts and furniture making), fodder, etc. The				
	Contract Package ESMP and Contractor's ESMP will				
	provide details of quantity to be disposed in this way				
	along with details of interested parties.				
	The following Dos and Don'ts are to be followed for				
	management of aquatic weed waste:				
	 The aquatic weed waste will not be stored at unauthorized locations. 				
	 Burning of aquatic weed waste is not to be 				
	undertaken.				
	• Dumping of aquatic weed waste at unauthorized				
	locations is not to be undertaken.				
	• In case on onward sale of the aquatic weed waste,				
	the sale agreement will include prohibition of				
	environmentally harmful practices (open burning of				
	semi-wet waste, dumping of waste residues in				
	unauthorized locations including water bodies, etc.).				
	Contractor shall not adopt practice of burning weeds;	Air quality in the work site and	Air quality report;	DPIU	Weekly
	Discouraging local community in burning of weeds;	aberration from standards.	Consultation with local	DITO	Weekiy
Air Pollution due to	Discouraging focul community in burning of weeds;		people / workers		
Burning of weeds		Usages of weeds along with hyacinths	Review of quarterly report		
			by contractor;		
	Most of the restoration work will be carried out when the		Site inspection / visit;	DPMU	Weekly
	canal bed is dry.	dewatering is done;	Consultation with farmer		
Flooding of nearby	Else, earthen bund shall be constructed for dewatering of		having land adjoining to		
agricultural field	active work zone;	dewatering; Crop compensation paid to affected	work site Review of quarterly report		
during dewatering	Canal water shall not be pumped out for dewatering purpose to nearby agricultural field to avoid any kind of	farmers.	by contractor;		
before re-sectioning	crop damage as well as agricultural field to avoid any kind of	larmers.	by contractor,		
	(although probability of land/ soil pollution is very low;				
	as this water is being used for irrigation purpose).				

Expected Impact	Mitigation Measures	Monitoring Indicators	Means of Verification	Supervising and Monitoring Entity	Monitoring Frequency
	Crop compensation shall be paid to affected farmers on occurrence of crop damage due to dewatering.				
Crop damage due to interrupted irrigation supply	Contractor shall submit work plan with canal closure timeline for each restoration site to DPMU at least before 45 days of any crop season; Restoration plan shall not be approved by DPMU, if not submitted at least 45 days prior to any crop season; Subsequent to receive and approve of work plan, farmers should be informed about canal closure plan at-least before 30 days of any crop season. Canal closure notice board shall be displayed at local panchayat/ irrigation/ fishery and BDO office.	Submission & approval of canal closure plan; Dissemination of canal closure plan	Review of canal closure plan Consultation with farmer having land adjoining to work site Review of quarterly report by contractor;	DPMU	Before each crop season
downstream canal water leading to	All earther bund constructed for dewatering purpose shall be removed and entire work zone shall be levelled properly before monsoon period to maintain natural canal flow, minimize soil and sediment transportation to downstream and water pollution. Immediate collection and clearance of excess muck/soil from canal bed to minimize the erosion potential and sediment transportation into canal water which may cause increased water turbidity or TDS;	levelling of work zone;	Site inspection / visit; Review of quarterly report by contractor; Analysis of water quality report	DPMU	Weekly (specially before monsoon) Quarterly
	Formulate and submit site specific temporary storing and reuse plan for generated earth material from re- sectioning.	Quantity of material generated, reused and disposed;	Review of plan/s;	SPMU	Weekly
generated earth on	Identification of temporary storage locations for the generated earth material in consultation with the IWD site engineers and the local government authority. The Contract Package ESMP and Contractor's ESMP will list and provide map of the identified locations. Temporary storage of the generated earth material at the identified locations for a period not exceeding 30 days. Muck may be stored on either side of embankment / canal bank and Government land along canal bank for temporary period; Storing of excavated material on nearby agricultural field shall be avoided to the extent possible;	Agricultural land (area in Ha.) affected due to stocking of materials; Provision of availability of alternative way, where ever required; Crop compensation paid	Physical observation; Consultation with affected farmers Report on amount of material excavated, used, dumped;	DPMU	Weekly

Expected Impact	Mitigation Measures	Monitoring Indicators	Means of Verification	Supervising and Monitoring Entity	Monitoring Frequency
	Generated earth material shall not be stored or dumped in unauthorized locations including water bodies and wetlands.				
	Available private land may be used for temporary stocking after discussion and willingness of the land owner;				
	The land owner will be paid compensation for the period of use of land;				
	Land should be restored to its previous condition after lifting excavated materials;				
	Bund shall be provided around storage area of muck to restrict littering and leaching.				
	Entire soil material shall be re-used for on-site and off- site works (such as canal backfilling, lining, levelling, embankment raising & strengthening, construction of				
	temporary diversion road, filling and levelling of access road) that require soil/ earth to the extent possible. Entire muck shall be reused before monsoon season;				
	Safe temporary access routes / by-pass route will be provided for community members to access their farms during the canal re-sectioning period, if no alternative is available.				
	Regular water sprinkling arrangement on desilted material specially during hot-summer season to maintain soil moisture and minimise dust pollution;	Arrangement of water sprinkling; Tarpaulin lining during transportation;	Site inspection; Community consultation	DPIU/ DPMU	Weekly
Dust and air pollution from flying of dried up earth generated from re-sectioning work	All truck shall be tarpaulin covered while transporting desilted material; At canal stretches in proximity of sensitive receptors, the following additional mitigation measures will be implemented: The Contract Package ESMPs and Contractors ESMPs will specify the list of sensitive receptors. (the list of sensitive receptors – educational institutions, healthcare institutions and etc. are provided in Table 36 under	Air quality near to the site and at habitation areas;			
	Section 4.16). Quarterly air quality monitoring shall be carried out at			M & E Agency	Quarterly
	the Sensitive Receptor locations.				
		Tarpaulin lining during transportation;	Grievances, if any; Community consultation	DPIU/ DPMU	Weekly

Expected Impact	Mitigation Measures	Monitoring Indicators	Means of Verification	Supervising and Monitoring Entity	Monitoring Frequency
Littering during transportation of excavated material	All transportation vehicle shall be provided lining arrangement while transporting muck to restrict littering on road.	Air quality near to the site and at habitation areas;	Air quality report		Quarterly
	of canal resectioning work due to construction of bund. However, fisher community may perform fishing on other part of canal, where bund is not constructed.	Submission & approval of canal closure plan; Dissemination of canal closure plan;	Review of canal closure plan	DPMU	Before construction of bund
Disturbance in fishing by local fisher community	Contractor shall submit work plan with canal closure timeline for each restoration site to DPMU at least before 45 days of construction of bund for dewatering purpose; Restoration plan shall not be approved by DPMU, if not submitted at least 45 days prior to initiation of work at	Grievance on fishing;	Site visit and consultation with local fisher community		Monthly
	each site; Subsequent to receive and approve of work plan, local fisher community should be informed about canal closure plan at-least before 30 days from bund construction. Canal closure notice board shall be displayed at local panchayat/ irrigation/ fishery and BDO office.				
	of Critically Affected Reaches of Main, Branch and Dis of critically affected reaches of Minor / Sub-minor (LV		ng (B.1)		
	ESMP for construction activity shall be applied				
Top soil exposure due to denudation leading to soil erosion	areas of the land to be developed at a particular time are exposed to agents of erosion. This will also ensure the cleared areas of the land are not left bare over long periods as development at the cleared areas will be carried out immediately. This will minimize arcsion at	phases and area restored; Quantum of earth (Cum) generated, percentage utilised and disposed-off. Denuded area covered under plantation after construction (% of area) Water quality in the working zone and deviations from the standards / baseline in different periods; Lining work initiated on cleared	Physical Verification of Site; Report of the Contractor; Water Quality Report	DPIU	Weekly
Impact on flora/ fauna during weed cleaning operation	Contractor shall take reasonable precaution to prevent his workers from damaging any flora or fauna of the area specially during vegetation clearance.	portion Quantum of weeds generated, its use and disposal	Physical verification of site; Review of quarterly report by contractor;	DPIU	Weekly

Expected Impact	Mitigation Measures	Monitoring Indicators	Means of Verification	Supervising and Monitoring Entity	Monitoring Frequency
	Vegetation clearance shall be limited to portions of the canal slope to be lined at a particular time. The entire land shall not be cleared at a time and this will allow any fauna to migrate to adjoining areas.		Consultation with locals		
Organic pollution due to improper dumping of removed weeds, shrub stems, stumps, roots, twinges and leave on canal side embankment leading to inconvenience to local commuters; odour pollution.	Possibility shall be explored to engage Food Processing Industries and Horticulture Department for using removed weed in vermi composting promoted under this project. The management and disposal of this waste will be as follows (details are provided in the ESMP for waste management): Local community will be allowed to collect the shrub stems, stumps, roots for use as fuelwood and fencing material and weeds for domestic use such as using it as fuel, animal fodder or for composting.	Quantum of weeds generated, its use and disposal;	Physical verification of site; Consultation with local community; Review of quarterly report by contractor;	DPIU	Weekly
	Identification of temporary storage locations for drying and temporary storage of the weed waste in consultation with the IWD site engineers and the local government authority. The locations will not be within 100 m of the identified Sensitive Receptors (listed in Table 36 under Section 4.16).				
	The Contract Package ESMP and Contractor's ESMP will list and provide map of the identified locations.				
	Temporary storage of the weed waste at identified locations for a period not exceeding 10 days.				
	Sale or free lifting of dry/semi-dry weed waste for onward processing into compost, ropes (for handicrafts and furniture making), fodder, etc. The Contract Package ESMP and Contractor's ESMP will provide details of quantity to be disposed in this way along with details of interested parties.				
	The following Dos and Don'ts are to be followed for management of weed waste:				
	 Weed waste will not be stored at unauthorized locations. Contractor shall not burn weed waste. Dumping of weed waste at unauthorized locations is not to be undertaken. In case on onward sale of the weed waste, the sale agreement will include prohibition of 				

Expected Impact	Mitigation Measures	Monitoring Indicators	Means of Verification	Supervising and Monitoring Entity	Monitoring Frequency
	environmentally harmful practices (open burning of semi-wet waste, dumping of waste residues in unauthorized locations including water bodies, etc.).				
Air Pollution due to Burning of weeds,	Contractor shall not adopt practice of burning weeds, shrub stems, stumps, roots, twinges and leave;	Air quality in the work site and aberration from standards.	Air quality test report;	DPIU	
shrub stems, stumps, roots, twinges and leave	Discouraging local community in burning of weeds, shrub stems, stumps, roots, twinges and leave;		Consultation with local people / workers	DPIU	Weekly
	Avoidance of tree cutting to the possible extent with locational and design alternatives;	No. of trees uprooted by at project site;	Physical verification by site inspection	SPMU	Quarterly
	Chainage wise requirement of tree felling shall be counted with their species;	No. of trees not falling in the working zone but uprooted;	Review of records / repots	DPMU	Monthly
	Consult with local community as well as DPIU in identifying suitable local indigenous tree species; available community land or Govt. vacant land for compensatory plantation.	No. of trees planted (compensatory afforestation) and zone of plantation;	Consultation with local community	DPMU	
	Tree felling shall be commenced only after obtaining permission from Dept. of forest.	Type of tree species planted and bio- diversity maintenance		DPMU	
Tree felling due to PCC lining activity	Shrub stems, stumps, roots shall be uprooted properly to eliminate any chance of void under PCC lining. Before taking civil measures, the surface area of the	Plant survival rate (newly planted saplings)		DPIU	
	ground to be occupied shall be cleared of all roots and vegetable matter and stripped to a suitable depth as per IS: 4701 – 1982.				
	To compensate loss of tree and to improve the local aesthetic value,			DPMU	
	Compensatory tree plantation at 1:5 ratio will be carried out.				
Loss of top soil	Generated small quantity of top soil shall be preserved and suitably reused for levelling, back filling purpose.	Quantum of top soil generated, percentage utilized and disposed-off;	Physical Verification of Site;	DPMU	Weekly
Loss of top soli	Top soil may be temporarily staked in either side of embankment for field reuse;	Denuded area covered under plantation after construction (% of area).	Review of quarterly report by contractor;		
Dust pollution due to	Regular water sprinkling shall be provided to maintain moisture content- which in turn will reduce dust pollution;	Record on water sprinkling	Report of the Contractor;	DPIU	Weekly
stocking of top soil on embankment site	In case of transportation of top soil, tarpaulin cover shall be provided to restrict dust pollution during transportation.	Tarpaulin cover during transportation	Record on days of water sprinkling done in non- monsoon seasons	DPIU	Weekly

Expected Impact	Mitigation Measures	Monitoring Indicators	Means of Verification	Supervising and Monitoring Entity	Monitoring Frequency
	At canal stretches in proximity of sensitive receptors, the following additional mitigation measures will be implemented:				
	The Contract Package ESMPs and Contractors ESMPs will specify the list of sensitive receptors. (the list of sensitive receptors – educational institutions, healthcare institutions and etc. are provided in Table 36 under Section 4.16).				
	Quarterly air quality monitoring shall be carried out at the Sensitive Receptor locations.				
Sediment transport in streams, canal, water bodies leading to increased TDS and turbidity	Immediate collection and clearance of excess muck/soil from canal slope/bed to minimize the erosion potential and sediment transportation into canal water which may cause increased water turbidity or TDS. Slopes of embankments to be constructed and maintained at a stable gradient according to design specifications to minimize gully erosion;	Quantum of earth (Cum) generated, percentage utilized and disposed-off; Mechanism adopted for safe storage of generated top soil for reuse / clearing; Denuded area covered under plantation after construction (% of area) Slope maintained as per design	Site inspection / visit; Review of quarterly report by contractor; Analysis of water quality report	DPMU	Monthly
	Embankments shall not be left un-compacted during construction works to minimize wind and water erosion.	Downstream and upstream water quality;			
Littering on road due to transportation of earth from borrow areas	All transportation vehicle shall be provided with tarpaulin lining.	Lining in transportation vehicle; Borrow area and earth quantity	Site inspection / visit; Review of quarterly report by contractor;	DPIU	Weekly
III. Rehabilitation and IV. Providing control	 d upgradation of canal regulating structures of Main, B d upgradation of canal regulating structures of Minor / led structures (Duckbill weir) at tail end of canals and o ates/shutters at uncontrolled outlets (sub-component un	Sub-minors (sub-component under B. ther locations of Level 4 canals (sub-c	2)		<u> </u>
Impact due to construction activity	ESMP for construction activity shall be applied				
Air and dust pollution due to demolition work; health impact on workers	All structure and demolition sites shall be wetted regularly before and after demolition work, to minimize air and fugitive dust pollution. Demolition site shall be covered from all site to arrest fine particle as well as to reduce air pollution.	Air quality in the site; Workers using PPEs	Site inspection and physical verification; Air quality report	DPMU	Weekly
	Demolition workers shall be provided with PPEs to minimize health impact due to dust and air pollution				

Expected Impact	Mitigation Measures	Monitoring Indicators	Means of Verification	Supervising and Monitoring Entity	Monitoring Frequency
		Machinery / equipment / vehicles having latest certificate of maintenance;	Site inspection and physical verification;	DPMU	Weekly
	All demolition work shall be restricted between day time (7.0 AM to 8.0 PM).	No. of workers using ear-plugs / ear- muffs to reduce occupation exposure;	Noise quality report;		Quarterly (During demolition)- 13 location
	Local people shall be made aware of specific time duration of demolition work, in advance.	Noise emitting machineries with protecting damping;			
	Sign board showing site of demolition work and time shall be provided at demolition site;	Use of explosive; blasting operation	Verification of used instrument / machineries;		
vibration and its	Demolition work will not be permitted at any silence area or zone (100 meters from hospital, school) during active working hours (10 AM to 5 PM); demolition work in silence zone shall preferably be carried out on weekend and holiday or between 6 A.M to 10 A.M and 5 PM to 8 PM of other weekdays.		Consultation with local habitants;		
	Heavy noise emitting equipment shall be fitted with silencer. Noise barrier shall be provided to generator set.				
	Reducing the noise produced from a vibrating machine by vibration damping i.e. making a layer of damping material (rubber, neoprene, cork or plastic) beneath the machine.		Site inspection and physical verification	DPMU	Weekly
	Explosion or blasting operation shall not be performed within 500 meters periphery of nearby local habitat or structure.	Blasting sites and measure adopted to reduce effect of vibration	Consultation with local habitants		
	Contractor shall conduct vibration testing during blasting operation (if any) by engaging any third party at least at ten $(10 - \text{for whole project})$ location. Testing location shall be identified in consultation with DPMU and submit vibration report to DPMU.	Damage due to blasting/ vibration	Vibration testing;	Contractor	Each Blasting Site
	Demolition workers shall be provided with PPEs (earmuff) to minimize health impact due to noise pollution				
	Apron/ wave breaker where ever required shall be provided for decapitation of excess energy	Apron/ wave breaker provided;	Site inspection and physical verification	DPIU/ DPMU	

Expected Impact	Mitigation Measures	Monitoring Indicators	Means of Verification	Supervising and Monitoring Entity	Monitoring Frequency
from dismantling	Reuse of dismantled materials to the possible extent; Unused / unusable materials shall be auctioned as per the procedures of Govt. / IWD or leftover C&D waste shall be disposed-off in the nearby sanitary landfill site.	Reuse and disposal of C&D items; Water Pollution management plan; Water quality in nearby river/ stream;	Water quality report; Site inspection; Review of records / reports	DPMU	Weekly
B 2 Minor Conol (I 4) and Chak Infrastructure Modernization				
	installation of pressured supply				
Impact due to construction of water storage sump	ESMP for construction activity shall be applied				
Consumption of conventional energy for pumping and water distribution which will increase economic cost of production		Percentage increase in area irrigated; Percentage reduction in gap ayacut in the command; Consumption of renewable and non- renewable energy;	Consultation with farmers in the command area; Reports / records; Site Inspection	IWD	Quarterly
VI Constant of an after		Anna an fan man in maki anang			
Impact due to construction activity	ater retaining structure over minor channels to create s ESMP for construction activity shall be applied	torage for use in rabi crops			
.	Construction work shall be carried out when the river/ canal bed is dry.	No. of sites where dewatering is done	Site inspection / visit;	DPMU	Weekly
Flooding of nearby agricultural field during dewatering before construction	Else, earthen bund shall be constructed for dewatering of active work zone;	Adopted dewatering mechanism;	Consultation with farmer having land adjoining to work site		
	River/ canal water shall not be pumped out for dewatering purpose to nearby agricultural field to avoid any kind of crop damage as well as agricultural land pollution (although probability of land/ soil pollution is very low; as this water is being used for irrigation purpose).	Crop area and type affected due to dewatering;	Review of quarterly report by contractor;		
	Crop compensation shall be paid to affected farmers on occurrence of crop damage due to dewatering.	Crop compensation paid to affected farmers.			
Crop damage due to interrupted irrigation supply	Contractor shall submit work plan with canal/ river closure timeline for each restoration site to DPMU at least before 45 days of any crop season;	Submission & approval of canal/river closure plan	Review of closure plan	DPMU	Before each crop season
	River/ canal closure plan shall not be approved by DPMU, if not submitted at least 45 days prior to any crop season;	Dissemination of canal/ river closure plan	Consultation with farmer having land adjoining to work site		

Expected Impact	Mitigation Measures	Monitoring Indicators	Means of Verification	Supervising and Monitoring Entity	Monitoring Frequency
	Subsequent to receive and approve of work plan, farmers should be informed about canal closure plan at-least before 30 days of any crop season. Canal closure notice board shall be displayed at local panchayat/ irrigation/ fishery and BDO office.		Review of quarterly report by contractor;		
Sediment transport in streams, canal leading to increased TDS and turbidity	All earther bund constructed for dewatering purpose shall be removed and entire work zone shall be levelled properly before monsoon period to maintain natural canal flow, minimize soil and sediment transportation to downstream and water pollution. Muck/ soil may be stored at canal/ river set back zone or either side of embankment for temporary period. Immediate collection and clearance of excess muck/soil from canal bed to minimize the erosion potential and sediment transportation into canal water which may cause increased water turbidity or TDS;	Removal of earthen bund; Clearing and levelling of work zone; Reuse and disposal of muck; Downstream and upstream water quality;	Site inspection / visit; Review of quarterly report by contractor; Analysis of water quality report	DPMU	Quarterly; before monsoon
Processing Industries 1) Providing subsidy fo	r area expansion and planting material to promote less wate Optimum use of fertilizer, promotion of the use of organic manure and bio-fertilizer.		Soil test report; Soil health card;		
may be containing excess fertilizer promotes the excessive growth of aquatic	Prevention of agricultural runoff to flow in to the canal / river / water bodies by adoption of efficient irrigation methods; Promotion of IPNM strategies among the farmers in the	Farm level soil test; No. of farmers adopted INM / IPM / IPNM by holding category and crop type during different agricultural seasons;	Farm level water quality report; Field assessment;	Dept. of FPI&H	Monthly
plants (such as algae, weed and water hyacinth)	command area by training, demonstrations and hand holding support. Supply of IEC materials on specific doses of application of fertilizer for different crops during different seasons, in accordance with the earlier researches.		Consultation with farmers Consultation with extension service provides		
Deterioration of groundwater quality	Promotion of organic farming that encourages use of organic fertilizers and pesticides Optimum use of chemical fertilizer and pesticides. Discouraging ground water extraction for agricultural and meeting high water consumption requirements in critical / semi-critical / unsafe zones. Sensitization / awareness of farmers on ground water extraction potential and ground water conservation.	No. of farmers adopted INM / IPM / IPNM by holding category and crop type during different agricultural seasons; Increase in surface water utilization and decrease in ground water withdrawal for irrigation purpose;	Ground water quality testing; Review of report on fertilizer and pesticide use; Field assessment on use of fertilizer and pesticide	Dept. of Agriculture	Monthly

Expected Impact	Mitigation Measures	Monitoring Indicators	Means of Verification	Supervising and Monitoring Entity	Monitoring Frequency
	Participatory Ground Water Management through ground water user groups may be promoted, more specifically in semi-critical groundwater zones.	Use of chemical fertilizer and pesticides			
Soil quality degradation due to excess use of Fertilizer and pesticide	Training farmers for promoting adoption of integrated weed and pest management practices such as use of certified and disease tolerant seed varieties, use of early maturing seed varieties, proper land preparation, early planting, following recommended planting space between rows and plants, timely/early weeding, suitable water management practices and the use of agrochemicals where necessary. This will minimize the rate of agrochemical use. Dept. of Horticulture and Agriculture will ensure successful implementation of IPNM (given in ESMF of WBMIFMP). Dept. of Horticulture and Agriculture will sensitize farmers to, preferentially, use selective pesticides with low environmental impact quotient (EIQ) where appropriate, rather than broad-spectrum products, to minimize impacts on non-target species. Under minimum/reduced tillage, the stocks and leaves of harvested crops will be left on the field as much as possible to serve as mulch to conserve soil moisture and also improve soil biological condition on decomposition. The farmers will be encouraged to use organic manure to minimize the use of inorganic manure and improve soil biological conditions.	No. of farmers adopted INM / IPM / IPNM by holding category and crop type during different agricultural seasons; No. of training organized on integrated weed and pest management.	Record on training provided; Review of record on use of different type of fertilizer and pesticide; Field assessment on use of fertilizer and pesticide	Dept. of FPI&H	Quarterly
	or construction of Shade-net house or infrastructure development for promotion of vermi compo	ost, protected cultivation and post-harve	st infrastructure		
Construction activity	ESMP for construction activity camp site management plan shall be applied				
Use of agricultural land for construction	Use of irrigated agriculture land for PHI will be avoided, Exploring availability of Govt./ GP land for construction PHI,	Location of and type of land selected for PHI development; Number of PHI constructed;	Field observation; Consultation with farmer/ community	Dept. of FPI&H	Quarterly

Expected Impact	Mitigation Measures	Monitoring Indicators	Means of Verification	Supervising and Monitoring Entity	Monitoring Frequency	
of Post-Harvest Infrastructure (PHI)	In PPP mode of infrastructure creation, the private body (FPC/ SHG), individual entrepreneur should arrange land in case of non-availability of Govt. land.	Use of Govt. land for construction of PHI				
Soil contamination due to storing of construction material on agriculture field	Construction work shall not be carried out during monsoon season; to minimize impact on cultivated crop, construction work shall be carried out only when firm land is devoid of any crop; any left-out waste or construction material shall be stored and collected and disposed properly; metal waste shall be sold to authorized recycler.	Period of construction work; list of construction material with quantity; Waste utilization plan adopted during implementation;	Community consultation; Consultation with implementing contractor on waste utilization; review of record on waste utilization	Dept. of FPI&H	Monthly	
	rketing – Agriculture Marketing Dept.					
	egation centre/ pack house for temporary/ intermediate stor	age of farm produces (1/ FPC)				
Impact due to construction activity	ESMP for construction activity shall be applied					
	Use of irrigated agricultural land for aggregation centre / pack house will be avoided; Exploring availability of Govt. land / GP land for PHI; In PPP mode of infrastructure creation; private body should arrange land in case of non-availability of govt. land.	Change in land use pattern, if any; Construction activities as per the design;	Physical verification and production assessment; Consultation with farmers; Review of reports	Dept. of Agriculture Marketing	Fortnightly	
	Solid waste shall be collected regularly to maintain aesthetic value of nearby area and maintain hygiene condition.	Construction related practices followed / adopted;	Detail project Report (DPR); Consultation with FPC members; Site visit and physical verification	Dept. of Agriculture Marketing	Fortnightly	
Procurement and use of machineries that does not comply to standards resulting with poor energy efficiency.	The machineries / instruments to be procured / installed should have ISI mark and energy efficiency certification.	Machineries / equipment procured / installed; Vendor details (registered / unregistered)	Review of documents; Consultation with FPC members; Site visit and physical verification	Dept. of Agriculture Marketing	Before Purchase	
2) Transport subsidy to	each FPC for procurement of motorized van (4.5 lakh/ FPC	3)				
Procurement and use of vans that are not as per the standard for agricultural	The van to be procured should comply to prescribed standards for transportation of agricultural commodities;	Vehicle procured and its standards; Vendor details (registered / unregistered)	Review of documents; Consultation with FPC members; Site visit and physical verification	Dept. of Agriculture Marketing	Before sanctioning subsidy	

			Monitoring Entity	Frequency
sed pisciculture in the main and branches of irrigation	on canals			
ith appurtenant to each SHG/ FPGs				
n feed etc. to SHG/ FPGs as one-time sustenance support	t			
voiding overfeeding; voiding or minimize or control use of medication	Use of feeding system and application of medicines	Consultation with fishers / SHGs / FPG members; Site inspection and physical verification	Dept. of Fishery	Monthly
aintaining proper stocking density; voiding stocking exotic and invasive species;	Stocking density and species assessment in cases	Consultation with fishers / SHGs / FPG members; Site inspection and physical verification	Dept. of Fishery	Monthly
rit 70 70	h appurtenant to each SHG/ FPGs feed etc. to SHG/ FPGs as one-time sustenance suppor biding overfeeding; biding or minimize or control use of medication ntaining proper stocking density;	feed etc. to SHG/ FPGs as one-time sustenance support biding overfeeding; biding or minimize or control use of medication Use of feeding system and application of medicines Intaining proper stocking density; biding stocking exotic and invasive species; Stocking density and species	h appurtenant to each SHG/ FPGs feed etc. to SHG/ FPGs as one-time sustenance support biding overfeeding; biding or minimize or control use of medication biding or minimize or control use of medication biding proper stocking density; biding stocking exotic and invasive species; biding stock	h appurtenant to each SHG/ FPGs feed etc. to SHG/ FPGs as one-time sustenance support biding overfeeding; biding or minimize or control use of medication biding or minimize or control use of medication biding proper stocking density; biding stocking exotic and invasive species; biding stocking exotic and plusical biding exotic and plusical biding exotic and plu

Annexure- 28(b) ESMP Implementation Monitoring Plan for Flood Management

Expected Impact	Mitigation Measures	Monitoring Indicators	Means of Verification	Supervising and Monitoring Entity	Monitoring Frequency
	eswari river for a length of 19.67 km from Beguahana t s. other drainage channels	to further downstream (including 430	metre u/s of undivided Dame	odar)	
due to denudation	areas of the land to be developed at a particular time are	Portion cleared at a particular time; Desilting work initiated on cleared portion;	Physical verification of site; Report of the Contractor;	DPIU	Weekly
	This will also ensure the cleared areas of the land are not left bare over long periods as development at the cleared areas will be carried out immediately. This will minimize erosion at the project site.	Water and air quality in the working	Water & Air Quality Report		
Impact on flora/ fauna during weed cleaning operation	Contractor shall take reasonable precaution to prevent his workers from damaging any flora or fauna of the area specially during vegetation clearance. Vegetation clearance shall be limited to portions of the river/ drainage channels to be desilted at a particular time. The entire land will not be cleared at a time and this will allow any fauna to migrate to adjoining areas.	and disposal	Physical verification of site; Consultation with workers/ local people; Review of quarterly report by contractor;	DPIU	Weekly
Organic pollution due to improper dumping of removed weed on river/ drainage channels side embankment leading to inconvenience to local commuters; odour pollution	Possibility shall be explored to engage Food Processing Industries and Horticulture Department for using removed weed/ hyacinth in vermi composting promoted under this project. The management and disposal of this waste will be as follows (details are provided in the ESMP for waste management): Local community will be allowed to use the weeds for domestic use such as using it as fuel (shrub stem, root), animal fodder or for composting.	Quantum of weeds generated, its use and disposal;	Physical verification of site; Consultation with local community; Review of quarterly report by contractor;	DPIU	Weekly
	Identification of temporary storage locations for drying and temporary storage of the aquatic weed waste in consultation with the IWD site engineers and the local government authority. The locations will not be within 100 m of the identified Sensitive Receptors (listed in Table 36 under Section 4.16). The Contract Package ESMP and Contractor's ESMP will list and provide map of the identified locations.				

Expected Impact	Mitigation Measures	Monitoring Indicators	Means of Verification	Supervising and Monitoring Entity	Monitoring Frequency
	Temporary storage of the aquatic weed waste at identified locations for a period not exceeding 10 days.			¥	
	 identified locations for a period not exceeding 10 days. Sale or free lifting of dry/semi-dry aquatic weed waste for onward processing into compost, ropes (for handicrafts and furniture making), fodder, etc. The Contract Package ESMP and Contractor's ESMP will provide details of quantity to be disposed in this way along with details of interested parties. The following Dos and Don'ts are to be followed for management of aquatic weed waste: The aquatic weed waste will not be stored at unauthorized locations. Burning of aquatic weed waste is not to be undertaken. Dumping of aquatic weed waste at unauthorized locations is not to be undertaken. In case on onward sale of the aquatic weed waste, the sale agreement will include prohibition of environmentally harmful practices (open burning of semi-wet waste, dumping of waste residues in 				
	unauthorized locations including water bodies, etc.).				
Air Pollution due to Burning of weeds	Contractor shall not adopt practice of burning weeds; Discouraging local community in burning of weeds;	Air quality in the work site and aberration from standards.	Air quality test report; Consultation with local people / workers	DPIU	Weekly
Flooding of nearby agricultural field during dewatering before desiltation	Most of the desiltation work will be carried out when the river/ drainage channels bed is dry. Else, bund shall be constructed for dewatering of active work zone; River/ drainage channels water shall not be pumped out for dewatering purpose to nearby agricultural field to avoid any kind of crop damage as well as agricultural land pollution (although probability of land/ soil pollution is very low; as this water is being used for irrigation purpose).	No. of sites where dewatering is done; Crop area and type affected due to dewatering; Crop compensation paid to affected farmers.	Site inspection / visit; Consultation with farmer having land adjoining to work site Review of quarterly report by contractor;	DPMU	Weekly
	Crop compensation shall be paid to affected farmers on occurrence of crop damaged due to dewatering.				

Expected Impact	Mitigation Measures	Monitoring Indicators	Means of Verification	Supervising and Monitoring Entity	Monitoring Frequency
	In case channel/ river (undivided Damodar) water is pumped out for dewatering the following do and don'ts will be followed: Ensure that the pumped-out water will not deteriorate the water quality of the receptor water bodies. Undertake prior consultation, secure agreement and give adequate notice to other users of receptor water bodies. Don't let the water out onto roads, areas close to habitations that are prone to water logging, etc.				
Crop damage due to interrupted irrigation supply	Contractor shall submit work plan with river/ drainage channel closure timeline for each desiltation site to DPMU at least before 45 days of any crop season; Desiltation plan shall not be approved by DPMU, if not submitted at least 45 days prior to any crop season; Subsequent to receive and approve of work plan, farmers should be informed about river/ drainage channel closure plan at-least before 30 days of any crop season. River/ drainage channel closure notice board shall be displayed at local panchayat/ irrigation/ fishery and BDO office.	Availability of approved of river/ canal closure plan; Dissemination of river/ canal closure plan	Review of river/ canal closure plan; Consultation with farmer having land adjoining to work site; Review of quarterly report by contractor;	DPMU	Before each crop season
	All bund constructed for dewatering purpose shall be removed and entire work zone shall be levelled properly before monsoon period to maintain natural river/ drainage channel flow, minimise soil and sediment transportation to downstream and water pollution. Immediate collection and clearance of excess sand/ muck/soil from river/ drainage channel bed to minimize the erosion potential and sediment transportation into river/ drainage channel water which may cause increased water turbidity or TDS;	Removal of bund; clearing and levelling of work zone; Amount of sand/ muck / silt generated, reused and disposed-off; Water Quality of upstream and downstream	Site inspection / visit; Review of quarterly report by contractor;	DPMU	Weekly (specially before monsoon)
Over desiltation and/or desiltation in unplanned area / manner may aggravate environmental impact	Contractor shall conduct site specific testing of desilted materials to assess the appropriateness for different users.	Experience of contractor in river and canal desiltation; Availability of desiltation plan, safety plan and desiltation scheduling; Volume of desilted material generated in each quarter and reused for beneficial purpose	Work order, work agreement and completion certificate; Physical verification of site and tallying with the plan; Consultation with contractor; Communication letter	SPMU	During selection of contractor Before desiltation

Expected Impact	Mitigation Measures	Monitoring Indicators	Means of Verification	Supervising and Monitoring Entity	Monitoring Frequency
	DPMU and SPMU for approval prior to carrying out desiltation operations. Desiltation plan should be prepared considering its location w.r.t environmental sensitive locations/ archaeological locations/ cultural festival/ pollution influx in the area/ quality & texture of desilted material/ available depth etc. through local sources and past experience.				
Health impact on workers and local community due to	Desilting contractor should follow the defined safety procedures to avoid accidents and spills. Inform local community prior to desiltation operation to	Application of safety norms Prior information to local community	Site visit; consultation with workers and contractor Consultation with local	DPMU/ SPMU	DPMU- Weekly, SPMU-
desiltation operation Dewatering of desilted material and associated water and soil contamination and sediment transportation	river water without sediment trapping;	No. of sediment trap provided; cleaning of sump;	community Site Inspection; Discussion with contractor / workers; Physical verification	DPMU/ SPMU	Monthly DPMU- Weekly, SPMU- Monthly
	Regular monitoring of the excess water at sediment trapping system shall be done. This will help in assessing the efficiency of sediment trap system provided at site.				
Sediment release,	No stacking of desilted material on river bed or agricultural field during monsoon period; Immediate shifting of desilted materials from stream to temporary stacking point;	Stacking and reused quantum of desilted materials; Removal of ramps	Site inspection and observation; Discussion with contractor; Site inspection, specifically	DPMU/ SPMU	DPMU- Weekly, SPMU- Monthly
transportation and mixing with water during desiltation	Early evacuation of desilted material/ dewatered sand material from set-back zone to next point to minimize the potential for erosion into river water which may cause soil and sediment transportation in downstream. Proper levelling of work zone before monsoon.		before the on-set of monsoons; Review of transportation log book;	DPMU	manuty
	shall be applied Desiltation material will temporarily be stored on river set back zone located on both side of river and bank of	Soil and water quality; Stacking and disposal management practices adopted; Soil and water quality;	Physical verification through site; Review of data on desilted quantum, used and disposed quantum;	DPMU/ SPMU	DPMU- Weekly, SPMU- Monthly

Expected Impact	Mitigation Measures	Monitoring Indicators	Means of Verification	Supervising and Monitoring Entity	Monitoring Frequency
	In case of unavoidable circumstances, agreement of farmer is mandatory for use of land for temporary stocking;	Quantum of stocking and area used (in Ha.);	Soil and water quality and comparing with baseline;	¥¥	
	Compensation to farmers for temporary stacking; Earmarked land shall be developed by removing top soil for temporary stacking.	No. of farmers land temporarily used for stacking;	Review of agreement with farmers;		
	Bed lining using brick paving and thick tarpaulin in the area of stocking to restrict it's mixing with top soil;		Consultation with farmers		
	Bund around temporary storing area of desilted material; Top soil shall be preserved and levelled properly after removal of entire desilted material;				
	Restoration of land to its previous position or its improvement Desilted material shall be reused before monsoon season;				
Disposal of excess desilted material- Impact on Soil quality.	Desilted material shall be redsed before highsoon season, Desilted material should not be disposed-off in river banks or agricultural field; Reuse of desilted material to the possible extent and disposal of remains; Filling up of vacant low-lying Government land identified and approved both by the IWD and by the local government authority In case, if the desilted materials found unsuitable for field or other application, it would be disposed-off as per the sediment disposal plan given in Section- 7.3.3. If desilted material is found contaminated with heavy metal at any particular location, material should be disposed at nearby approved TSDF site.	Soil quality in disposal site	Site inspection; Consultation with locals / inhabitants; Review of documents; Soil quality report	DPMU/ SPMU	DPMU- Weekly, SPMU- Monthly
Dust and air pollution from flying of dried up desilted material;	transporting desilted material to restrict littering on road.	Air pollution in the work and habitation site; Covering of transportation means	Air quality report review; Site inspection; Discussion with local habitants.	DPMU	Regular
littering during transportation	At canal stretches in proximity of sensitive receptors, the following additional mitigation measures will be implemented: The Contract Package ESMPs and Contractors ESMPs				
	will specify the list of sensitive receptors. (the list of				

Expected Impact	Mitigation Measures	Monitoring Indicators	Means of Verification	Supervising and Monitoring Entity	Monitoring Frequency
	sensitive receptors – educational institutions, healthcare institutions and etc. are provided in Section 4.16).				
	Quarterly air quality monitoring shall be carried out at the Sensitive Receptor locations.				Quarterly
mammal (Fishing Cat, Asian Small-clawed	Desiltation operation shall be carried out only during non-monsoon period when major portion of river/ drainage channel bed remains dry; The contractor and its workers will be educated / sensitized on endangered/ vulnerable species and its protection measures;	Reported cases of impact on aquatic fauna	Site inspection and observation; Review of reports / data; Discussion with local community	DPIU/ DPMU	DPIU- Regular, DPMU- Weekly
	Hunting or poaching of Vulnerable mammal (Fishing Cat, Asian Small-clawed Otter) and Snake (King Cobra) shall be strictly restricted. On observation, any such species shall be allowed to migrate in nearby area.				
	Not using any threatened/ near threatened species for commercial purpose;				
	Desiltation work at Mundeswari river shall be restricted between 6 AM to 6 PM; any kind of work on river bed shall NOT be performed during night time (7 PM to 6 AM)				
	All sources of light on Mundeswari river bed shall be switched off during night time (6PM to 7AM)				
	Vibration measures shall be performed before initiation of desiltation work at Mundeswari River to allow species to come out from their cave and migrate to surrounding places;				
	Weed clearing on Mundeswari river shall be restricted to active work zone, this will allow fauna species to migrate in nearby bushes;				
	Fishing cat which is State animal of West Bengal shall be protected from any kind of damage; occurrence of damage to any vulnerable, threatened species shall be reported to Dept. of Biodiversity on regular basis;				
	Silencer shall be provided with all noise generating machineries operating during desiltation operation; Reducing the noise produced from a vibrating machine by vibration damping i.e. making a layer of damping material (rubber, neoprene, cork or plastic) beneath the machine;				

Expected Impact	Mitigation Measures	Monitoring Indicators	Means of Verification	Supervising and Monitoring Entity	Monitoring Frequency
Impact on aquatic fish and benthic communities	Desiltation operation shall be carried out only during non-monsoon period when major portion of river/ drainage channel bed remains dry;	Reported cases of impact on aquatic fish	Site inspection and observation; Review of reports / data; Discussion with local community	DPIU/ DPMU	DPIU- Regular, DPMU- Weekly
	The contractor and its workers will be educated / sensitized on vulnerable (3), endangered (1), near threatened (3) and near extinction fish species and its protection measures;				
	Not performing fishing activity during desiltation work in river/ drainage channel or near-around area water- bodies,				
	Not using any threatened/ near threatened species for commercial purpose;				
	Any vulnerable (3), endangered (1), near threatened (3) and near extinction fish species found during dewatering of active desiltation zone shall be preserved and immediately release to downstream river/ drainage channel water.				
Impact on socioeconomic environment	Limiting desiltation operations to day time only, i.e. 7:00 Am-8:00 PM; Use of machineries equipped with noise reduction / masking equipment; Log book should be maintained for recording the accidents at site. Analysis shall be carried out to assess the reason for the accident / mortality and measures should be taken to prevent repetition of the event.	Seasonality and timing of desilting operation; Use of technically specified earthmoving machineries with operational clearance;	Site inspection; Log book and document verification; Consultation with local inhabitants;	DPIU/ DPMU	DPIU- Regular, DPMU- Weekly
Disruption of livelihoods due to temporary stocking of desilted material in agricultural land located at set back zone	To the extent possible areas with habitation / business establishments / cultivable areas will be avoided; In case of any loss of livelihood, PAP will be compensated under the project.	Total cultivated and uncultivated land (in Ha.) used for temporary stocking; Temporary acquisition of land for stocking (in Ha.); Willingness of the land owner / cultivator to use land for stacking No. of persons affected and no. of persons paid compensation	Site inspection; Consultation with farmers / contractor / local community; Review of reports / documents	DPMU/ SPMU	DPMU- Weekly, SPMU- Monthly
	Allowing fishing in other locations, excluding the working zone on temporary basis;	No. of fisher's dependent on specific location for fishing;	Discussion with fishers;	DPIU	Weekly

Expected Impact	Mitigation Measures	Monitoring Indicators	Means of Verification	Supervising and Monitoring Entity	Monitoring Frequency
		Average percentage increase or reduction in seasonal catch; Shift in catching locations	Discussion with fishery Dept.	<u> </u>	
IV. Improving Damod V. Improving Upper R VI. Raising & Strengt VII. Protection / River	nodar Right Dwarf embankment to act as Broad Creste ar Protected Left Embankment by providing adequate Rampur & Hurhura Channels by providing adequate fr hening of countryside existing earthen embankments to training works on river Damodar / Mundeswari, Hurl	free board to withstand flood through eeboard through provision of flood wa its design section of Damodar Left, H	construction of flood walls all on Left Embankments urhura Left & Lower Ramp		
Impact due to construction activity	ESMP for construction activity shall be applied				
Top soil exposure due to denudation leading to soil erosion	areas of the land to be developed at a particular time are exposed to agents of erosion. This will also ensure the cleared areas of the land are not left bare over long periods as development at the cleared areas will be carried out immediately. This will minimize erosion at the project site.	phases and area restored; Quantum of earth (Cum) generated, percentage utilized and disposed-off. Denuded area covered under plantation after construction (% of area) Water quality in the working zone and deviations from the standards / baseline in different periods; Work initiated on cleared portion	Physical Verification of Site; Report of the Contractor; Water Quality Report	DPIU	Weekly
Impact on flora/ fauna during weed cleaning operation	Contractor shall take reasonable precaution to prevent his workers from damaging any flora or fauna of the area specially during vegetation clearance. Vegetation clearance shall be limited to portions of the embankment at a particular time. The entire land will not be cleared at a time and this will allow any fauna to migrate to adjoining areas.	Quantum of weeds generated, its use and disposal	Physical verification of site; Consultation with workers/ local people; Review of quarterly report by contractor; Review of quarterly report by contractor;	DPIU	Weekly
Organic pollution due to improper dumping of removed weeds, shrub stems, stumps, roots, twinges and leave on canal side embankment leading to inconvenience to local commuters; odour pollution	Possibility shall be explored to engage Food and Horticulture Department for using removed weed in vermi composting promoted under this project. The management and disposal of this waste will be as follows (details are provided in the ESMP for waste management): Local community will be allowed to use the weeds for domestic use such as using it as fuel (shrub stem, root), animal fodder or for composting.	Quantum of weeds generated, its use and disposal;	Physical verification of site; Consultation with local community; Review of quarterly report by contractor;	DPIU	Weekly

Expected Impact	Mitigation Measures	Monitoring Indicators	Means of Verification	Supervising and Monitoring Entity	Monitoring Frequency
	Identification of temporary storage locations for drying and temporary storage of the aquatic weed waste in consultation with the IWD site engineers and the local government authority. The locations will not be within 100 m of the identified Sensitive Receptors (listed in				
	Section 4.16). The Contract Package ESMP and Contractor's ESMP will list and provide map of the identified locations.				
	Temporary storage of the aquatic weed waste at identified locations for a period not exceeding 10 days.				
	Sale or free lifting of dry/semi-dry aquatic weed waste for onward processing into compost, ropes (for handicrafts and furniture making), fodder, etc. The Contract Package ESMP and Contractor's ESMP will provide details of quantity to be disposed in this way along with details of interested parties. The following Dos and Don'ts are to be followed for				
	 management of aquatic weed waste: The aquatic weed waste will not be stored at unauthorized locations. Burning of aquatic weed waste is not to be undertaken. Dumping of aquatic weed waste at unauthorized 				
	 locations is not to be undertaken. In case on onward sale of the aquatic weed waste, the sale agreement will include prohibition of environmentally harmful practices (open burning of semi-wet waste, dumping of waste residues in unauthorized locations including water bodies, etc.). 				
Air Pollution due to Burning of weeds, shrub stems, stumps, roots, twinges and leave	Contractor shall not adopt practice of burning weeds, shrub stems, stumps, roots, twinges and leave; Discouraging local community in burning of weeds, shrub stems, stumps, roots, twinges and leave;	Air quality in the work site and aberration from standards.	Consultation with local people / workers; Review of quarterly report by contractor; Air quality test report;	DPIU	Weekly
Water and soil pollution due to coal arring of bullah; health impact on workers	Coal tarring of bullah on agricultural land or river bed/ bank shall be avoided to the possible extent; h	Quantity or coal tar purchased; Lining provided; use of PPF by workers	Site visit, Consultation with workers	DPIU	Weekly

Expected Impact	Mitigation Measures	Monitoring Indicators	Means of Verification	Supervising and Monitoring Entity	Monitoring Frequency
	Impervious lining arrangement shall be provided at coal tarring area;				
	Worker shall use full set of protective gear (hand gloves, shoes, mask, etc.) while handling coal tar; a first-aid kit will be available;				
	Avoidance of tree cutting to the possible extent with locational and design alternatives;	No. of trees uprooted by at project site;	Physical verification by site inspection	SPMU	Quarterly
$GBH \ge 80$ nos.) due to	Chainage wise requirement of tree felling shall be counted with their species;	No. of trees not falling in the working zone but uprooted;	Review of records / repots	DPMU	Monthly
flood wall construction and embankment strengthening works	Consult with local community as well as DPIU in identifying suitable local indigenous tree species; available community land or Govt. vacant land for compensatory plantation.	No. of trees planted (compensatory afforestation);	Consultation with local community	DPMU	
	Tree felling shall be commenced only after obtaining permission from Dept. of forest.	Type of tree species planted and bio- diversity maintenance		DPMU	
	No tree felling will be allowed beyond the identified working zone; cutting of holy tree <i>Ficus religiosa</i> (<i>Peepal</i>) shall be avoided to the possible extent;	Plant survival rate (newly planted saplings)		DPIU	
	The construction and excavated materials will be staked at a safe distance from tree located in such areas to avoid any damage to the trees;			DPMU	
	Shrub stems, stumps, roots shall be uprooted properly to eliminate any chance of void.				
	To compensate loss of tree and to improve the local aesthetic value, compensatory tree plantation at 1:5 ratio will be carried out.				
	Maintaining bio-diversity in compensatory afforestation and avoid mono species plantation; Mixed plantation with locally grown species will be promoted in consultation with Forest Department and local community / Gram Panchayat;				
	Bamboo palisade will be provided around plantation area; after care measures for a period of thee year will be taken up				
Loss of top soil	Generated small quantity of top soil shall be preserved and suitably reused for levelling, back filling purpose. Top soil may be temporarily staked in either side of embankment for field reuse;	Quantum of top soil generated, percentage utilized and disposed-off; Denuded area covered under plantation after construction (% of area).	Physical Verification of Site; Review of quarterly report by contractor;	DPMU	Weekly

Expected Impact	Mitigation Measures	Monitoring Indicators	Means of Verification	Supervising and Monitoring Entity	Monitoring Frequency
	Regular water sprinkling shall be provided to maintain moisture content- which in turn will reduce dust pollution; In case of transportation of top soil, tarpaulin cover shall be provided to restrict dust pollution during transportation.	Arrangement of water sprinkling; Record on water sprinkling; Tarpaulin cover during transportation; Air quality near to the site and at habitation areas;	Site inspection; Report of the Contractor; Record on days of water sprinkling done in non- monsoon seasons	DPIU	Weekly
	At canal stretches in proximity of sensitive receptors, the following additional mitigation measures will be implemented: The Contract Package ESMPs and Contractors ESMPs will specify the list of sensitive receptors. (the list of				
	sensitive receptors – educational institutions, healthcare institutions and etc. are provided in Section 4.16). Quarterly air quality monitoring shall be carried out at the Sensitive Receptor locations.		Air quality monitoring report	DPMU	Quarterly
Littering on road due to transportation of earth from borrow areas; dust pollution	All transportation vehicle shall be provided with	Lining in transportation vehicle;	Site inspection / visit; Review of quarterly report by contractor;	DPIU	Weekly
Impact on public utilities and disruption of services	Consideration of design and locational alternative for minimum disruption of public utilities. Relocation of affected public utilities in consultation with concerned dept.; Reconstruction of demolished community facilities or provision of compensation in consultation with GP / local community; Necessary permission shall be obtained from respective Govt. agency;	-	Site inspection; Discussion with inhabitants on facilities and services; Review of records / reports	SPMU	Monthly
Impact on assets and livelihood; due to eviction from encroached land	To the extent possible, eviction will be avoided; In case of any eviction, the affected persons/families to be identified in advance and will be compensated at replacement value for the lost asset; (Refer RAP for detail) The affected person will be compensated / assisted before taking physical possession of the asset; Option for temporary relocation, till the end of construction, will be explored Loss of crop to be compensated financially in case of temporary use of land;	No. of persons affected and relocated (temporarily / permanently) No. of affected persons provided compensation awards for loss / acquisition of assets; No. of persons reengaged in different livelihood activities; Improvement / reduction in income of the affected families	List of affected families; List of PAFs / PAPs compensated for loss of assets; Consultation with PAFs / PAPs; Visit to project sites and physical observation of livelihood restoration.	DPMU/ SPMU	DPMU- Weekly SPMU- Monthly

Expected Impact	Mitigation Measures	Monitoring Indicators	Means of Verification	Supervising and Monitoring Entity	Monitoring Frequency
Cultural properties	Re-examination of CPR before commencement of the work and list down CPR to be affected.	No. and type of cultural properties affected;	Site inspection;	DPMU	DPMU- Weekly SPMU- Monthly
such as Mandir- 31,	Design and location shall be modified to the possible extent to protect all cultural property and / or to minimize impact on it;	No. and type of CPR for which compensation paid or newly constructed;	Discussion with inhabitants on affected and restored CPR;	SPMU	DPMU- Weekly SPMU- Monthly
	If in case it is unavoidable, project shall construct or arrange similar establishment or compensate for the loss of asset in consultation with local people / GP.		Review of records / reports	SPMU	
VIII. Remodeling & R	econstruction of sluices at the outfalls of drainage chan	nels			
Impact due to construction activity	ESMP for construction activity shall be applied				
	Demolition site shall be covered from all site to arrest fine particle as well as to reduce air pollution.	Air quality in the site; Workers using PPEs	Site inspection and physical verification; Air quality report	DPMU	Weekly
	Demolition workers shall be provided with PPEs to minimise health impact due to dust and air pollution				
	The Contract Package ESMPs and Contractors ESMPs will specify the list of sensitive receptors (given in Section 4.16).				
	Regular monitoring of air emissions at the Sensitive Receptor locations.				Quarterly
Noise pollution & vibration and its impact on workers and community health	Demolition site shall be covered from all site to arrest / restrict spreading of noise due to demolition work.	Machinery / equipment / vehicles having latest certificate of maintenance;	Site inspection and physical verification	DPMU	Weekly
	All demolition work shall be restricted between day time (7.0 AM to 8.0 PM).	muffs to reduce occupation exposure;	Noise quality report		Quarterly (During demolition)
	specific time duration of demolition work.	Noise emitting machineries with protecting damping.			
	Sign board showing site of demolition work and time shall be provided at demolition site;	Use of explosive; blasting operation	Verification of used instrument / machineries;		
	Demolition work will not be permitted at any silence area or zone (100 metres from hospital, school) during active working hours (10 AM to 5 PM); demolition work in		Consultation with local habitants		

Expected Impact	Mitigation Measures	Monitoring Indicators	Means of Verification	Supervising and Monitoring Entity	Monitoring Frequency
	silence zone shall preferably be carried out on weekend and holiday or between 7 A.M to 10 A.M and 5 PM to 8 PM of other weekdays.				
	Heavy noise emitting equipment shall be fitted with silencer. Noise barrier shall be provided to generator set.				
	Reducing the noise produced from a vibrating machine by vibration damping i.e. making a layer of damping material (rubber, neoprene, cork or plastic) beneath the machine.		Site inspection and physical verification	DPMU	Weekly
	Explosion or blasting operation shall not be performed within 500-meter periphery of nearby local habitat or structure.	Blasting sites and measure adopted to reduce effect of vibration;	Consultation with local habitants		
	Contractor shall conduct vibration testing during blasting operation (if any) by engaging any third party at least at ten (10 - for whole project) location. Testing location shall be identified in consultation with DPMU and submit vibration report to DPMU.	Damage due to blasting/ vibration	Vibration testing;	Contractor	During Blasting Operation/ Each Site
	Demolition workers shall be provided with PPEs (earmuff) to minimise health impact due to noise pollution				
	The Contract Package ESMPs and Contractors ESMPs will specify the list of sensitive receptors (given in Section 4.16).				
	Regular monitoring of air emissions at the Sensitive Receptor locations.				
Vertical water fall with high velocity on the downstream side of crest may cause erosion	Apron/ wave breaker where ever required shall be provided for decapitation of excess energy	Apron/ wave breaker provided	Site inspection and physical verification	DPIU/ DPMU	Monthly
	Reuse of dismantled materials to the possible extent (C&D waste management plan given in Section 7.3.1	Reuse and disposal of C&D items Water quality in nearby river/ stream;	Water quality report; Site inspection;	DPMU	Weekly
from dismantling structures and spoil	shall be applied); Unused / unusable materials shall be auctioned as per the procedures of Govt. / IWD or left-over C&D waste shall be disposed-off in the nearby sanitary landfill site.		Review of records / reports		