

Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

email id- eewmid2012@gmail.com

NIT NO:-WBIW/EE/WMD/NIT 05 of 2016-17

Sl. No. 06

Schedule of Quantity, Unit, Rate and Amount for the work, "Periodical maintenance of Kowari and Kathua Irrigation Scheme for Khariff Irrigation 2016 during the month July to October under Lodhasuli Irrigation Section of Jhargram Irrigation Sub-Division within West Midnapore Division.


Amount put to Tender : ₹ 306,707.00

Earnest Money : ₹ 6,134.00

Time allowed for Completion : 120 days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge	25350.00	Sqm	₹ 7.70	Rupees seven and paise seventy only	₹ 195,195.00
2	Earthwork in excavation by any means from borrowpits, canals and channels in all kinds of soil for maintenance and repairs of embankments, canals, channels and roads as per profile within an initial lead of 30 metres and lift of 1.50 metre including breaking clods, rough dressing, including removal of jungles and trees upto 30 cm. girth in both cutting and filling zone etc. complete as per direction of Engineer-in-charge	994.00	Cum	₹ 76.70	Rupees seventy six and paise seventy only	₹ 76,240.00
3	Extra rate for earthwork in Item no. 2 above for each additional lead of 30 metres or part there of beyond the initial lead of 30 metre. (one no lead)	86.00	Cum	₹ 15.40	Rupees fifteen and paise forty only	₹ 1,324.00
4	Supplying, dressing and stacking at site bamboo pins (diameter to be measured at mid length) (a) Above 5 cm to 7.50 cm diameter.	630.00	M	₹ 23.60	Rupees twenty three and paise sixty only	₹ 14,868.00
5	Driving bamboo pins of average 5 cm to 7.5 cm diameter (payment will be made for driven length only) (i) Where boats are not necessary	315.00	M	₹ 6.30	Rupees six and paise thirty only	₹ 1,985.00
6	Supplying, fitting, fixing with iron nails, half split bamboo wailing pieces. (Diameter of bamboo not less than 5 cm, to be measured at mid length)	160.00	M	₹ 19.30	Rupees nineteen and paise thirty only	₹ 3,088.00
7	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	580	each	5.00	Rupees five and paise zero only	₹ 2,900.00
8	Supply of Labour (Mazdoor)	30	Day	₹ 206.00	Rupees two hundred six only	₹ 6,180.00
9	Filling polly bags with all kinds of earth (wet or dry) including sewing after filling and placing in position within an initial lead of 150 metre.	580	each	₹ 6.30	Rupees six and paise thirty only	₹ 3,654.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
10	Cement concrete with 32 mm down well graded coarse aggregate in piers, abutments, wing walls, retaining walls, bracket walls etc. (above PL or DBL) including shuttering, staging and curing supply and carriage of all materials to site of work.	0.225	Cum	5656.10	Rupees five thousand six hundred fifty six and paise ten only	₹ 1,273.00
Total Amount put to Tender in figure =						₹ 306,707.00
Total Amount put to Tender in word :		Rupees two lakh forty seven thousand six hundred and thirty seven only				


 Executive Engineer
 West Midnapore Division
 Irrigation & Waterways Dte.
 Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

 (Signature of the Contractor)