

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer,
Page 1 of 1
West Midnapore Division
Medinipur, Paschim Medinipur

WBIW/EE/WMD/NIT-05 of 2016-17

Schedule of Quantity, Unit, Rate and Amount for the work, "Sealing of Parbotipur & Jadupur Singe Vent Sluices over Mohankhali & Chetua Circuit Embankment respectively in c/w forthcoming monsoon- 2016 in Block- Daspur- I, Dist. Paschim Medinipur under Dussaspur- I Section of Ghatal Irrigation Sub-Division within West Midnapore Division."


Amount put to Tender : ₹ 39,309.00

Sl. No. 14

Earnest Money : ₹ 786.00

Time allowed for Completion : 120 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	172.00	sqm	₹ 7.70	Rupees seven and paise seventy only	₹ 1,324.00
1	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	1666.00	each	₹ 5.00	Rupees five only	₹ 8,330.00
2	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge.	1666.00	each	₹ 6.30	Rupees six and paise thirty only	₹ 10,496.00
3	Extra rate in Sl. no. 2 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres.	1666.00	each	₹ 9.20	Rupees nine and paise twenty only	₹ 15,327.00
	4 (four) Extra Lead					
4	Dumping in position earth filled polly bags inclusive of all leads and lifts. (admissible only when placed under flowing water)	1666.00	each	₹ 2.30	Rupee two and poise thirty only	₹ 3,832.00
Total Amount put to Tender in figure =						₹ 39,309.00
Total Amount put to Tender in word :						Rupees thirtyninethousand threehundred and nine only


Executive Engineer
West Midnapore Division
Irrigation & Waterways Dte.
Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)

Abstract of Cost