Schedule of work:- "Irrigation Precautionary Measure for Garbeta Branch Canal from Ch.976.00 to Ch.2106.38 in connection with Kharif Irrigation 2016 1st and 2nd watering under Amlagora H.Q, Panikotor & C.K.Town Section of K.C. Sub Divn No.VII during 2016-17".

SI. No.	Description of items	Quantity	Unit	Rate	Amount
1	Ref :- Item No.7,Page no.2 of KC/SOR Cutting and removing ordinary thick or thorny jungles including clearing and depositing the same with all leads and lifts as	1,219.20	SqMt.	10.00	12,192.00
2	Ref:-Item No. 19(b),Page no.13 of KC/SOR Supplying empty cement polythene bags in good condition including stacking and cost of carriage to site complete(Capicity 50 Kg).	200.00	Each	6.00	1,200.00
3	Ref:-Item No. 20,Page no.13 of KC/SOR Labour charges for filling gunny bags / polythene bags with all kinds of earth or sand wet or dry including sewing mouth and stacking within a lead of 150 Metres and all lifts as per direction of the Engineer-in-charge (filled up weight not less than 30 Kgs. (Measurement to be taken in stacks). (filled up volume of gunny / Polythene bag = 0.0226 M³)				
		200.00	Each	6.00	1,200.00
4	Ref :- Item No. 22,Page no.13 of KC/SOR Labour charges for dumping filled up gunny bags / polythene bags in standing or flowing water with or without boats inclusive of placing in position with all leads and lifts complete as per direction of the Engineer-in-charge (Filled weight not less than 30 Kgs.) (Measurement to be taken in stacks).		Each	2.00	600.00
	Defection New Address New Assistance	200.00	Each	3.00	600.00
5	Ref:-Item No.1,Page No.1 of KC/SOR Earth work in excavation in the canals/drainage channels/borrow pits/River bed/Slope of bank as noted below as per designed section & throwing the spoils in layer of 23cm for making banks as per profile or to deposit the same in any other place as wanted by the Engineer - in - charge within an initial lead of 30 metre and initial lift of 2.00 metre including breaking clods,rough dressing etc. complete as per direction of the Engineer - in - charge. a)Local soil/soil mixed with moorum or kankar/silt, dry or moist/slushy silt/sticky soil.				
		120.00	Cum	77.00	9,240.00
	Ref:-Item No.11,Page No. 12 of KC/SOR Supply dressing and stacking at site bamboo pins (Dia to be measured at half half length). (a) Above 6 Cm dia uoto 7.50 cm. dia.	265.20	Metre	21.00	5,569.20
7	Ref :- Item No.12,Page No. 12 of KC/SOR Driving bamboo pins in standing & flowing water including scaffolding and driving appliances.	61.20	Metre	6.00	367.20
		01.20	IVICTIC	0.00	001.20

SI. No.	Description of items	Quantity	Unit	Rate	Amount
8	Ref:-Item No.13,Page No. 12 of KC/SOR Supplying fitting and fixing with iron nails or spikes half split bamboo walling piece (dia of bamboo not less than 6 cm.)				
		105.00	Metre	14.00	1,470.00
	Ref :- Item No.23,Page No.XXII of Daily Labour Wages of KC/SOR Providing Unskilled Mazdoor (Male) for watching,Guarding of Crosss regulator Gates and other allied works as and when				
	required.	120.00	No.	170.50	20,460.00
			•	Total	52,298.40
				Say	52,298.00

Rupees Fifty two thousand two hundred ninety eight only

Asst. Engg. / S.D.O. Kangsabati Canal Sub-Division No. VII Amlagora, Paschim Medinipur

I/We do here by agree to execute the above work @

% Above/Low/At per than the Schedule of Rates attached herewith .

Signature of the Contractor(s)