

**Govt. of West Bengal**  
**Irrigation & Waterways Dte.**  
**Office of the Executive Engineer**  
**West Midnapore Division**  
**Medinipur, Paschim Medinipur**  
**email id - eewmid2012@gmail.com**

**NIT No:- WBIW/EE/WMD/NIT 09 of 2016-17****Sl. No. 8**

Schedule of Quantity, Unit, Rate and Amount for the work, "Flood Precautionary Measure (FPM) of Chetua Circuit Embankment along L/B of River Old Cossye in between Ch. 51.00 Km & 57.00 Km in c/w monsoon- 2016 in Mouzas- Kolmijore, Paikan Durjodhan, Dadpur, Gokulnagar & Jadupur in Block- Daspur- I, Dist. Paschim Medinipur under Dussaspur- I Section of Ghatal Irrigation Sub-Division under West Midnapore Division." (2nd call)

**Amount put to Tender : ₹ 4,49,600.00****Earnest Money : ₹ 8,992.00****Time allowed for Completion : 70 days**

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	2925.00	sqm	₹ 7.70	Rupees seven and paise seventy only	₹ 22,523.00
2	Supplying, dressing and stacking at site bamboo pins (diameter to be measured at mid length (a) Above 5 cm to 7.50 cm diameter.	2880.00	m	₹ 23.60	Rupees twenty three and paise sixty only	₹ 67,968.00
3	Driving bamboo pins of average 5 cm to 7.5 cm diameter (payment will be made for driven length only) (i) Where boats are not necessary	1920.00	m	₹ 6.30	Rupees six and paise thirty only	₹ 12,096.00
4	Supplying, fitting, fixing with iron nails, half split bamboo wailing pieces. (Diameter of bamboo not less than 5 cm, to be measured at mid length)	624.00	m	₹ 19.30	Rupees nineteen and paise thirty only	₹ 12,043.00
5	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	10330.00	each	₹ 5.00	Rupees five only	₹ 51,650.00
6	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge.	10330.00	each	₹ 6.30	Rupees six and paise thirty only	₹ 65,079.00
7	Extra rate in Sl. No. 6 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres.  5 (five) Extra Lead	10330.00	each	(₹ 2.30 x 5) = ₹ 11.50	Rupees eleven three and paise fifty only	₹ 1,18,795.00
8	Earthwork, transporting the earth by manually operated thela/ van/ ricksaw etc. beyond the lead of 150 metres and upto 500 metre including removal of jungle and trees upto 30 cm girth, all cost of excavation of earth in all kinds of soil, loading, transporting, unloading, stacking, placing the same or making embankments, rough dressing etc. including all lifts, as directed by the Engineer-in-charge.	360.00	cum	₹ 138.90	Rupees one hundred thirty eight and paise ninety only	₹ 50,004.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
9	Extra rate in Sl. No. 8 above for each additional lead of 500 metre or part there of beyond the initial lead of 500 metre. NB:- This item is applicable only where the track/ tractors are not accessible at site. 3 (three) Extra Lead	360.00	cum	(₹ 20.70 x 3) = ₹ 62.10	Rupees sixty two and paise ten only	₹ 22,356.00
10	SUPPLY OF LABOUR : Mazdoor	108.00	Per Day	₹ 206.00	Rupees two hundred six only	₹ 22,248.00
11	Supplying 500 C. P. incandescent lamp (i.e. Petromax daylight, Hasag etc.) on hire basis for 10 hours including supply of necessary fuel etc. complete.	36.00	each	₹ 134.40	Rupees one hundred thirty four and paise forty only	₹ 4,838.00
Total Amount put to Tender in figure =						₹ 4,49,600.00
Total Amount put to Tender in word :						Rupees four lakh forty nine thousand and six hundred only

  
 Executive Engineer  
 West Midnapore Division  
 Irrigation & Waterways Pte.  
 Paschim Medinipur

I / We do hereby agree to do the above work @ .....

Above / Less / At par than this Schedule Of Rates attached herewith.

\_\_\_\_\_  
(Signature of the Contractor)