

Schedule of works for SI No. -1 of NIT No. -09/SDO/KC SD-XII/2016-17

Schedule of quantity, rate & amount for items of work for the work :-M/R to Electrical installation work of S.D.O-XII' Qtr. at Sekhpura Kangsabati Colony in H.Q.Section of K.C.Sub-Division No-XII under K.C.Division No-IV					
Amount Put To Tender		: Rs. 26000.00			
Earnest Money		: Rs. 520.00			
Time allowed for Completion		: 7 Days			
SI No	Item	Qty	Unit	Rate	Amt (Rs.)
1	Supplying and fixing Sheet steel Main Switches on flat iron frame on wall 15/16 A Anchor 240V DP with fuse on L&N	1	Each	500.00	500.00
2	Wiring in 1.1 KV grade single core stranded 'FR' PVC insulated & unsheathed copper wire (Brand approved by EIC) of following sizes in 25mm PVC casing-capping (Precision make) incl. necy. PVC clips, fittings etc. (c) 2 x 36/0.3 (2.5 sqmm) + 1 x 22/0.3 (1.5 sqmm)	38	RM	118.00	4484.00
3	Distribution wiring in 1.1 KV grade 2x22/0.3 (1.5 sqmm) single core stranded 'FR' PVC insulated & unsheathed copper wire (Brand approved by EIC) in suitable size PVC casing-capping (Precision make) with 1x22/0.3 (1.5 sqmm) single core stranded 'FR' PVC insulated & unsheathed copper wire for ECC, incl. necy. PVC clips, fittings etc. to light/fan/call bell point with piano key type switch (Anchor make) fixed on sheet steel fabricated switch board with Perspex/bakelite top cover on wall incl. necy. connections and making earthing attachment and mending good damages to building works. [PVC casing-capping and Switch board both on surface] (a) Average run 5 mtr	28	point	659.00	18452.00
4	Supplying and fixing 240/415 V MCB of Breaking capacity 10kA & C characteristics on din rail of existing DBs and necessary connection (6-32 A) SP Havells	2	Each	198.00	396.00
5	Supply & Fixing 240 V, 20A, plug socket with separate 20 A Piano key type switch (Brand approved by EIC) on sheet metal switch board embedded in wall incl. S & F 150x100x65mm MS (16SWG) switch board and bakelite/perspex top cover of 3mm thick by Brass screws after making housing for switch by cutting bakelite/perspex cover and making necessary connections as required	3	Each	324.00	972.00
6	Supply & Fixing angular batten holder (Anchor) on 75mm dia PVC round block / round bakelite on wall/ceiling.	6	Each	43.00	258.00

SI No	Item	Qty	Unit	Rate	Amt (Rs.)
7	Excavation of soil for installation of Earth Electrode and filling & ramming For Soft Soil	2	Cum	215.00	430.00
8	Connecting the equipments to earth busbar including S & F GI (Hot Dip) wire of size as below on wall/floor with staples buried inside wall/floor as required and making connection to equipments with bolts, nuts, washers, cable lugs etc. as required and mending good damages (a) Solid GI wire (iv) No. 10 SWG	28	RM	6.00	168.00
9	Supplying & fixing earth busbar of galvanized (Hot Dip) MS flat 25 mm x 6 mm on wall having clearance of 6 mm from wall including providing drilled holes on the busbar complete with GI bolts, nuts, washers, spacing insulators etc. as required	2	RM	170.00	340.00
				Total =	26000.00

(Rupees Twenty Six thousand) only.

(A.K.Pal)
Sub Divisional Officer
K.C Sub Div. -XII, Midnapur

I / We do hereby agree to execute the above work @ % (in figure)
..... (in words) percent above /at par /
below than the schedule of rates. I shall abide by all terms and conditions laid down in the NIT & WBF 2911(ii)
and in the printed schedule, specification etc. of Kangsabati Circle/PWD now in force.

[Signature of the Contractor]