

Schedule of works for SI No. -2 of NIT No. -09/SDO/KC SD-XII/2016-17

Schedule of quantity, rate & amount of items for the work :-M/R to Installation of Busbar Chambers at Meter Box in K.C Division-IVs Office premises in Hd. Qtr. Section of K.C.Sub Division No-XII under K.C.Division No-IV, Midnapore

Amount Put To Tender : Rs. 6642.00

Earnest Money : Rs. 133.00

Time allowed for Completion : 3 Days

Sl. No.	Items of Works	Unit	Quantity	Rate (Rs.)	Amount (Rs.)
1	Suplling and fixing sheet metal(16SWG) iron clad Busbar Chambers on angle iron frame on wall including earthing attachment and painting as required(as per Drg. No. 470 of P.W.D specification Book -May,1991) (a) 2 Bars 240V,63A Dimension of Al. Bar(85 mm long) 2X20X5 mm, Dimension of sheet metal Box (300X150mm)	Mt	3.60	1845.00	6642.00
				Total=	6642.00

(Rupees Six thousand six hundred forty two) only

(A.K.Pal)

Sub Divisional Officer
K.C Sub Div. -XII, Midnapur

I / We do hereby agree to execute the above work @ % (in figure) (in words) percent above /at par / below than the schedule of rates. I shall abide by all terms and conditions laid down in the NIT & WBF 2911(ii) and in the printed schedule, speication etc. of Kangsabati Circle/PWD now in force.

[Signature of the Contractor]