

Schedule of works for SI No. -3 of NIT No. -09/SDO/KC SD-XII/2016-17

Schedule of quantity, rate & amount for items for the work :- M/R to painting of
Godown Shed at Narampura Kangsabati Colony in Hd. Qtr. Section of K.C.Sub
Division No-XII under K.C.Division No-IV, Midnapore

Earnest Money : **Rs. 485.00**

Time allowed for Completion : **7 Days**

Amount Put To Tender : **Rs. 24240.00**

Sl. No.	Items of Works	Unit	Quantity	Rate (Rs.)	Amount (Rs.)
1	(b) Priming one coat on steel or other metal surface with synthetic oil bound primer of approved quality including smoothening surfaces by sand papering etc.	Sqm	303.00	31.00	9393.00
2	(A) Painting with best quality synthetic enamel paint of approved make and brand including smoothening surface by sand papering etc. including using of approved putty etc. on the surface, if necessary: (b) On steel or other metal surface : With other than hi-gloss of approved quality- (iii) One coat (with any shade except white)	Sqm	303.00	49.00	14847.00
				Total=	24240.00

(Rupees Twenty four thousand two hundred forty) only

(A.K.Pal)
Sub Divisional Officer
K.C Sub Div. -XII, Midnapur

I / We do hereby agree to execute the above work @ % (in figure)
..... (in words) percent **above /at par / below** than the schedule of rates. I shall abide by all terms and conditions laid down in the NIT & WBF 2911(ii) and in the printed schedule, specification etc. of Kangsabati Circle/PWD now in force.

[Signature of the Contractor]