

Schedule for the work: "M/R to Dy. No.18 of M.B.C. from ch.0.00 to ch.10.00 along with Construction of Cast-in-situ Lining on canal side slope from ch.9.00 to ch.9.30 (L/B) under Ramgarh Section of K.C. Sub-Divn.No.IV, Sarenga under K.C. Divn. No.I, Amlagora during 2016-17

Sl. No.	Description of Item	Quantity	Unit	Rate (Rs.)	Unit	Amount (Rs.)
1	Cutting and removing ordinary thick or thorny jungles including clearing and depositing the same with all leads and lifts as per direction of the Engineer-in-Charge.	365.76	Sqm.	10.00	Sqm.	3658.00
2	Earthwork in excavation in the canals / drainage channels / borrowpits / River bed / slope of bank as noted below as per designed section & throwing the spoils in layer of 23 cm. for making banks as per profile or to deposit the same in any other place as wanted by the Engineer-in-Charge within an initial lead of 30 metre and initial lift of 2.00 metre including breaking clods, rough dressing etc. complete as per direction of the Engineer-in-Charge. (Including dewatering as necessary) a) Local soil / soil mixed with moorum or kankar / silt, dry or moist / slushy silt / sticky soil.	194.69	Cum.	77.00	Sqm.	14991.00
3	Earthwork in filling in layers not exceeding 25cm including watering and ramming with all leads and lifts. b) Earth borrowed from outside	17.31	Cum.	83.00	Cum.	1437.00
4	Extra rate for puddling, watering & ramming etc. complete as per direction of the Engineer-in-Charge.	17.31	Cum.	23.00	Cum.	398.00
5	Preparing sub grade for lining including cutting and filling earth watering, hand ramming and fine dressing as per direction of Engineer-in-charge complete	23.50	Sqm.	12.00	Sqm.	282.00
6	Cement concrete lining with cast in situ blocks in canal bed and slope with 20mm down coarse aggregate (stone chips) including drop walls as per direction and drawing including necessary a) Prop. 1:2:4	4.43	Cum.	5248.00	Cum.	23249.00
Total					Rs.-	44015.00

(Rupees forty four thousand and fifteen only)

Amy...
Executive Engineer
K.C. Division No. I

Amlagora, Paschim Medinipur
201.09.16

I/We do here by agree to execute the above work @

% Above/Low/At per than the Schedule of Rates attached herewith .

Signature of the Contractor(s) ,