Govt. of West Bengal,
Irrigation & Waterways Directorate,
Office of the Executive Engineer,
Kaliaghai-Kapaleswari-Baghai Project Division,
Temathani (Sabang), Paschim Medinipur

Corrigendum No.1 to

Notice Inviting Tender No. WBIW/EE/KKBPD/NIT-08/2016-17 of Kaliaghai-Kapaleswari-Baghai Project Division (I&W Dtc.) issued vide this Office Memo No. 927^E Dated 23/09/2016

Due to some unavoidable circumstances the following changes are being made against SI No.-6 to 9 of the above mentioned NIT and in Schedule of respective SI.

Sl. No.	ne to some unavoidable circumstances the following changes are being mad Name of Work	Amount put to tender (In Rs.)	Earnest Money (In Rs.)	Cost of Tender paper with Schedule (In Rs.)	Time allowed for completion	Contractors eligibility for participation
1	2	3	4	5	6	7
6	Read As Restoration of Side Slip near Ch 3.950 Km at R/S of Kolonda Ex-Zamindary Bundh R/B of Deuli River at Mouza- Chaksafi, Block: Sabang, Dist. Paschim Medinipur under K. K. B. Project Sub- Division No. I of K.K.B. Project Division Instead of Abstract cost for "Restoration of Side Slip near Ch 3.950 Km at R/S of Kolonda Ex-Zamindary Bundh R/B of Deuli River at Mouza- Chaksafi, Block: Sabang, Dist. Paschim Medinipur under K. K. B. Project Sub- Division No. I of K.K.B. Project Division	No Change	No Change	No Change	No Change	No Change
7	Read As Restoration of crest depression near Ch4.05 Km of Kolonda Ex-Zamindary Bundh R/B of Deuli River at Mouza- Chaksafi, Block: Sabang, Dist. Paschim Medinipur under K. K. B. Project Sub- Division No. I of K.K.B. Project Division Instead of Abstract cost for "Restoration of crest depression near Ch4.05 Km of Kolonda Ex-Zamindary Bundh R/B of Deuli River at Mouza- Chaksafi, Block: Sabang, Dist. Paschim Medinipur under K. K. B. Project Sub- Division No. I of K.K.B. Project Division.	No Change	No Change	No Change	No Change	No Change
8	Read As Restoration of Side Slip near Ch 3.450 Km at R/S of Kolonda Ex-Zamindary Bundh R/B of Deuli River at Mouza- Chaksafi, Block: Sabang, Dist. Paschim Medinipur under K. K. B. Project Sub- Division No. I of K.K.B. Project Division. Instead of Abstract cost for "Restoration of Side Slip near Ch 3.450 Km at R/S of Kolonda Ex-Zamindary Bundh R/B of Deuli River at Mouza- Chaksafi, Block: Sabang, Dist. Paschim Medinipur under K. K. B. Project Sub- Division No. I of K.K.B. Project Division.	No Change	No Change	No Change	No Change	No Change
8	Read As Restoration of Side Slip near Ch 3.120 Km at R/S of Kolonda Ex-Zamindary Bundh R/B of Deuli River at Mouza- Chaksafi, Block: Sabang, Dist. Paschim Medinipur under K. K. B. Project Sub- Division No. I of K.K.B. Project Division. Instead of Abstract cost for "Restoration of Side Slip near Ch 3.120 Km at R/S of Kolonda Ex-Zamindary Bundh R/B of Deuli River at Mouza- Chaksafi, Block: Sabang, Dist. Paschim Medinipur under K. K. B. Project Sub- Division No. I of K.K.B. Project Division.	No Change	No Change	No Change	No Change	No Change

a	Date, time and Place for Dropping Tender Forms	No Change	No Change	No Change
b	Date, time and Place for Opening Tender Forms	No Change	No Change	No Change

Shits.

Executive Engineer Kaliaghai-Kapaleswari-Baghai-Project Division Temathani (Sabang), Paschim Medinipur Memo No. 945 Date: 29.09.2016

Copy for information & wide Circulation to the:-

- 1. Chief Engineer, South-West I & W Dte. Khas jungle, Abash, Paschim Midnapore.
- 2. Superintending Engineer, Western Circle, II, I & W Dte. Midnapore, Paschim Medinipur.
- 3. Sabhadhipati, Paschim Medinipur ZillaParishad, Midnapore.
- 4. Sabhadhipati, Purba Medinipur ZillaParishad, Tamluk, Purba Medinipur.
- 5. Executive Engineer, East Midnapur Division, I & W Dte. Tamluk, Purba Medinipur.
- 6. Executive Engineer, Contai Irrigation Division. I &W. Dte. Contai, Purba Medinipur.
- 7. Executive Engineer, West Midnapore Division. I &W. Dte. Midnapore, Paschim Medinipur.
- 8. Executive Engineer, Kangsabati Canal Division No.- IV, I &W.Dte., Midnapore, Paschim Medinipur.
- 9. Sub-Divisional Officer. /K.K.B Project Sub Division-I, I&W. Dte. Temathani (Sabang), Paschim Medinipur.
- 10. Sub- Divisional Officer. /K.K.B Project Sub Division-II, I&W. Dte. Sabang, Paschim Medinipur.
- 11. Sub-Divisional Officer. /K.K.B Project Sub Division-III, I&W. Dte. Sabang, Paschim Medinipur. .
- 12. Secretary, Midnapore Sadar/ Contai/ Ghatal/ Jhargram/ Khargapur Sub- Divisional contractors' Association.
- 13. Secretary, Association of Paschim Medinipur Engineers' Co-operative societies Ltd, Midnapore, Paschim Medinipur.
- 14. Office Notice Board/ Divisional Accounts Officer / Estimating Section /Hd. Clerk / Cash Section of Kaliaghai-Kapaleswari-Baghai Project Division.

Executive Engineer Kaliaghai-Kapaleswari-Baghai-Project Division Temathani (Sabang), Paschim Medinipur

Government of West Bengal Irrigation & Waterways Directorate Office of the Executive Engineer Kaliaghai-Kapaleswari-Baghai Project Division

Temathani (Sabang), Paschim Medinipur.

Notice Inviting Tender No.08 of 2016-2017, Sl. No.6

Restoration of Side Slip near Ch 3.950 Km at R/S of Kolonda Ex-Zamindary Bundh R/B of Deuli River at Mouza- Chaksafi, Block: Sabang, Dist. Paschim Medinipur under K. K. B. Project Sub- Division No. I of K.K.B. Project Division.

Amount Put to Tender- Rs. 3,39,978.00 Earnest Money- Rs. 6,800.00

Time allowed for completion- 25 Days

	Time allowed for completion- 25 Days				
Sl.No.	Description of Items	Quantity	Unit	Rate in Rs.	Amount in Rs.
	Supplying Eucalyptus-bullah piles at work site, including dressing and				
1	making one end pointed.				
	(i)150mm diameter	910.00	Mtr	217.00	197470.00
	Labour for driving Sal-bullah / Eucalyptus bullah piles by monkey in				
	sorts of soil including hoisting and placing piles in position, protecting				
2	the pile head with iron ring and cutting and shaping heads before and				
2	after driving and including hire and labour for necessary driving				
	appliances and all tackles				
	(i) 150mm diameter	782.60	Mtr	105.00	82173.00
	Supplying and fitting fixing with iron nails, half split Eucalyptus Bullah	410.00	Mtr	54.80	22468.00
3	wailing pieces and cross pieces with the thicker end as specified below with				
3	cost of all materials and carriage to site etc. complete. a) Above				
	10.00 cm & up to 12.50 cm				
	Supplying, dressing and stacking at site bamboo pins (diametre to be	237.30	Mtr	23.60	5600.00
4	measured at mid length.				
	(a) Above 5 cm to 7.50 cm diametre.				
	Driving bamboo pins of average 5 cm to 7.5 cm diametre (payment will	169.50	Each	6.30	1068.00
5	be made for driven length only).				
	(i) Where boats are not necessary				
	Supplying to site 2nd hand cement polly bags in good condition	502.00	Each	0.00	0.00
6	delivered and stacked (capacity 50 kg). (Departmental)	302.00	Lacii	0.00	0.00
	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds	502.000	Each	6.30	3163.00
	of earth (wet or dry) or sand including sewing the mouth after filling (cost of	302.000	Lucii	0.50	3103.00
	thread included), as done in case of cement bags, (tying with a knot after filling				
7	will not be accepted) and placing in position within an initial lead of 150				
,	metres including cost of excavation of earth as per direction of the Engineer-in-				
	charge. NB:- Volume of earth/ sand filled bags should not be less than 0.028				
	m3/ bag.				
	Earthwork in excavation by any means from borrowpits, canals and	315.00	Cum	76.70	24161.00
	channels in all kinds of soil for maintenance and repairs of			, , , ,	
	embankments, canals, channels and roads as per profile within an initial				
8	lead of 30 metres and lift of 1.50 metre including breaking clods, rough				
	dressing, including removal of jungles and trees upto 30 cm. girth in				
	both cutting and filling zone etc. complete as per direction of Engineer-				
	in-charge				
	Extra rate for earthwork in Item no.8 above for each additional lead of	315.00	Cum	7.70	2426.00
9	30 metres or part there of beyond the initial lead of 30 metre.	212.00	C 3111	,., 0	2.20.00
,	1 (one) extra lead				
	Extra rate for earthwork in Item no. 8 above for each additional lift of	215.00	Cura	1.60	1440.00
			Cum	4.60	1449.00
10	1.5 metres or part thereof beyond the initial lift of 1.5 metre. all kind of				
	soil.				
	1 (One) Extra lift			m / 1	D 2 20 070 00
				Total	Rs. 3,39,978.00

(Rupees Three lakhs Thirty-nine thousand nine hundred seventy-eight only)

Executive Engineer
K.K.B. Project Division I & W Dte.
Temathani (Sabang), Paschim Medinipur

I / We do hereby agree to do the above work @	()
Above / less / at par than the Schedule of Rates attached herewith.	
	(Signature of the contractor)

Government of West Bengal Irrigation & Waterways Directorate Office of the Executive Engineer Kaliaghai-Kapaleswari-Baghai Project Division Temathani (Sabang), Paschim Medinipur.

Notice Inviting Tender No.08 of 2016-2017, Sl. No.7

Restoration of crest depression near Ch4.05 Km of Kolonda Ex-Zamindary Bundh R/B of Deuli River at Mouza- Chaksafi, Block: Sabang, Dist. Paschim Medinipur under K. K. B. Project Sub- Division No. I of K.K.B. Project Division.

Amount Put to Tender- Rs. 4,37,314.00 Earnest Money- Rs. 8,746.00

Time allowed for completion- 25 Days

	l ime allowed for completion- 25 Days				
Sl.No.	Description of Items	Quantity	Unit	Rate in Rs.	Amount in Rs.
	Supplying Eucalyptus-bullah piles at work site, including dressing and				
1	making one end pointed.				
	(i)150mm diameter	985.00	Mtr	217.00	213745.00
	Labour for driving Sal-bullah / Eucalyptus bullah piles by monkey in				
	sorts of soil including hoisting and placing piles in position, protecting				
2	the pile head with iron ring and cutting and shaping heads before and				
2	after driving and including hire and labour for necessary driving				
	appliances and all tackles				
	(i) 150mm diameter	880.10	Mtr	105.00	92411.00
	Supplying and fitting fixing with iron nails, half split Eucalyptus Bullah	590.00	Mtr	54.80	32332.00
3	wailing pieces and cross pieces with the thicker end as specified below with				
3	cost of all materials and carriage to site etc. complete. a) Above				
	10.00 cm & up to 12.50 cm				
	Supplying, dressing and stacking at site bamboo pins (diametre to be	342.30	Mtr	23.60	8078.00
4	measured at mid length.				
	(a) Above 5 cm to 7.50 cm diametre.				
	Driving bamboo pins of average 5 cm to 7.5 cm diametre (payment will	244.50	Each	6.30	1540.00
5	be made for driven length only).				
	(i) Where boats are not necessary				
6	Supplying to site 2nd hand cement polly bags in good condition	725.00	Each	0.00	0.00
O	delivered and stacked (capacity 50 kg). (Departmental)				
	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds	725.000	Each	6.30	4568.00
7	of earth (wet or dry) or sand including sewing the mouth after filling (cost of				
	thread included), as done in case of cement bags, (tying with a knot after filling				
	Earthwork in excavation by any means from borrowpits, canals and		Cum	76.70	72942.00
	channels in all kinds of soil for maintenance and repairs of				
	embankments, canals, channels and roads as per profile within an initial				
8	lead of 30 metres and lift of 1.50 metre including breaking clods, rough				
	dressing, including removal of jungles and trees upto 30 cm. girth in				
	both cutting and filling zone etc. complete as per direction of Engineer-				
	in-charge				
	Extra rate for earthwork in Item no.8 above for each additional lead of	951.00	Cum	7.70	7323.00
9	30 metres or part there of beyond the initial lead of 30 metre.				
	1 (one) extra lead				
	Extra rate for earthwork in Item no. 8 above for each additional lift of		Cum	4.60	4375.00
10	1.5 metres or part thereof beyond the initial lift of 1.5 metre. all kind of				
- 0	soil.				
	1 (One) Extra lift				D 40-011-
				Total	Rs. 4,37,314.00

(Rupees Fore lakhs Thirty-seven thousand three hundred and fourteen only)

Executive Engineer
K.K.B. Project Division I & W Dte.
Temathani (Sabang), Paschim Medinipur

I / We do hereby agree to do the above work @(()	
Above / less / at par than the Schedule of Rates attached herewith.		

(Signature of the contractor)

Government of West Bengal Irrigation & Waterways Directorate Office of the Executive Engineer Kaliaghai-Kapaleswari-Baghai Project Division Temathani (Sabang), Paschim Medinipur.

Notice Inviting Tender No.08 of 2016-2017, Sl. No.8

Restoration of Side Slip near Ch 3.450 Km at R/S of Kolonda Ex-Zamindary Bundh R/B of Deuli River at Mouza- Chaksafi, Block: Sabang, Dist. Paschim Medinipur under K. K. B. Project Sub- Division No. I of K.K.B. Project Division.

Amount Put to Tender- Rs. 1,58,456.00 Earnest Money- Rs. 3,169.00

Time allowed for completion- 25 Days

CLAI	Time allowed for completion-	25 Da	-	D D	
Sl.No.	Description of Items	Quantity	Unit	Rate in Rs.	Amount in Rs.
	Supplying Eucalyptus-bullah piles at work site, including dressing and				
1	making one end pointed.	44.0.00		217.00	
	(i)150mm diameter	410.00	Mtr	217.00	88970.00
	Labour for driving Sal-bullah / Eucalyptus bullah piles by monkey in				
	sorts of soil including hoisting and placing piles in position, protecting				
2	the pile head with iron ring and cutting and shaping heads before and				
	after driving and including hire and labour for necessary driving				
	appliances and all tackles	2.72 (0	3.6	105.00	25022.00
	(i) 150mm diameter	352.60	Mtr	105.00	37023.00
3	Supplying and fitting fixing with iron nails, half split Eucalyptus Bullah wailing pieces and cross pieces with the thicker end as specified below with cost of all materials and carriage to site etc. complete. a) Above 10.00 cm & up to 12.50 cm	285.00	Mtr	54.80	15618.00
4	Supplying, dressing and stacking at site bamboo pins (diametre to be measured at mid length. (a) Above 5 cm to 7.50 cm diametre.	106.05	Mtr	23.60	2503.00
	× /	75.75	E. 1	(20	477.00
5	Driving bamboo pins of average 5 cm to 7.5 cm diametre (payment will be made for driven length only).	75.75	Each	6.30	477.00
3	· ,				
	(i) Where boats are not necessary Supplying to site 2nd hand cement polly bags in good condition	223.00	Each	0.00	0.00
6	delivered and stacked (capacity 50 kg). (Departmental)	223.00	Each	0.00	0.00
	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds	223.000	Each	6.30	1405.00
7	of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling	223.000	Lacii	0.30	1403.00
8	Earthwork in excavation by any means from borrowpits, canals and channels in all kinds of soil for maintenance and repairs of embankments, canals, channels and roads as per profile within an initial lead of 30 metres and lift of 1.50 metre including breaking clods, rough dressing, including removal of jungles and trees upto 30 cm. girth in both cutting and filling zone etc. complete as per direction of Engineer-in-charge	140.00	Cum	76.70	10738.00
	Extra rate for earthwork in Item no.8 above for each additional lead of	140.00	Cum	7.70	1078.00
9	30 metres or part there of beyond the initial lead of 30 metre.				
-	1 (one) extra lead				
10	Extra rate for earthwork in Item no. 8 above for each additional lift of 1.5 metres or part thereof beyond the initial lift of 1.5 metre. all kind of soil. 1 (One) Extra lift	140.00	Cum	4.60	644.00
	I (OIIC) EAUX IIII			Total	Rs. 1,58,456.00
				10141	165. 1,50,750.00

(Rupees One lakhs fifty-eight thousand foue hundred fifty-six only)

Executive Engineer
K.K.B. Project Division I & W Dte.
Temathani (Sabang), Paschim Medinipur

I / We do hereby agree to do the above work @()
Above / less / at par than the Schedule of Rates attached herewith.	

(Signature of the contractor)

Government of West Bengal Irrigation & Waterways Directorate Office of the Executive Engineer Kaliaghai-Kapaleswari-Baghai Project Division

Temathani (Sabang), Paschim Medinipur.

Notice Inviting Tender No.08 of 2016-2017, Sl. No.9

Restoration of Side Slip near Ch 3.120 Km at R/S of Kolonda Ex-Zamindary Bundh R/B of Deuli River at Mouza- Chaksafi, Block: Sabang, Dist. Paschim Medinipur under K. K. B. Project Sub- Division No. I of K.K.B. Project Division, I & W Dte.

Amount Put to Tender- Rs. 4,52,086.00 Earnest Money- Rs. 9,042.00

Time allowed for completion- 25 Days

	I ime allowed for completion-	25 Da	ıys		
Sl.No.	Description of Items	Quantity	Unit	Rate in Rs.	Amount in Rs.
	Supplying Eucalyptus-bullah piles at work site, including dressing and				
1	making one end pointed.				
	(i)150mm diameter	1,210.00	Mtr	217.00	262570.00
	Labour for driving Sal-bullah / Eucalyptus bullah piles by monkey in				
	sorts of soil including hoisting and placing piles in position, protecting				
2	the pile head with iron ring and cutting and shaping heads before and				
2	after driving and including hire and labour for necessary driving				
	appliances and all tackles				
	(i) 150mm diameter	1040.60	Mtr	105.00	109263.00
	Supplying and fitting fixing with iron nails, half split Eucalyptus Bullah		Mtr	54.80	29866.00
3	wailing pieces and cross pieces with the thicker end as specified below with				
3	cost of all materials and carriage to site etc. complete. a) Above				
	10.00 cm & up to 12.50 cm				
	Supplying, dressing and stacking at site bamboo pins (diametre to be	316.05	Mtr	23.60	7459.00
4	measured at mid length.				
	(a) Above 5 cm to 7.50 cm diametre.				
	Driving bamboo pins of average 5 cm to 7.5 cm diametre (payment will	210.70	Each	6.30	1327.00
5	be made for driven length only).				
	(i) Where boats are not necessary				
6	Supplying to site 2nd hand cement polly bags in good condition	670.00	Each	0.00	0.00
O	delivered and stacked (capacity 50 kg). (Departmental)				
	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds	670.00	Each	6.30	4221.00
	of earth (wet or dry) or sand including sewing the mouth after filling (cost of				
	thread included), as done in case of cement bags, (tying with a knot after filling				
7	will not be accepted) and placing in position within an initial lead of 150				
	metres including cost of excavation of earth as per direction of the Engineer-in-				
	charge. NB:- Volume of earth/ sand filled bags should not be less than 0.028				
	m3/ bag.				
	Earthwork in excavation by any means from borrowpits, canals and	420.00	Cum	76.70	32214.00
	channels in all kinds of soil for maintenance and repairs of				
	embankments, canals, channels and roads as per profile within an initial				
8	lead of 30 metres and lift of 1.50 metre including breaking clods, rough				
	dressing, including removal of jungles and trees upto 30 cm. girth in				
	both cutting and filling zone etc. complete as per direction of Engineer-				
	in-charge				
	Extra rate for earthwork in Item no.8 above for each additional lead of	420.00	Cum	7.70	3234.00
9	30 metres or part there of beyond the initial lead of 30 metre.				
	1 (one) extra lead				
	Extra rate for earthwork in Item no. 8 above for each additional lift of	420.00	Cum	4.60	1932.00
1.6	1.5 metres or part thereof beyond the initial lift of 1.5 metre. all kind of				-
10	soil.				
	1 (One) Extra lift				
	a (one) white			Total	Rs. 4,52,086.0

(Rupees four lakhs fifty-two thousand and eighty-six only)

Executive Engineer

K.K.B. Project Division I & W Dte. Temathani (Sabang), Paschim Medinipur

I / We do hereby agree to do the above work @	()
Above / less / at par than the Schedule of Rates attached herewith.	

(Signature of the contractor)