

Page 1 of 2
Govt. of West Bengal
 Irrigation & Waterways Dte.
 Office of the Executive Engineer
 West Midnapore Division
 Medinipur, Paschim Medinipur
 email id- eewmid2012@gmail.com

WBIW/EE/WMD/NIT 15 of 2016-17

Sl. No. 7

Schedule of Quantity, Unit, Rate and Amount for the work, " Urgent repair to rain cuts of DC Embankment in between Ch. 0.00 km & 0.50Km in Block- Daspur-I, Dist- Paschim Medinipur under Dussapur-II section of Ghatat Irrigation Sub-Division under West Midnapore Division, I&W Dte.

Amount put to Tender : ₹ 50,010.00

Earnest Money : ₹ 1,000.00

Time allowed for Completion : 30 days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	126.00	Sqm	₹ 7.70	Rupees seven paise seven zero only	₹ 970.00
2	Supplying, dressing and stacking at site bamboo pins (diametre to be measured at mid length (a) Above 5 cm to 7.50 cm diametre.	60.00	M	₹ 23.60	Rupees twenty three paise six zero only	₹ 1,416.00
3	Driving bamboo pins of average 5 cm to 7.5 cm diametre (payment will be made for driven length only) (i) Where boats are not necessary	30.00	M	₹ 6.30	Rupees six and paise three zero only	₹ 189.00
4	Supplying, fitting, fixing with iron nails, half split bamboo wailing pieces. (Diametre of bamboo not less than 5 cm, to be measured at mid length)	20.00	M	₹ 19.30	Rupees nineteen and paise three zero only	₹ 386.00
5	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	675.00	Each	₹ 5.00	Rupees five and paise zero only	₹ 3,375.00
6	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge.	675.00	Each	₹ 6.30	Rupees six and paise three zero only	₹ 4,253.00
7	Extra rate in item no. 4.02 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres. 5 (five) Extra lead.	675.00	Each	11.50	Rupees sixteen and paise ten zero only	₹ 7,763.00
8	Earthwork, transporting the earth by manually operated thela/ van/ ricksaw etc. beyond the lead of 150 metres and upto 500 metre including removal of jungle and trees upto 30 cm girth, all cost of excavation of earth in all kinds of soil, loading, transporting, unloading, stacking, placing the same or making embankments, rough dressing etc. including all lifts, as directed by the Engineer-in-charge.	157.50	Cum	₹ 138.90	Rupees one hundred thirty eight and paise nine zero only	₹ 21,877.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
9	Extra rate in Sl. No. 8 above for each additional lead 500 metre or part there of beyond the initial lead of 500 metre. NB:- This item is applicable only where the track/ tractor are not accessible at site. 3 (three) Extra Lead	157.50	Cum	62.10	Rupees eighty two and paise eight zero only	₹ 9,781.00
Total Amount put to Tender in figure =						₹ 50,010.00
Total Amount put to Tender in word :						Rupees Fifty thousand and ten only

Executive Engineer
West Medinipur Division
Irrigation & Waterways Dte.
Paschim Medinipur

22/12/16

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)