

Government of West Bengal
Irrigation & Waterways Directorate
Office of the Sub-Divisional Officer
Kangsabati Canals Sub-Division No-XIV
Midnapore, Paschim Medinipur.

Notice Inviting Tender No -04 of SDO, K.C. Sub-Division No-XIV of 2016-2017

M/R to canal bed of MBC in-between ch. 448.00 to 468.00, & ch. 515.00 to ch.525.00 in Bhimpur Section of K.C. Sub Division No-XIV under K.C. Division No-IV during the year 2016-2017

Amount Put To Tender : **Rs. 154816.00**
Earnest Money : **Rs. 3096.00**
Time allowed for Completion : **30 Days**

SL NO.	Description of Item	Quantity	UNIT	RATE (Rs.)	AMOUNT (Rs.)
1	[Ref : Page-2, Item No.- 7(a)] Cutting and removing ordinary thick or thorny jungles including cleaning and depositing the same with all leads and lift as per direction of Engineer-in-Charge.	853.00	Sqm.	10.00	8530.00
2	[Ref.:Page-1, Item No. 1(a)] Earthwork in excavation in the canals / drainage channels / borrowpits / River bed / slope of bank as noted below as per designed section & throwing the spoils in layer of 23 cm. for making banks as per profile or to deposit the same in any other place as wanted by the Engineer-in-Charge within an initial lead of 30 metre and initial lift of 2.00 metre including breaking clods, rough dressing etc. complete as per direction of the Engineer-in-Charge. (Including dewatering as necessary). a) Local soil / soil mixed with moorum or kankar / silt, dry or moist / slushy silt / sticky soil.	1701.00	Cum	77.00	130977.00
3	[Ref.:Page-13, Item No. 20] Extra rate over item No.1 for all kinds of soil for every additional lift of 2.00 metre or part thereof beyond the initial lift of 2.00 metre.	1701.00	Cum	9.00	15309.00
Total Rs =					154816.00

(Rupees one lakh fifty four thousand eight hundred sixteen only)

Sub-Divisional Officer
K.C. Sub-Division No-XIV
Midnapur, Paschim Medinipur.

I / We do hereby agree to execute the above work @ % (in figure) (in words) percent **above /at par / below** than the schedule of rates. I shall abide by all terms and conditions laid down in the NIT & WBF 2911 and in the printed schedule, specification etc. of Kangsabati Circle now in force.

(Signature of the Contractor)