

Page 1 of 2  
**Govt. of West Bengal**  
**Irrigation & Waterways Dte.**  
**Office of the Executive Engineer**  
**West Midnapore Division**  
**Medinipur, Paschim Medinipur**  
**email id- eewmid2012@gmail.com**

**WBIW/EE/WMD/NIT 17 of 2016-17**

**Sl. No. 6**

Schedule of Quantity, Unit, Rate and Amount for the work, " Emergement restroration of Mohankhali Circuit Embankment along L/B of river Dubrachati near Kakramari Khal in between ch. 1.00 km to 1.05 km Mouza- Maguria, in Block- Daspur-II, Dist- Paschim Medinipur under Ajuria section of Ghatal Irrigation Sub-Division under West Midnapore Division". (2nd call)

**Amount put to Tender : ₹ 194,609.00**

**Earnest Money : ₹ 3,892.00**

**Time allowed for Completion : 30 days**

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	376.00	Sqm	₹ 7.70	Rupees seven paise seven zero only	₹ 2,895.00
2	Supplying, dressing and stacking at site bamboo pins (diameter to be measured at mid length (a) Above 5 cm to 7.50 cm diameter.	355.00	M	₹ 23.60	Rupees twenty three paise six zero only	₹ 8,378.00
3	Driving bamboo pins of average 5 cm to 7.5 cm diameter (payment will be made for driven length only) (i) Where boats are not necessary	236.60	M	₹ 6.30	Rupees six and paise three zero only	₹ 1,491.00
4	Supplying, fitting, fixing with iron nails, half split bamboo walling pieces. (Diameter of bamboo not less than 5 cm, to be measured at mid length)	40.00	M	₹ 19.30	Rupees nineteen and paise three zero only	₹ 772.00
5	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	4701	Each	₹ 5.00	Rupees five and paise zero only	₹ 23,505.00
6	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge.	4701	Each	₹ 6.30	Rupees six and paise three zero only	₹ 29,616.00
7	Extra rate in item no. 4.02 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres. 7(seven) extra lead	4701	Each	16.10	Rupees sixteen and paise ten zero only	₹ 75,686.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
8	Earthwork, transporting the earth by manually operated thela/ van/ ricksaw etc. beyond the lead of 150 metres and upto 500 metre including removal of jungle and trees upto 30 cm girth, all cost of excavation of earth in all kinds of soil, loading, transporting, unloading, stacking, placing the same or making embankments, rough dressing etc. including all lifts, as directed by the Engineer-in-charge.	226.00	Cum	₹ 138.90	Rupees one hundred thirty eight and paise nine zero only	₹ 31,391.00
9	Extra rate in Sl. No. 8 above for each additional lead 500 metre or part there of beyond the initial lead of 500 metre. NB:- This item is applicable only where the track/ tractor are not accessible at site. 4 (four) Extra Lead	226.00	Cum	82.80	Rupees eighty two and paise eight zero only	₹ 18,713.00
10	Dumping in position earth filled poly bags inclusive of all leads and lifts. (admissible only when placed under flowing water)	940	Each	₹ 2.30	Rupees two and paise three zero only	₹ 2,152.00
Total Amount put to Tender in figure =						₹ 194,609.00
Total Amount put to Tender in word :						Rupees One lakh ninety four thousand six hundred and nine only

  
 Executive Engineer  
 West Midnapore Division  
 Irrigation & Waterways Dte.  
 Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

\_\_\_\_\_  
 (Signature of the Contractor)