

Schedule for the work: "M/R to Dy.No.7 of M.B.C.in between ch.0.00 and Ch.70.00 under Head Qtr. Section of K.C. Sub-Division No.IV, Sarenga under K.C. Divn. No.I, Amlagora, Paschim Medinipur, during the year 2017-18".

Sl. No.	Description of Item	Quantity	Unit	Rate (Rs.)	Unit	Amount (Rs.)
1	Cutting and removing ordinary thick or thorny jungles including clearing and depositing the same with all leads and lifts as per direction of the Engineer-in-Charge.	914.40	Sqm.	10.00	Sqm.	9144.00
2	Earthwork in excavation in the canals / drainage channels / borrowpits / River bed / slope of bank as noted below as per designed section & throwing the spoils in layer of 23 cm. for making banks as per profile or to deposit the same in any other place as wanted by the Engineer-in-Charge within an initial lead of 30 metre and initial lift of 2.00 metre including breaking clods, rough dressing etc. complete as per direction of the Engineer-in-Charge. (Including dewatering as necessary) a) Local soil / soil mixed with moorum or kankar / silt, dry or moist / slushy silt / sticky soil.	339.86	Cum.	77.00	Cum.	26169.00
3	Earthwork in filling in layers not exceeding 25cm including watering and ramming with all leads and lifts. b) Earth borrowed from outside.	218.08	Cum.	83.00	Cum.	18101.00
					Total	Rs.- 53414.00

(Rupees fifty three thousand four hundred and fourteen only)

Amlagora

Executive Engineer

Kangsabati Canals Division No. I

Amlagora, Paschim Medinipur

12.05.17

I/We do here by agree to execute the above work @..... % Above/Low/At per than the Schedule of Rates attached herewith .

Signature of the Contractor(s)