

Schedule for the work: "Removal of deposited earth from canal bed.in between ch.117.00 to Ch.139.50 of GBC under Adalia Section of K.C. Sub-Division No.II, under K.C. Divn. No.I, Amlagora,Block-Garbata II, Mouza- Balikahunia & Hatia, Dist Paschim Medinipur, during the year 2017-18."

Sl. No.	Description of Item	Quantity	Unit	Rate (Rs.)	Unit	Amount (Rs.)
1	Cutting and removing ordinary thick or thorny jungles including clearing and depositing the same with all leads and lifts as per direction of the Engineer-in-Charge.	2880.36	Sqm.	10.00	Sqm.	28804.00
2	Earthwork in excavation in the canals / drainage channels / borrowpits / River bed / slope of bank as noted below as per designed section & throwing the spoils in layer of 23 cm. for making banks as per profile or to deposit the same in any other place as wanted by the Engineer-in-Charge within an initial lead of 30 metre and initial lift of 2.00 metre including breaking clods, rough dressing etc. complete as per direction of the Engineer-in-Charge. (Including dewatering as necessary) a) Local soil / soil mixed with moorum or kankar / silt, dry or moist / slushy silt / sticky soil..	2631.41	Cum.	77.00	Cum.	202619.00
3	Extra rate over item No.1 for all kinds of soil for every additional lift of 2.00 metre or part thereof beyond the initial lift of 2.00 metre. i)for one extra lift	2631.41	Cum.	9.00	Cum.	23683.00
					Total	Rs.- 255106.00

(Rupees two lakh fifty five thousand one hundred and six only)

Amyankar
Executive Engineer

Kangsabati Canals Division No. I

Amlagora, Paschim Medinipur

12.05.17

I/We do here by agree to execute the above work @..... % Above/Low/At per than the Schedule of Rates attached herewith .

Signature of the Contractor(s)