

Page 1 of 2
Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur
email id- eewmid2012@gmail.com

NIT NO- WBIW/EE/WMD/NIT-08 of 2017-18

Sl. No. 01

Schedule of Quantity, Unit, Rate and Amount for the work FPM works in between Ch. 0.00 KM & 4.80 KM of TE1H1 embkkt. Right Bank of river Cossy under Khanamohan (I) Section of Lachmapur (I) Sub-Division under West Midnapore Division during the year 2017-18.

Amount put to Tender :

₹ 1,38,926.00

Earnest Money :

₹ 2,779.00

Time allowed for Completion :

150 days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Supplying, dressing and stacking at site bamboo pins (diameter to be measured at mid length) (a) Above 5 cm to 7.50 cm diameter.	1080.00	Mtr.	₹ 23.60	Rupees twenty three and paise six zero only	₹ 25,488.00
2	Driving bamboo pins of average 5 cm to 7.5 cm diameter (payment will be made for driven length only) (i) Where boats are not necessary a) Not less than 5 cm. Av. Diameter	540.00	Mtr.	₹ 6.30	Rupees six and paise three zero only	₹ 3,402.00
3	Supplying, fitting, fixing with iron nails, half split bamboo wailing pieces. (Diameter of bamboo not less than 5 cm, to be measured at mid length)	240.00	Mtr.	₹ 19.30	Rupees nineteen and paise three zero only	₹ 4,632.00
4	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg)	2300.00	Mtr.	₹ 5.00	Rupees five and paise zero only	₹ 11,500.00
5	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge. NB:- Volume of earth/ sand filled bags should not be less than 0.028 m ³ / bag.	2300.00	Mtr.	₹ 6.30	Rupees six and paise three zero only	₹ 14,490.00
6	Extra rate in item no. 5.00 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres. a) 3 (Three) extra lead	1035.00	Mtr.	₹ 6.90	Rupees six and paise nine zero only	₹ 7,142.00
	b) 4 (Four) extra lead	1035.00	Mtr.	₹ 9.20	Rupees nine and paise two zero only	₹ 9,522.00
7	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	2800.00	Sqm	₹ 7.70	Rupees seven and paise seven zero only	₹ 21,560.00
8	Mazdoor (Day work)	45	Nos	₹ 206.00	Rupees two hundred six and paise zero only	₹ 9,270.00
9	Mazdoor (Night work)	90	Nos	₹ 206.00	Rupees two hundred six and paise zero only	₹ 18,540.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
10	Supplying 500 C.P. incandescent lamp (i.e. petromax daylight, Hasag, etc.) on hire basis for 10 hours including supply of necessary fuel etc. complete.	45	Each	₹ 112.00	Rupees one hundred twelve and paise zero only	₹ 5,040.00
11	Supplying brush wood including tying them in bundles with 12 SWG galvanized wire filling in specified areas in bundles and providing ties with half split bamboos fitted, fixed including lead upto 2 km and all lifts, laying and placing complete as per direction of the Engineer- in - charge.(measurement to be made on volume of each bundle)	150	Cum	₹ 55.60	Rupees fifty five and paise six zero only	₹ 8,340.00
	Total Amount put to Tender in figure =					₹ 1,38,926.00
	Total Amount put to Tender in word :	Rupees one lakh thirty eight thousand nine hundred and twenty six only				


 Executive Engineer
 West Midnapore Division
 Irrigation & Waterways Dte.
 Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

 (Signature of the Contractor)

Page 1 of 2
Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur
email id- eewmid2012@gmail.com

NIT NO- WBIW/EE/WMD/NIT-08 of 2017-18

Sl. No. 02

Schedule of Quantity, Unit, Rate and Amount for the work FPM works in between Ch. 5.00 KM & 9.00 KM of TE1H1 embktt. Right Bank of river Cossy under Khanamohan (I) Section of Lachmapur (I) Sub Division under West Midnapore Division during the year 2017-18.

Amount put to Tender :

₹ 1,19,537.00

Earnest Money :

₹ 2,391.00

Time allowed for Completion :

150 days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Supplying, dressing and stacking at site bamboo pins (diametre to be measured at mid length (a) Above 5 cm to 7.50 cm diametre.	900.00	Mtr.	₹ 23.60	Rupees twenty three and paise six zero only	₹ 21,240.00
2	Driving bamboo pins of average 5 cm to 7.5 cm diametre (payment will be made for driven length only) (i) Where boats are not necessary a) Not less than 5 cm. Av. Diametre	450.00	Mtr.	₹ 6.30	Rupees six and paise three zero only	₹ 2,835.00
3	Supplying, fitting, fixing with iron nails, half split bamboo walling pieces. (Diametre of bamboo not less than 5 cm, to be measured at mid length)	200.00	Mtr.	₹ 19.30	Rupees nineteen and paise three zero only	₹ 3,860.00
4	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg)	2000.00	Mtr.	₹ 5.00	Rupees five and paise zero only	₹ 10,000.00
5	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge. NB:- Volume of earth/ sand filled bags should not be less than 0.028 m ³ / bag.	2000.00	Mtr.	₹ 6.30	Rupees six and paise three zero only	₹ 12,600.00
6	Extra rate in item no. 5.00 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres. a) 3 (Three) extra lead	900.00	Mtr.	₹ 6.90	Rupees six and paise nine zero only	₹ 6,210.00
	b) 4 (Four) extra lead	900.00	Mtr.	₹ 9.20	Rupees nine and paise two zero only	₹ 8,280.00
7	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	2800.00	Sqm	₹ 7.70	Rupees seven and paise seven zero only	₹ 21,560.00
8	Mazdoor (Day work)	36	Nos	₹ 206.00	Rupees two hundred six and paise zero only	₹ 7,416.00
9	Mazdoor (Night work)	72	Nos	₹ 206.00	Rupees two hundred six and paise zero only	₹ 14,832.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
10	Supplying 500 C.P. incandescent lamp (i.e. petromax daylight, Hasag, etc.) on hire basis for 10 hours including supply of necessary fuel etc. complete.	36	Each	₹ 112.00	Rupees one hundred twelve and paise zero only	₹ 4,032.00
11	Supplying brush wood including tying them in bundles with 12 SWG galvanized wire filling in specified areas in bundles and providing ties with half split bamboos fitted, fixed including lead upto 2 km and all lifts, laying and placing complete as per direction of the Engineer- in - charge.(measurement to be made on volume of each bundle)	120.00	Cum	₹ 55.60	Rupees fifty five and paise six zero only	₹ 6,672.00
	Total Amount put to Tender in figure =					₹ 1,19,537.00
	Total Amount put to Tender in word :			Rupees one lakh nineteen thousand five hundred and thirty seven only		


 Executive Engineer
 West Midnapore Division
 Irrigation & Waterways Dte.
 Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)

Page 1 of 2
Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur
email id- eewmid2012@gmail.com

NIT NO- WBIW/EE/WMD/NIT-08 of 2017-18

Sl. No. 03

Schedule of Quantity, Unit, Rate and Amount for the work FPM works in between Ch. 9.20 KM & 12.900 KM of TE1H1 embktt. Right bank of river Cossy under Khanamohan (I) Section of Lachmapur (I) Sub-Division under West Midnapore division during the year 2017-18.

Amount put to Tender :

₹ 1,13,505.00

Earnest Money :

₹ 2,270.00

Time allowed for Completion :

150 days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Supplying, dressing and stacking at site bamboo pins (diameter to be measured at mid length) (a) Above 5 cm to 7.50 cm diameter.	900.00	Mtr.	₹ 23.60	Rupees twenty three and paise six zero only	₹ 21,240.00
2	Driving bamboo pins of average 5 cm to 7.5 cm diameter (payment will be made for driven length only) (i) Where boats are not necessary a) Not less than 5 cm. Av. Diameter	450.00	Mtr.	₹ 6.30	Rupees six and paise three zero only	₹ 2,835.00
3	Supplying, fitting, fixing with iron nails, half split bamboo walling pieces. (Diameter of bamboo not less than 5 cm, to be measured at mid length)	200.00	Mtr.	₹ 19.30	Rupees nineteen and paise three zero only	₹ 3,860.00
4	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg)	2000.00	Mtr.	₹ 5.00	Rupees five and paise zero only	₹ 10,000.00
5	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge. NB:- Volume of earth/ sand filled bags should not be less than 0.028 m ³ / bag	2000.00	Mtr.	₹ 6.30	Rupees six and paise three zero only	₹ 12,600.00
6	Extra rate in item no. 5.00 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres.	900.00	Mtr.	₹ 6.90	Rupees six and paise nine zero only	₹ 6,210.00
	a) 3 (Three) extra lead b) 4 (Four) extra lead	900.00	Mtr.	₹ 9.20	Rupees nine and paise two zero only	₹ 8,280.00
7	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	1800.00	Sqm	₹ 7.70	Rupees seven and paise seven zero only	₹ 13,860.00
8	Mazdoor (Day work)	36	Nos	₹ 206.00	Rupees two hundred six and paise zero only	₹ 7,416.00
9	Mazdoor (Night work)	72	Nos	₹ 206.00	Rupees two hundred six and paise zero only	₹ 14,832.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
10	Supplying 500 C.P. Incandescent lamp (i.e. petromax daylight, Hasag, etc.) on hire basis for 10 hours including supply of necessary fuel etc. complete.	36	Each	₹ 112.00	Rupees one hundred twelve and paise zero only	₹ 4,032.00
11	Supplying brush wood including tying them in bundles with 12 SWG galvanized wire filling in specified areas in bundles and providing ties with half split bamboos fitted, fixed including lead upto 2 km and all lifts, laying and placing complete as per direction of the Engineer-in-charge.(measurement to be made on volume of each bundle)	150.00	Cum	₹ 55.60	Rupees fifty five and paise six zero only	₹ 8,340.00
	Total Amount put to Tender in figure =					₹ 1,13,505.00
	Total Amount put to Tender in word :				Rupees one lakh thirteen thousand five hundred five only	


 Executive Engineer
 West Midnapore Division
 Irrigation & Waterways Dte.
 Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)

Page 1 of 2
Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur
email id- eewmid2012@gmail.com

NIT NO- WBIW/EE/WMD/NIT-08 of 2017-18

Sl. No. 04

Schedule of Quantity, Unit, Rate and Amount for the work FPM works in between Ch. 13.00 KM & 17.00 KM of TE1H1 embkkt. Right bank of river Cossy under Khanamohan (I) Section of Lachmapur (I) Sub-Division under West Midnapore division during the year 2017-18.

Amount put to Tender :

₹ 1,17,741.00

Earnest Money :

₹ 2,355.00

Time allowed for Completion :

150 days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Supplying, dressing and stacking at site bamboo pins (diameter to be measured at mid length (a) Above 5 cm to 7.50 cm diameter.	900.00	Mtr.	₹ 23.60	Rupees twenty three and paise six zero only	₹ 21,240.00
2	Driving bamboo pins of average 5 cm to 7.5 cm diameter (payment will be made for driven length only) (i) Where boats are not necessary a) Not less than 5 cm. Av. Diameter	450.00	Mtr.	₹ 6.30	Rupees six and paise three zero only	₹ 2,835.00
3	Supplying, fitting, fixing with iron nails, half split bamboo walling pieces. (Diameter of bamboo not less than 5 cm, to be measured at mid length)	200.00	Mtr.	₹ 19.30	Rupees nineteen and paise three zero only	₹ 3,860.00
4	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg)	2000.00	Mtr.	₹ 5.00	Rupees five and paise zero only	₹ 10,000.00
5	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge. NB:- Volume of earth/ sand filled bags should not be less than 0.028 m ³ / bag.	2000.00	Mtr.	₹ 6.30	Rupees six and paise three zero only	₹ 12,600.00
6	Extra rate in item no. 5.00 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres. a) 3 (Three) extra lead	900.00	Mtr.	₹ 6.90	Rupees six and paise nine zero only	₹ 6,210.00
	b) 4 (Four) extra lead	900.00	Mtr.	₹ 9.20	Rupees nine and paise two zero only	₹ 8,280.00
7	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	3000.00	Sqm	₹ 7.70	Rupees seven and paise seven zero only	₹ 23,100.00
8	Mazdoor (Day work)	36	Nos	₹ 206.00	Rupees two hundred six and paise zero only	₹ 7,416.00
9	Mazdoor (Night work)	72	Nos	₹ 206.00	Rupees two hundred six and paise zero only	₹ 14,832.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
10	Supplying 500 C.P. incandescent lamp (i.e. petromax daylight, Hasag, etc.) on hire basis for 10 hours including supply of necessary fuel etc. complete.	36	Each	₹ 112.00	Rupees one hundred twelve and paise zero only	₹ 4,032.00
11	Supplying brush wood including tying them in bundles with 12 SWG galvanized wire filling in specified areas in bundles and providing ties with half split bamboos fitted, fixed including lead upto 2 km and all lifts, laying and placing complete as per direction of the Engineer- in - charge.(measurement to be made on volume of each bundle)	60.00	Cum	₹ 55.60	Rupees fifty five and paise six zero only	₹ 3,336.00
Total Amount put to Tender in figure =						₹ 1,17,741.00
Total Amount put to Tender in word :						Rupees one lakh seventeen thousand seven hundred forty one only


 Executive Engineer
 West Midnapore Division
 Irrigation & Waterways Dte.
 Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

 (Signature of the Contractor)

Page 1 of 2
Govt. of West Bengal
Irrigation & Waterways Dtc.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur
email id- eewmid2012@gmail.com

NIT NO- WBIW/EE/WMD/NIT-08 of 2017-18

Sl. No. 05

Schedule of Quantity, Unit, Rate and Amount for the work FPM works in between Ch. 17.20 KM & 21.80 KM of TE1H1 embkkt. Right Bank of river Cossy under Khanamohan (I) Section of Lachmapur (I) Sub-Division under West Midnapore Division during the year 2017-18.

Amount put to Tender :

₹ 1,34,906.00

Earnest Money :

₹ 2,698.00

Time allowed for Completion :

150 days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Supplying, dressing and stacking at site bamboo pins (diameter to be measured at mid length) (a) Above 5 cm to 7.50 cm diameter.	1080.00	Mtr.	₹ 23.60	Rupees twenty three and paise six zero only	₹ 25,488.00
2	Driving bamboo pins of average 5 cm to 7.5 cm diameter (payment will be made for driven length only) (I) Where boats are not necessary a) Not less than 5 cm. Av. Diameter	540.00	Mtr.	₹ 6.30	Rupees six and paise three zero only	₹ 3,402.00
3	Supplying, fitting, fixing with iron nails, half split bamboo wailing pieces. (Diameter of bamboo not less than 5 cm, to be measured at mid length)	240.00	Mtr.	₹ 19.30	Rupees nineteen and paise three zero only	₹ 4,632.00
4	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg)	2300.00	Mtr.	₹ 5.00	Rupees five and paise zero only	₹ 11,500.00
5	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge. NB:- Volume of earth/ sand filled bags should not be less than 0.028 m ³ / bag.	2300.00	Mtr.	₹ 6.30	Rupees six and paise three zero only	₹ 14,490.00
6	Extra rate in item no. 5.00 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres. a) 3 (Three) extra lead	1035.00	Mtr.	₹ 6.90	Rupees six and paise nine zero only	₹ 7,142.00
	b) 4 (Four) extra lead	1035.00	Mtr.	₹ 9.20	Rupees nine and paise two zero only	₹ 9,522.00
7	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	3000.00	Sqm	₹ 7.70	Rupees seven and paise seven zero only	₹ 23,100.00
8	Mazdoor (Day work)	45	Nos	₹ 206.00	Rupees two hundred six and paise zero only	₹ 9,270.00
9	Mazdoor (Night work)	90	Nos	₹ 206.00	Rupees two hundred six and paise zero only	₹ 18,540.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
10	Supplying 500 C.P. incandescent lamp (i.e. petromax daylight, Hasag, etc.) on hire basis for 10 hours including supply of necessary fuel etc. complete.	45	Each	₹ 112.00	Rupees one hundred twelve and paise zero only	₹ 5,040.00
11	Supplying brush wood including tying them in bundles with 12 SWG galvanized wire filling in specified areas in bundles and providing ties with half split bamboos fitted, fixed including lead upto 2 km and all lifts, laying and placing complete as per direction of the Engineer- in - charge.(measurement to be made on volume of each bundle)	50.00	Cum	₹ 55.60	Rupees fifty five and paise six zero only	₹ 2,780.00
Total Amount put to Tender in figure =						₹ 1,34,906.00
Total Amount put to Tender in word :		Rupees one lakh thirty four thousand nine hundred and six only				


 Executive Engineer
 West Midnapore Division
 Irrigation & Waterways Dte.
 Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)

Page 1 of 2
Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur
email id- eewmid2012@gmail.com

NIT NO- WBIW/EE/WMD/NIT-08 of 2017-18

Sl. No. 06

Schedule of Quantity, Unit, Rate and Amount for the work FPM works in between Ch. 22.00 KM & 25.90 KM of TE1H1 embktt. Right Bank of river Cossy under Khanamohan (I) Section of Lachmapur (I) Sub Division under West Midnapore division during the year 2017-18.*

Amount put to Tender :

₹ 1,15,373.00

Earnest Money :

₹ 2,307.00

Time allowed for Completion :

150 days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Supplying, dressing and stacking at site bamboo pins (diameter to be measured at mid length (a) Above 5 cm to 7.50 cm diameter.	900.00	Mtr.	₹ 23.60	Rupees twenty three and paise six zero only	₹ 21,240.00
2	Driving bamboo pins of average 5 cm to 7.5 cm diameter (payment will be made for driven length only) (i) Where boats are not necessary a) Not less than 5 cm. Av. Diameter	450.00	Mtr.	₹ 6.30	Rupees six and paise three zero only	₹ 2,835.00
3	Supplying, fitting, fixing with iron nails, half split bamboo walling pieces. (Diameter of bamboo not less than 5 cm, to be measured at mid length)	200.00	Mtr.	₹ 19.30	Rupees nineteen and paise three zero only	₹ 3,860.00
4	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg)	1900.00	Mtr.	₹ 5.00	Rupees five and paise zero only	₹ 9,500.00
5	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge. NB:- Volume of earth/ sand filled bags should not be less than 0.028 m ³ / bag	1900.00	Mtr.	₹ 6.30	Rupees six and paise three zero only	₹ 11,970.00
6	Extra rate in item no. 5.00 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres. a) 3 (Three) extra lead	855.00	Mtr.	₹ 6.90	Rupees six and paise nine zero only	₹ 5,900.00
	b) 4 (Four) extra lead	855.00	Mtr.	₹ 9.20	Rupees nine and paise two zero only	₹ 7,866.00
7	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	2500.00	Sqm	₹ 7.70	Rupees seven and paise seven zero only	₹ 19,250.00
8	Mazdoor (Day work)	36	Nos	₹ 206.00	Rupees two hundred six and paise zero only	₹ 7,416.00
9	Mazdoor (Night work)	72	Nos	₹ 206.00	Rupees two hundred six and paise zero only	₹ 14,832.00

No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
10	Supplying 500 C.P. incandescent lamp (i.e. petromax daylight, Hasag, etc.) on hire basis for 10 hours including supply of necessary fuel etc. complete.	36	Each	₹ 112.00	Rupees one hundred twelve and paise zero only	₹ 4,032.00
11	Supplying brush wood including tying them in bundles with 12 SWG galvanized wire filling in specified areas in bundles and providing ties with half split bamboos fitted, fixed including lead upto 2 km and all lifts, laying and placing complete as per direction of the Engineer-in-charge.(measurement to be made on volume of each bundle)	120.00	Cum	₹ 55.60	Rupees fifty five and paise six zero only	₹ 6,672.00
	Total Amount put to Tender in figure =					₹ 1,15,373.00
	Total Amount put to Tender in word :			Rupees one lakh fifteen thousand three hundred and seventy three only		


 Executive Engineer
 West Midnapore Division
 Irrigation & Waterways Dte.
 Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)

Page 1 of 2
Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur
email id- eewmid2012@gmail.com

NIT NO- WBIW/EE/WMD/NIT-08 of 2017-18

Sl. No. 07

Schedule of Quantity, Unit, Rate and Amount for the work FPM works in between Ch. 26.00 KM & 28.00 KM of TE1H1 embkkt. Right bank of river New Cossy under Khanamohan (I) Section of Lachmapur (I) Sub- Division under West Midnapore division during the year 2017-18".

Amount put to Tender :

₹ 1,30,463.00

Earnest Money :

₹ 2,609.00

Time allowed for Completion :

150 days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Supplying, dressing and stacking at site bamboo pins (diameter to be measured at mid length (a) Above 5 cm to 7.50 cm diameter.	450.00	Mtr.	₹ 23.60	Rupees twenty three and paise six zero only	₹ 10,620.00
2	Driving bamboo pins of average 5 cm to 7.5 cm diameter (payment will be made for driven length only) (I) Where boats are not necessary a) Not less than 5 cm. Av. Diameter	225.00	Mtr.	₹ 6.30	Rupees six and paise three zero only	₹ 1,418.00
3	Supplying, fitting, fixing with iron nails, half split bamboo wailing pieces. (Diameter of bamboo not less than 5 cm, to be measured at mid length)	100.00	Mtr.	₹ 19.30	Rupees nineteen and paise three zero only	₹ 1,930.00
4	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg)	1000.00	Mtr.	₹ 5.00	Rupees five and paise zero only	₹ 5,000.00
5	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge. NB:- Volume of earth/ sand filled bags should not be less than 0.028 m ³ / bag.	1000.00	Mtr.	₹ 6.30	Rupees six and paise three zero only	₹ 6,300.00
6	Extra rate in item no. 5.00 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres. a) 3 (Three) extra lead	450.00	Mtr.	₹ 9.20	Rupees nine and paise two zero only	₹ 4,140.00
	b) 4 (Four) extra lead	450.00	Mtr.	₹ 11.50	Rupees eleven and paise five zero only	₹ 5,175.00
7	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	1000.00	Sqm	₹ 7.70	Rupees seven and paise seven zero only	₹ 7,700.00
8	Mazdoor (Day work)	166	Nos	₹ 206.00	Rupees two hundred six and paise zero only	₹ 34,196.00
9	Mazdoor (Night work)	202	Nos	₹ 206.00	Rupees two hundred six and paise zero only	₹ 41,612.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
10	Supplying 500 C.P. incandescent lamp (i.e. petromax daylight, Hasag, etc.) on hire basis for 10 hours including supply of necessary fuel etc. complete.	36	Each	₹ 112.00	Rupees one hundred twelve and paise zero only	₹ 4,032.00
11	Supplying brush wood including tying them in bundles with 12 SWG galvanized wire filling in specified areas in bundles and providing ties with half split bamboos fitted, fixed including lead upto 2 km and all lifts, laying and placing complete as per direction of the Engineer-in-charge.(measurement to be made on volume of each bundle)	150.00	Cum	₹ 55.60	Rupees fifty five and paise six zero only	₹ 8,340.00
	Total Amount put to Tender in figure =					₹ 1,30,463.00
	Total Amount put to Tender in word :	Rupees one lakh thirty thousand four hundred and sixty three only				


 Executive Engineer
 West Midnapore Division
 Irrigation & Waterways Dte.
 Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

 (Signature of the Contractor)

Page 1 of 2
Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur
email id- eewmid2012@gmail.com

NIT NO- WBIW/EE/WMD/NIT-08 of 2017-18

Sl. No. 08

Schedule of Quantity, Unit, Rate and Amount for the work FPM works in between Ch.28.00 KM & 29.90 KM of TE1H1 embkkt. Right bank of river New Cossy under Khanamohan (I) Section of Lachmapur (I) Sub- Division under West Midnapore Division during the year 2017-18.

Amount put to Tender :

₹ 1,03,565.00

Earnest Money :

₹ 2,071.00

Time allowed for Completion :

150 days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Supplying, dressing and stacking at site bamboo pins (diameter to be measured at mid length) (a) Above 5 cm to 7.50 cm diameter.	900.00	Mtr.	₹ 23.60	Rupees twenty three and paise six zero only	₹ 21,240.00
2	Driving bamboo pins of average 5 cm to 7.5 cm diameter (payment will be made for driven length only) (i) Where boats are not necessary a) Not less than 5 cm. Av. Diameter	450.00	Mtr.	₹ 6.30	Rupees six and paise three zero only	₹ 2,835.00
3	Supplying, fitting, fixing with iron nails, half split bamboo wailing pieces. (Diameter of bamboo not less than 5 cm, to be measured at mid length)	200.00	Mtr.	₹ 19.30	Rupees nineteen and paise three zero only	₹ 3,860.00
4	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg)	2000.00	Mtr.	₹ 5.00	Rupees five and paise zero only	₹ 10,000.00
5	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge. NB:- Volume of earth/ sand filled bags should not be less than 0.028 m ³ / bag.	2000.00	Mtr.	₹ 6.30	Rupees six and paise three zero only	₹ 12,600.00
6	Extra rate in item no. 5.00 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres.	900.00	Mtr.	₹ 9.20	Rupees nine and paise two zero only	₹ 8,280.00
	a) 3 (Three) extra lead b) 4 (Four) extra lead	900.00	Mtr.	₹ 11.50	Rupees eleven and paise five zero only	₹ 10,350.00
7	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	2400.00	Sqm	₹ 7.70	Rupees seven and paise seven zero only	₹ 18,480.00
8	Mazdoor (Day work)	18	Nos	₹ 206.00	Rupees two hundred six and paise zero only	₹ 3,708.00
9	Mazdoor (Night work)	36	Nos	₹ 206.00	Rupees two hundred six and paise zero only	₹ 7,416.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
10	Supplying 500 C.P. incandescent lamp (i.e. petromax daylight, Hasag, etc.) on hire basis for 10 hours including supply of necessary fuel etc. complete.	18	Each	₹ 112.00	Rupees one hundred twelve and paise zero only	₹ 2,016.00
11	Supplying brush wood including tying them in bundles with 12 SWG galvanized wire filling in specified areas in bundles and providing ties with half split bamboos fitted, fixed including lead upto 2 km and all lifts, laying and placing complete as per direction of the Engineer- in - charge.(measurement to be made on volume of each bundle)	50.00	Cum	₹ 55.60	Rupees fifty five and paise six zero only	₹ 2,780.00
	Total Amount put to Tender in figure =					₹ 1,03,565.00
	Total Amount put to Tender in word :			Rupees one lakh three thousand five hundred and sixty five only		


 Executive Engineer
 West Midnapore Division
 Irrigation & Waterways Dte.
 Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

[Signature of the Contractor]

Govt. of West Bengal

Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur
email id- eewmid2012@gmail.com

NIT NO- WBIW/EE/WMD/NIT-08 of 2017-18

Sl. No. 09

Schedule of Quantity, Unit, Rate and Amount for the work FPM works in between Ch. 30.10 KM & 35.90 KM of TE1H1 embkkt. Right bank of river New Cossy under Khanamohan (I) Section of Lachmapur (I) Sub- Division under West Midnapore division during the year 2017-18.

Amount put to Tender :

₹ 1,49,218.00

Earnest Money :


₹ 2,984.00

Time allowed for Completion :

150 days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Supplying, dressing and stacking at site bamboo pins (diameter to be measured at mid length (a) Above 5 cm to 7.50 cm diameter.	1080.00	Mtr.	₹ 23.60	Rupees twenty three and paise six zero only	₹ 25,488.00
2	Driving bamboo pins of average 5 cm to 7.5 cm diameter (payment will be made for driven length only) (i) Where boats are not necessary a) Not less than 5 cm. Av. Diameter	540.00	Mtr.	₹ 6.30	Rupees six and paise three zero only	₹ 3,402.00
3	Supplying, fitting, fixing with iron nails, half split bamboo wailing pieces. (Diameter of bamboo not less than 5 cm, to be measured at mid length)	240.00	Mtr.	₹ 19.30	Rupees nineteen and paise three zero only	₹ 4,632.00
4	Supplying to site 2nd hand cement poly bags in good condition delivered and stacked (capacity 50 kg)	2300.00	Mtr.	₹ 5.00	Rupees five and paise zero only	₹ 11,500.00
5	Labour charge for filling poly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge. NB:- Volume of earth/ sand filled bags should not be less than 0.028 m ³ / bag.	2300.00	Mtr.	₹ 6.30	Rupees six and paise three zero only	₹ 14,490.00
6	Extra rate in item no. 5.00 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres.	1035.00	Mtr.	₹ 6.90	Rupees six and paise nine zero only	₹ 7,142.00
	a) 3 (Three) extra lead b) 4 (Four) extra lead	1035.00	Mtr.	₹ 9.20	Rupees nine and paise two zero only	₹ 9,522.00
7	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	3500.00	Sqm	₹ 7.70	Rupees seven and paise seven zero only	₹ 26,950.00
8	Mazdoor (Day work)	54	Nos	₹ 206.00	Rupees two hundred six and paise zero only	₹ 11,124.00
9	Mazdoor (Night work)	108	Nos	₹ 206.00	Rupees two hundred six and paise zero only	₹ 22,248.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
10	Supplying 500 C.P. incandescent lamp (i.e. petromax daylight, Hasag, etc.) on hire basis for 10 hours including supply of necessary fuel etc. complete.	54	Each	₹ 112.00	Rupees one hundred twelve and paise zero only	₹ 6,048.00
11	Supplying brush wood including tying them in bundles with 12 SWG galvanized wire filling in specified areas in bundles and providing ties with half split bamboos fitted, fixed including lead upto 2 km and all lifts, laying and placing complete as per direction of the Engineer- in - charge.(measurement to be made on volume of each bundle)	120.00	Cum	₹ 55.60	Rupees fifty five and paise six zero only	₹ 6,672.00
Total Amount put to Tender in figure =						₹ 1,49,218.00
Total Amount put to Tender in word :		Rupees one lakh forty nine thousand two hundred and eighteen only				


 Executive Engineer
 West Midnapore Division
 Irrigation & Waterways Dte.
 Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)

Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur
email id- eewmid2012@gmail.com

NIT NO- WBIW/EE/WMD/NIT-08 of 2017-18

Sl. No. 10

Schedule of Quantity, Unit, Rate and Amount for the work FPM works in between Ch. 36.00 KM & 41.50 KM of TE1H1 embkkt. Right bank of river New Cossy under Khanamohan (I) Section of Lachmapur (I) Sub- Division under West Midnapore division during the year 2017-18.

Amount put to Tender : ₹ 1,55,975.00
Earnest Money : ₹ 3,120.00
Time allowed for Completion : 150 days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Supplying, dressing and stacking at site bamboo pins (diameter to be measured at mid length (a) Above 5 cm to 7.50 cm diameter.	1080.00	Mtr.	₹ 23.60	Rupees twenty three and paise six zero only	₹ 25,488.00
2	Driving bamboo pins of average 5 cm to 7.5 cm diameter (payment will be made for driven length only) (i) Where boats are not necessary a) Not less than 5 cm. Av. Diameter	540.00	Mtr.	₹ 6.30	Rupees six and paise three zero only	₹ 3,402.00
3	Supplying, fitting, fixing with iron nails, half split bamboo wailing pieces. (Diameter of bamboo not less than 5 cm, to be measured at mid length)	240.00	Mtr.	₹ 19.30	Rupees nineteen and paise three zero only	₹ 4,632.00
4	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg)	2300.00	Mtr.	₹ 5.00	Rupees five and paise zero only	₹ 11,500.00
5	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge. NB:- Volume of earth/ sand filled bags should not be less than 0.028 m ³ / bag.	2300.00	Mtr.	₹ 6.30	Rupees six and paise three zero only	₹ 14,490.00
6	Extra rate in item no. 5.00 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres.	1035.00	Mtr.	₹ 9.20	Rupees nine and paise two zero only	₹ 9,522.00
	a) 3 (Three) extra lead b) 4 (Four) extra lead	1035.00	Mtr.	₹ 11.50	Rupees eleven and paise five zero only	₹ 11,903.00
7	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	4000.00	Sqm	₹ 7.70	Rupees seven and paise seven zero only	₹ 30,800.00
8	Mazdoor (Day work)	54	Nos	₹ 206.00	Rupees two hundred six and paise zero only	₹ 11,124.00
9	Mazdoor (Night work)	99	Nos	₹ 206.00	Rupees two hundred six and paise zero only	₹ 20,394.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
10	Supplying 500 C.P. incandescent lamp (i.e. petromax daylight, Hasag, etc.) on hire basis for 10 hours including supply of necessary fuel etc. complete.	54	Each	₹ 112.00	Rupees one hundred twelve and paise zero only	₹ 6,048.00
11	Supplying brush wood including tying them in bundles with 12 SWG galvanized wire filling in specified areas in bundles and providing ties with half split bamboos fitted, fixed including lead upto 2 km and all lifts, laying and placing complete as per direction of the Engineer- in - charge.(measurement to be made on volume of each bundle)	120.00	Cum	₹ 55.60	Rupees fifty five and paise six zero only	₹ 6,672.00
	Total Amount put to Tender in figure =					₹ 1,55,975.00
	Total Amount put to Tender in word :			Rupees one lakh fifty five thousand nine hundred and seventy five only		


 Executive Engineer
 West Midnapore Division
 Irrigation & Waterways Dte.
 Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

 (Signature of the Contractor)