

Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur
email id- eewmid2012@gmail.com

NIT NO- WBIW/EE/WMD/NIT-08 of 2017-18

Sl. No. 11

Schedule of Quantity, Unit, Rate and Amount for the work FPM works in between Ch.0.00 KM & 3.00 KM of TE2H2 embktt. Right bank of river Old Cossy under Khanamohan (I) Section of Lachmapur (I) Sub- Division under West Midnapore Division during the year 2017-18.

Amount put to Tender : ₹ 1,20,133.00

Earnest Money : ₹ 2,403.00

Time allowed for Completion : 150 days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Supplying, dressing and stacking at site bamboo pins (diameter to be measured at mid length (a) Above 5 cm to 7.50 cm diameter.	1080.00	Mtr.	₹ 23.60	Rupees twenty three and paise six zero only	₹ 25,488.00
2	Driving bamboo pins of average 5 cm to 7.5 cm diameter (payment will be made for driven length only) (i) Where boats are not necessary a) Not less than 5 cm. Av. Diameter	540.00	Mtr.	₹ 6.30	Rupees six and paise three zero only	₹ 3,402.00
3	Supplying, fitting, fixing with iron nails, half split bamboo walling pieces. (Diameter of bamboo not less than 5 cm, to be measured at mid length)	240.00	Mtr.	₹ 19.30	Rupees nineteen and paise three zero only	₹ 4,632.00
4	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg)	2300.00	Mtr.	₹ 5.00	Rupees five and paise zero only	₹ 11,500.00
5	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge. NB:- Volume of earth/ sand filled bags should not be less than 0.028 m ³ / bag	2300.00	Mtr.	₹ 6.30	Rupees six and paise three zero only	₹ 14,490.00
6	Extra rate in item no. 5.00 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres. a) 3 (Three) extra lead	1035.00	Mtr.	₹ 9.20	Rupees nine and paise two zero only	₹ 9,522.00
	b) 4 (Four) extra lead	1035.00	Mtr.	₹ 11.50	Rupees eleven and paise five zero only	₹ 11,903.00
7	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	2400.00	Sqm	₹ 7.70	Rupees seven and paise seven zero only	₹ 18,480.00
8	Mazdoor (Day work)	36	Nos	₹ 206.00	Rupees two hundred six and paise zero only	₹ 7,416.00
9	Mazdoor (Night work)	18	Nos	₹ 206.00	Rupees two hundred six and paise zero only	₹ 3,708.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
10	Supplying 500 C.P. incandescent lamp (i.e. petromax daylight, Hasag, etc.) on hire basis for 10 hours including supply of necessary fuel etc. complete.	36	Each	₹ 112.00	Rupees one hundred twelve and paise zero only	₹ 4,032.00
11	Supplying brush wood including tying them in bundles with 12 SWG galvanized wire filling in specified areas in bundles and providing ties with half split bamboos fitted, fixed including lead upto 2 km and all lifts, laying and placing complete as per direction of the Engineer- in - charge.(measurement to be made on volume of each bundle)	100.00	Cum	₹ 55.60	Rupees fifty five and paise six zero only	₹ 5,560.00
Total Amount put to Tender in figure =						₹ 1,20,133.00
Total Amount put to Tender in word :						Rupees one lakh twenty thousand one hundred and thirty three only


 Executive Engineer
 West Midnapore Division
 Irrigation & Waterways Dte.
 Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

 [Signature of the Contractor]

Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur
email id- eewmid2012@gmail.com

NIT NO- WBIW/EE/WMD/NIT-08 of 2017-18

Sl. No. 12

Schedule of Quantity, Unit, Rate and Amount for the work FPM works in between Ch.14.00 KM & 16.00 KM of TE3H2 embkkt. Left bank of river New Cossy under Khanamohan (I) Section of Lachmapur (I) Sub- Division under West Midnapore Division during the year 2017-18.

Amount put to Tender :

₹ 1,00,010.00

Earnest Money :

₹ 2,000.00

Time allowed for Completion :

150 days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Supplying, dressing and stacking at site bamboo pins (diametre to be measured at mid length (a) Above 5 cm to 7.50 cm diametre.	900.00	Mtr.	₹ 23.60	Rupees twenty three and paise six zero only	₹ 21,240.00
2	Driving bamboo pins of average 5 cm to 7.5 cm diametre (payment will be made for driven length only) (i) Where boats are not necessary a) Not less than 5 cm. Av. Diametre	450.00	Mtr.	₹ 6.30	Rupees six and paise three zero only	₹ 2,835.00
3	Supplying, fitting, fixing with iron nails, half split bamboo walling pieces. (Diametre of bamboo not less than 5 cm, to be measured at mid length)	200.00	Mtr.	₹ 19.30	Rupees nineteen and paise three zero only	₹ 3,860.00
4	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg)	1950.00	Mtr.	₹ 5.00	Rupees five and paise zero only	₹ 9,750.00
5	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge. NB:- Volume of earth/ sand filled bags should not be less than 0.028 m ³ / bag	1950.00	Mtr.	₹ 6.30	Rupees six and paise three zero only	₹ 12,285.00
6	Extra rate in item no. 5.00 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres.	877.50	Mtr.	₹ 9.20	Rupees nine and paise two zero only	₹ 8,073.00
	a) 3 (Three) extra lead b) 4 (Four) extra lead	877.50	Mtr.	₹ 11.50	Rupees eleven and paise five zero only	₹ 10,091.00
7	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	2000.00	Sqm	₹ 7.70	Rupees seven and paise seven zero only	₹ 15,400.00
8	Mazdoor (Day work)	18	Nos	₹ 206.00	Rupees two hundred six and paise zero only	₹ 3,708.00
9	Mazdoor (Night work)	36	Nos	₹ 205.00	Rupees two hundred six and paise zero only	₹ 7,416.00

No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
10	Supplying 500 C.P. incandescent lamp (i.e. petromax daylight, Hasag, etc.) on hire basis for 10 hours including supply of necessary fuel etc. complete.	18	Each	₹ 112.00	Rupees one hundred twelve and paise zero only	₹ 2,016.00
11	Supplying brush wood including tying them in bundles with 12 SWG galvanized wire filling in specified areas in bundles and providing ties with half split bamboos fitted, fixed including lead upto 2 km and all lifts, laying and placing complete as per direction of the Engineer- in - charge.(measurement to be made on volume of each bundle)	60.00	Cum	₹ 55.60	Rupees fifty five and paise six zero only	₹ 3,336.00
Total Amount put to Tender in figure =						₹ 1,00,010.00
Total Amount put to Tender in word :						Rupees one lakh and ten only


 Executive Engineer
 West Midnapore Division
 Irrigation & Waterways Dte.
 Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

 (Signature of the Contractor)

Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur
email id- eewmid2012@gmail.com

NIT NO- WBIW/EE/WMD/NIT-08 of 2017-18

Sl. No. 13

Schedule of Quantity, Unit, Rate and Amount for the work FPM works in between Ch.16.10 KM & 19.80 KM of TE3H2 embktt. Left bank of river New Cossy under Khanamohan (I) Section of Lachmapur (I) Sub- Division under West Midnapore Division during the year 2017-18.

Amount put to Tender :

₹ 2,00,853.00

Earnest Money :

₹ 4,017.00

Time allowed for Completion :

150 days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Supplying, dressing and stacking at site bamboo pins (diameter to be measured at mid length) (a) Above 5 cm to 7.50 cm diameter.	1350.00	Mtr.	₹ 23.60	Rupees twenty three and paise six zero only	₹ 31,860.00
2	Driving bamboo pins of average 5 cm to 7.5 cm diameter (payment will be made for driven length only) (I) Where boats are not necessary a) Not less than 5 cm. Av. Diameter	675.00	Mtr.	₹ 6.30	Rupees six and paise three zero only	₹ 4,253.00
3	Supplying, fitting, fixing with iron nails, half split bamboo wailing pieces. (Diameter of bamboo not less than 5 cm, to be measured at mid length)	300.00	Mtr.	₹ 19.30	Rupees nineteen and paise three zero only	₹ 5,790.00
4	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg)	4400.00	Mtr.	₹ 5.00	Rupees five and paise zero only	₹ 22,000.00
5	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge. NB:- Volume of earth/ sand filled bags should not be less than 0.028 m ³ / bag.	4400.00	Mtr.	₹ 6.30	Rupees six and paise three zero only	₹ 27,720.00
6	Extra rate in item no. 5.00 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres.	1980.00	Mtr.	₹ 9.20	Rupees nine and paise two zero only	₹ 18,216.00
	a) 3 (Three) extra lead b) 4 (Four) extra lead	1980.00	Mtr.	₹ 11.50	Rupees eleven and paise five zero only	₹ 22,770.00
7	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	4800.00	Sqm	₹ 7.70	Rupees seven and paise seven zero only	₹ 36,960.00
8	Mazdoor (Day work)	36.00	Nos	₹ 206.00	Rupees two hundred six and paise zero only	₹ 7,416.00
9	Mazdoor (Night work)	72.00	Nos	₹ 206.00	Rupees two hundred six and paise zero only	₹ 14,832.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
10	Supplying 500 C.P. incandescent lamp (i.e. petromax daylight, Hasag, etc.) on hire basis for 10 hours including supply of necessary fuel etc. complete.	36.00	Each	₹ 112.00	Rupees one hundred twelve and paise zero only	₹ 4,032.00
11	Supplying brush wood including tying them in bundles with 12 SWG galvanized wire filling in specified areas in bundles and providing ties with half split bamboos fitted, fixed including lead upto 2 km and all lifts, laying and placing complete as per direction of the Engineer- in - charge.(measurement to be made on volume of each bundle)	90.00	Cum	₹ 55.60	Rupees fifty five and paise six zero only	₹ 5,004.00
	Total Amount put to Tender in figure =					₹ 2,00,853.00
	Total Amount put to Tender in word :			Rupees two lakh eight hundred and fifty three only		


 Executive Engineer
 West Midnapore Division
 Irrigation & Waterways Dte.
 Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)

Page 1 of 2
Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur
email id- eewmid2012@gmail.com

NIT NO- WBIW/EE/WMD/NIT-08 of 2017-18

Sl. No. 14

Schedule of Quantity, Unit, Rate and Amount for the work FPM works in between Ch.20.00 KM & 23.00 KM of TE3H2 embkkt. Left bank of river New Cossy under Khanamohan (I) Section of Lachmapur (I) Sub- Division under West Midnapore division during the year 2017-18.

Amount put to Tender :

₹ 1,18,827.00

Earnest Money :

₹ 2,377.00

Time allowed for Completion :

150 days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Supplying, dressing and stacking at site bamboo pins (diameter to be measured at mid length (a) Above 5 cm to 7.50 cm diameter.	1080.00	Mtr.	₹ 23.60	Rupees twenty three and paise six zero only	₹ 25,488.00
2	Driving bamboo pins of average 5 cm to 7.5 cm diameter (payment will be made for driven length only) (i) Where boats are not necessary a) Not less than 5 cm. Av. Diameter	540.00	Mtr.	₹ 6.30	Rupees six and paise three zero only	₹ 3,402.00
3	Supplying, fitting, fixing with iron nails, half split bamboo walling pieces. (Diameter of bamboo not less than 5 cm, to be measured at mid length)	240.00	Mtr.	₹ 19.30	Rupees nineteen and paise three zero only	₹ 4,632.00
4	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg)	2300.00	Mtr.	₹ 5.00	Rupees five and paise zero only	₹ 11,500.00
5	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge. NB:- Volume of earth/ sand filled bags should not be less than 0.028 m ³ / bag.	2300.00	Mtr.	₹ 6.30	Rupees six and paise three zero only	₹ 14,490.00
6	Extra rate in item no. 5.00 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres.	1035.00	Mtr.	₹ 9.20	Rupees nine and paise two zero only	₹ 9,522.00
	a) 3 (Three) extra lead b) 4 (Four) extra lead	1035.00	Mtr.	₹ 11.50	Rupees eleven and paise five zero only	₹ 11,903.00
7	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	2000.00	Sqm	₹ 7.70	Rupees seven and paise seven zero only	₹ 15,400.00
8	Mazdoor (Day work)	27	Nos	₹ 205.00	Rupees two hundred six and paise zero only	₹ 5,562.00
9	Mazdoor (Night work)	54	Nos	₹ 205.00	Rupees two hundred six and paise zero only	₹ 11,124.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
10	Supplying 500 C.P. incandescent lamp (i.e. petromax daylight, Hasag, etc.) on hire basis for 10 hours including supply of necessary fuel etc. complete.	27	Each	₹ 112.00	Rupees one hundred twelve and paise zero only	₹ 3,024.00
11	Supplying brush wood including tying them in bundles with 12 SWG galvanized wire filling in specified areas in bundles and providing ties with half split bamboos fitted, fixed including lead upto 2 km and all lifts, laying and placing complete as per direction of the Engineer in charge.(measurement to be made on volume of each bundle)	50.00	Cum	₹ 55.60	Rupees fifty five and paise six zero only	₹ 2,780.00
	Total Amount put to Tender in figure =					₹ 1,18,827.00
	Total Amount put to Tender in word :			Rupees one lakh eighteen thousand eight hundred and twenty seven only		


 Executive Engineer
 West Midnapore Division
 Irrigation & Waterways Dte.
 Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)

Page 1 of 2
Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur
email id- eewmid2012@gmail.com

NIT NO- WBIW/EE/WMD/NIT-08 of 2017-18

Sl. No. 15

Schedule of Quantity, Unit, Rate and Amount for the work FPM works in between Ch.23.20 KM & 26.00 KM of TE3H2 embkkt. Left Bank of River New Cossy under Khanamohan (I) Section of Lachmapur (I) Sub- Division under West Midnapore Division during the year 2017-18.

Amount put to Tender :

₹ 1,09,587.00

Earnest Money :

₹ 2,192.00

Time allowed for Completion :

150 days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Supplying, dressing and stacking at site bamboo pins (diametre to be measured at mid length (a) Above 5 cm to 7.50 cm diametre.	1080.00	Mtr.	₹ 23.60	Rupees twenty three and paise six zero only	₹ 25,488.00
2	Driving bamboo pins of average 5 cm to 7.5 cm diametre (payment will be made for driven length only) (i) Where boats are not necessary a) Not less than 5 cm. Av. Diametre	540.00	Mtr.	₹ 6.30	Rupees six and paise three zero only	₹ 3,402.00
3	Supplying, fitting, fixing with iron nails, half split bamboo walling pieces. (Diametre of bamboo not less than 5 cm, to be measured at mid length)	240.00	Mtr.	₹ 19.30	Rupees nineteen and paise three zero only	₹ 4,632.00
4	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg)	2300.00	Mtr.	₹ 5.00	Rupees five and paise zero only	₹ 11,500.00
5	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge. NB:- Volume of earth/ sand filled bags should not be less than 0.028 m ³ / bag	2300.00	Mtr.	₹ 6.30	Rupees six and paise three zero only	₹ 14,490.00
6	Extra rate in item no. 5.00 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres.	1035.00	Mtr.	₹ 9.20	Rupees nine and paise two zero only	₹ 9,522.00
	a) 3 (Three) extra lead b) 4 (Four) extra lead	1035.00	Mtr.	₹ 11.50	Rupees eleven and paise five zero only	₹ 11,903.00
7	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	800.00	Sqm	₹ 7.70	Rupees seven and paise seven zero only	₹ 6,160.00
8	Mazdoor (Day work)	27	Nos	₹ 206.00	Rupees two hundred six and paise zero only	₹ 5,562.00
9	Mazdoor (Night work)	54	Nos	₹ 206.00	Rupees two hundred six and paise zero only	₹ 11,124.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
10	Supplying 500 C.P. incandescent lamp (i.e. petromax daylight, Hasag, etc.) on hire basis for 10 hours including supply of necessary fuel etc. complete.	27	Each	₹ 112.00	Rupees one hundred twelve and paise zero only	₹ 3,024.00
11	Supplying brush wood including tying them in bundles with 12 SWG galvanized wire filling in specified areas in bundles and providing ties with half split bamboos fitted, fixed including lead upto 2 km and all lifts, laying and placing complete as per direction of the Engineer- in - charge.(measurement to be made on volume of each bundle)	50.00	Cum	₹ 55.60	Rupees fifty five and paise six zero only	₹ 2,780.00
	Total Amount put to Tender in figure =					₹ 1,09,587.00
	Total Amount put to Tender in word :			Rupees one lakh nine thousand five hundred and eighty seven only		


 Executive Engineer
 West Midnapore Division
 Irrigation & Waterways Dte.
 Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

NIT NO- WBIW/EE/WMD/NIT-08 of 2017-18

Sl. No. 16

Schedule of Quantity, Unit, Rate and Amount for the work, "Flood Precautionary Measure (FPM) of Chetua Circuit Embankment from Ch. 22.00 Km to 26.00 Km along R/B of River Rupnarayan in c/w monsoon- 2017 in Mouzas- Koijuri & Benai in Block- Daspur- II, Dist. Paschim Medinipur under Ajuria Section of Ghatal Irrigation Sub-Division under West Midnapore Division."


Amount put to Tender : ₹ 1,03,021.00

Earnest Money : ₹ 2,060.00

Time allowed for Completion : 150 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	1200.00	sqm	₹ 7.70	Rupees seven and paise seventy only	₹ 9,240.00
2	Supplying, dressing and stacking at site bamboo pins (diameter to be measured at mid length (a) Above 5 cm to 7.50 cm diameter.	600.00	m	₹ 23.60	Rupees twenty three and paise sixty only	₹ 14,160.00
3	Driving bamboo pins of average 5 cm to 7.5 cm diameter (payment will be made for driven length only) (i) Where boats are not necessary	400.00	m	₹ 6.30	Rupees six and paise thirty only	₹ 2,520.00
4	Supplying, fitting, fixing with iron nails, half split bamboo wailing pieces. (Diameter of bamboo not less than 5 cm, to be measured at mid length)	176.00	m	₹ 19.30	Rupees nineteen and paise thirty only	₹ 3,397.00
5	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	1955.00	each	₹ 5.00	Rupees five only	₹ 9,775.00
6	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge.	1955.00	each	₹ 6.30	Rupees six and paise thirty only	₹ 12,317.00
7	Extra rate in Sl. No. 6 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres. 5 (five) Extra Lead	1955.00	each	(₹ 2.30 x 5) = ₹ 11.50	Rupees eleven three and paise fifty only	₹ 22,483.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
8	Earthwork, transporting the earth by manually operated thela/ van/ ricksaw etc. beyond the lead of 150 metres and upto 500 metre including removal of jungle and trees upto 30 cm girth, all cost of excavation of earth in all kinds of soil, loading, transporting, unloading, stacking, placing the same or making embankments, rough dressing etc. Including all lifts, as directed by the Engineer-in-charge.	100.00	cum	₹ 138.90	Rupees one hundred thirty eight and paise ninety only	₹ 13,890.00
9	Extra rate in Sl. No. 8 above for each additional lead of 500 metre or part there of beyond the initial lead of 500 metre. NB:- This item is applicable only where the track/ tractors are not accessible at site. 3 (three) Extra Lead	100.00	cum	(₹ 20.70 × 3) = ₹ 62.10	Rupees sixty two and paise ten only	₹ 6,210.00
10	SUPPLY OF LABOUR : Mazdoor	36.00	Per Day	₹ 206.00	Rupees two hundred six only	₹ 7,416.00
11	Supplying 500 C. P. incandescent lamp [i.e. Petromax daylight, Hasag etc.] on hire basis for 10 hours including supply of necessary fuel etc. complete.	12.00	each	₹ 134.40	Rupees one hundred thirty four and paise forty only	₹ 1,613.00
Total Amount put to Tender in figure =						₹ 1,03,021.00
Total Amount put to Tender in word :						Rupees One lakh three thousand twenty one only


 Executive Engineer
 West Midnapore Division
 Irrigation & Waterways Dte.
 Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)

Govt. of West Bengal
Irrigation & Waterways Dto.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

NIT NO- WBIW/EE/WMD/NIT-08 of 2017-18

Sl. No. 17

Schedule of Quantity, Unit, Rate and Amount for the work, "Flood Precautionary Measure (FPM) of Chetua Circuit Embankment from Ch. 53.00 Km to 57.00 Km along L/B of River Old Cossye in c/w monsoon- 2017 in Mouzas- Dadpur, Gokulnagar & Jadupur in Block- Daspur- I, Dist. Paschim Medinipur under Dussaspur- I Section of Ghatal Irrigation Sub-Division under West Midnapore Division."


Amount put to Tender : ₹ 1,39,358.00

Earnest Money : ₹ 2,787.00

Time allowed for Completion : 150 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	1800.00	sqm	₹ 7.70	Rupees seven and paise seventy only	₹ 13,860.00
2	Supplying, dressing and stacking at site bamboo pins (diametre to be measured at mid length (a) Above 5 cm to 7.50 cm diametre.	1140.00	m	₹ 23.60	Rupees twenty three and paise sixty only	₹ 26,904.00
3	Driving bamboo pins of average 5 cm to 7.5 cm diametre (payment will be made for driven length only) (i) Where boats are not necessary	760.00	m	₹ 6.30	Rupees six and paise thirty only	₹ 4,788.00
4	Supplying, fitting, fixing with iron nails, half split bamboo walling pieces. (Diametre of bamboo not less than 5 cm, to be measured at mid length)	256.00	m	₹ 19.30	Rupees nineteen and paise thirty only	₹ 4,941.00
5	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	2620.00	each	₹ 5.00	Rupees five only	₹ 13,100.00
6	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge.	2620.00	each	₹ 6.30	Rupees six and paise thirty only	₹ 16,506.00
7	Extra rate in Sl. No. 6 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres. 5 (five) Extra Lead	2620.00	each	(₹ 2.30 x 5) = ₹ 11.50	Rupees eleven three and paise fifty only	₹ 30,130.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
8	Earthwork, transporting the earth by manually operated thela/ van/ ricksaw etc. beyond the lead of 150 metres and upto 500 metre including removal of jungle and trees upto 30 cm girth, all cost of excavation of earth in all kinds of soil, loading, transporting, unloading, stacking, placing the same or making embankments, rough dressing etc. including all lifts, as directed by the Engineer-in-charge.	100.00	cum	₹ 138.90	Rupees one hundred thirty eight and paise ninety only	₹ 13,890.00
9	Extra rate in Sl. No. 8 above for each additional lead of 500 metre or part there of beyond the initial lead of 500 metre. NB:- This item is applicable only where the track/ tractors are not accessible at site. 3 (three) Extra Lead	100.00	cum	(₹ 20.70 x 3) = ₹ 62.10	Rupees sixty two and paise ten only	₹ 6,210.00
10	SUPPLY OF LABOUR : Mazdoor	36.00	Per Day	₹ 206.00	Rupees two hundred six only	₹ 7,416.00
11	Supplying 500 C. P. incandescent lamp (I.e. Petromax daylight, Hasag etc.) on hire basis for 10 hours including supply of necessary fuel etc. complete.	12.00	each	₹ 134.40	Rupees one hundred thirty four and paise forty only	₹ 1,613.00
Total Amount put to Tender in figure =						₹ 1,39,358.00
Total Amount put to Tender in word :						Rupees One lakh thirty nine thousand three hundred and fifty eight only


 Executive Engineer
 West Midnapore Division
 Irrigation & Waterways Dte.
 Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

NIT NO- WBIW/EE/WMD/NIT-08 of 2017-18

Sl. No. 18

Schedule of Quantity, Unit, Rate and Amount for the work, "Flood Precautionary Measure (FPM) of Chetua Circuit Embankment from Ch. 70.00 Km to 72.00/0.00 Km to 3.00 km along R/B of River Silabati in c/w monsoon- 2017 in Mouzas- Gadighat, Nimtala & Konnagar in Block- Ghatal & Ghatai Municipality, Dist. Paschim Medinipur under Ghatal Section of Ghatal Irrigation Sub-Division under West Midnapore Division."

Amount put to Tender : ₹ 1,12,463.00

Earnest Money : ₹ 2,249.00

Time allowed for Completion : 150 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	1650.00	sqm	₹ 7.70	Rupees seven and paise seventy only	₹ 12,705.00
2	Supplying, dressing and stacking at site bamboo pins (diametre to be measured at mid length (a) Above 5 cm to 7.50 cm diametre.	750.00	m	₹ 23.60	Rupees twenty three and paise sixty only	₹ 17,700.00
3	Driving bamboo pins of average 5 cm to 7.5 cm diametre (payment will be made for driven length only) (i) Where boats are not necessary	500.00	m	₹ 6.30	Rupees six and paise thirty only	₹ 3,150.00
4	Supplying, fitting, fixing with iron nails, half split bamboo walling pieces. (Diametre of bamboo not less than 5 cm, to be measured at mid length)	180.00	m	₹ 19.30	Rupees nineteen and paise thirty only	₹ 3,474.00
5	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	1711.50	each	₹ 5.00	Rupees five only	₹ 8,558.00
6	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge.	1711.50	each	₹ 6.30	Rupees six and paise thirty only	₹ 10,782.00
7	Extra rate in Sl. No. 6 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres.	0.00		(₹ 2.30 x 5) =	Rupees eleven three and paise fifty only	
	5 (five) Extra Lead	1711.50	each	₹ 11.50		₹ 19,682.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
8	Earthwork, transporting the earth by manually operated thela/ van/ ricksaw etc. beyond the lead of 150 metres and upto 500 metre including removal of jungle and trees upto 30 cm girth, all cost of excavation of earth in all kinds of soil, loading, transporting, unloading, stacking, placing the same or making embankments, rough dressing etc. including all lifts, as directed by the Engineer-in-charge.	125.00	cum	₹ 138.90	Rupees one hundred thirty eight and paise ninety only	₹ 17,363.00
9	Extra rate in Sl. No. 8 above for each additional lead of 500 metre or part there of beyond the initial lead of 500 metre. NB:- This item is applicable only where the track/ tractors are not accessible at site. 3 (three) Extra Lead	0.00		(₹ 20.70 x 3) =		
		125.00	cum	₹ 62.10	Rupees sixty two and paise ten only	₹ 7,763.00
10	SUPPLY OF LABOUR : Mazdoor	45.00	Per Day	₹ 206.00	Rupees two hundred six only	₹ 9,270.00
11	Supplying 500 C. P. incandescent lamp (i.e. Petromax daylight, Hasag etc.) on hire basis for 10 hours including supply of necessary fuel etc. complete.	15.00	each	₹ 134.40	Rupees one hundred thirty four and paise forty only	₹ 2,016.00
Total Amount put to Tender in figure =						₹ 1,12,463.00
Total Amount put to Tender in word :						Rupees One lakhtwelve thousand four hundred sixty three only


 Executive Engineer
 West Midnapore Division
 Irrigation & Waterways Dte.
 Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

NIT NO- WBIW/EE/WMD/NIT-08 of 2017-18

SI. No. 19

Schedule of Quantity, Unit, Rate and Amount for the work, "Flood Precautionary Measure (FPM) of Chetua Circuit Embankment from Ch. 3.30 Km to 7.30 Km along R/B of River Silabati in c/w monsoon- 2017 in Mouzas- Konnagar, Harisingpur, Pratappur, & Ratneswarbati in Block- Ghatal, Dist. Paschim Medinipur under Ghatal Section of Ghatal Irrigation Sub-Division under West Midnapore Division."


Amount put to Tender : ₹ 1,70,737.00

Earnest Money : ₹ 3,415.00

Time allowed for Completion : 150 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	2700.00	sqm	₹ 7.70	Rupees seven and paise seventy only	₹ 20,790.00
2	Supplying, dressing and stacking at site bamboo pins (diametre to be measured at mid length (a) Above 5 cm to 7.50 cm diametre.	1462.50	m	₹ 23.60	Rupees twenty three and paise sixty only	₹ 34,515.00
3	Driving bamboo pins of average 5 cm to 7.5 cm diametre (payment will be made for driven length only) (i) Where boats are not necessary	975.00	m	₹ 6.30	Rupees six and paise thirty only	₹ 6,143.00
4	Supplying, fitting, fixing with iron nails, half split bamboo wailing pieces. (Diametre of bamboo not less than 5 cm, to be measured at mid length)	330.00	m	₹ 19.30	Rupees nineteen and paise thirty only	₹ 6,369.00
5	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	2917.00	each	₹ 5.00	Rupees five only	₹ 14,585.00
6	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge.	2917.00	each	₹ 6.30	Rupees six and paise thirty only	₹ 18,377.00
7	Extra rate in Sl. No. 6 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres.	0.00		(₹ 2.30 x 5) =	Rupees elean three and paise fifty only	
	5 (five) Extra Lead	2917.00	each	₹ 11.50		₹ 33,546.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
8	Earthwork, transporting the earth by manually operated thela/ van/ ricksaw etc. beyond the lead of 150 metres and upto 500 metre including removal of jungle and trees upto 30 cm girth, all cost of excavation of earth in all kinds of soil, loading, transporting, unloading, stacking, placing the same or making embankments, rough dressing etc. including all lifts, as directed by the Engineer-in-charge.	125.00	cum	₹ 138.90	Rupees one hundred thirty eight and paise ninety only	₹ 17,363.00
9	Extra rate in Sl. No. 8 above for each additional lead of 500 metre or part there of beyond the initial lead of 500 metre. NB:- This item is applicable only where the track/ tractors are not accessible at site. 3 (three) Extra Lead			(₹ 20.70 x 3) =		
		125.00	cum	₹ 62.10	Rupees sixty two and paise ten only	₹ 7,763.00
10	SUPPLY OF LABOUR : Mazdoor	45.00	Per Day	₹ 206.00	Rupees two hundred six only	₹ 9,270.00
11	Supplying 500 C. P. incandescent lamp (i.e. Petromax daylight, Hasag etc.) on hire basis for 10 hours including supply of necessary fuel etc. complete.	15.00	each	₹ 134.40	Rupees one hundred thirty four and paise forty only	₹ 2,016.00
Total Amount put to Tender in figure =						₹ 1,70,737.00
Total Amount put to Tender in word :						Rupees One lakh seventy thousand seven hundred thirty seven only


 Executive Engineer
 West Midnapore Division
 Irrigation & Waterways Dte.
 Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

NIT NO- WBIW/EE/WMD/NIT-08 of 2017-18

Sl. No. 20

Schedule of Quantity, Unit, Rate and Amount for the work, "Flood Precautionary Measure (FPM) of Mohankhali Circuit Embankment from Ch. 45.00 Km to 51.00 Km along R/B of River Rupnarayan in c/w monsoon- 2017 in Mouzas- Kultikri, Dudkumra, kasiara & Sibara in Block- Daspur- II, Dist. Paschim Medinipur under Ajuria Section of Ghatal Irrigation Sub-Division under West Midnapore Division."

Amount put to Tender : ₹ 1,55,215.00

Earnest Money : ₹ 3,104.00

Time allowed for Completion : 150 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	1800.00	sqm	₹ 7.70	Rupees seven and paise seventy only	₹ 13,860.00
2	Supplying, dressing and stacking at site bamboo pins (diametre to be measured at mid length (a) Above 5 cm to 7.50 cm diametre.	972.00	m	₹ 23.60	Rupees twenty three and paise sixty only	₹ 22,939.00
3	Driving bamboo pins of average 5 cm to 7.5 cm diametre (payment will be made for driven length only) (i) Where boats are not necessary	648.00	m	₹ 6.30	Rupees six and paise thirty only	₹ 4,082.00
4	Supplying, fitting, fixing with iron nails, half split bamboo walling pieces. (Diametre of bamboo not less than 5 cm, to be measured at mid length)	288.00	m	₹ 19.30	Rupees nineteen and paise thirty only	₹ 5,558.00
5	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	2854.50	each	₹ 5.00	Rupees five only	₹ 14,273.00
6	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge.	2854.50	each	₹ 6.30	Rupees six and paise thirty only	₹ 17,983.00
7	Extra rate in Sl. No. 6 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres.	0.00		(₹ 2.30 x 5) =	Rupees eleven three and paise fifty only	
	5 (five) Extra Lead	2854.50	each	₹ 11.50		₹ 32,827.00

Abstract of Cost

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
8	Earthwork, transporting the earth by manually operated thela/ van/ ricksaw etc. beyond the lead of 150 metres and upto 500 metre including removal of jungle and trees upto 30 cm girth, all cost of excavation of earth in all kinds of soil, loading, transporting, unloading, stacking, placing the same or making embankments, rough dressing etc. including all lifts, as directed by the Engineer-in-charge.	150.00	cum	₹ 138.90	Rupees one hundred thirty eight and paise ninety only	₹ 20,835.00
9	Extra rate in Sl. No. 8 above for each additional lead of 500 metre or part there of beyond the initial lead of 500 metre. NB:- This item is applicable only where the track/ tractors are not accessible at site. 3 (three) Extra Lead	0.00		(₹ 20.70 x 3) =		
		150.00	cum	₹ 62.10	Rupees sixty two and paise ten only	₹ 9,315.00
10	SUPPLY OF LABOUR : Mazdoor	54.00	Per Day	₹ 206.00	Rupees two hundred six only	₹ 11,124.00
11	Supplying 500 C. P. incandescent lamp (i.e. Petromax daylight, Hasag etc.) on hire basis for 10 hours including supply of necessary fuel etc. complete.	18.00	each	₹ 134.40	Rupees one hundred thirty four and paise forty only	₹ 2,419.00
Total Amount put to Tender in figure =						₹ 1,55,215.00
Total Amount put to Tender in word :						Rupees One lakh fifty five thousand two hundred and fifteen only


 Executive Engineer
 West Midnapore Division
 Irrigation & Waterways Dte.
 Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)