

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

NIT NO- WBIW/EE/WMD/NIT-08 of 2017-18

Sl. No. 21

Schedule of Quantity, Unit, Rate and Amount for the work, "Flood Precautionary Measure (FPM) of Mohankhali Circuit Embankment from Ch. 5.00 Km to 12.00 Km along L/B of River Durbachati in c/w monsoon- 2017 in Mouzas- Nona narayanchack, Donga bhanga, Narayan chack & Kasinathpur in Block- Daspur- II, Dist. Paschim Medinipur under Ajuria Section of Ghatal Irrigation Sub-Division under West Midnapore Division."

Amount put to Tender : ₹ 1,79,256.00

Earnest Money : ₹ 3,585.00

Time allowed for Completion : 150 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	2100.00	sqm	₹ 7.70	Rupees seven and paise seventy only	₹ 16,170.00
2	Supplying, dressing and stacking at site bamboo pins (diametre to be measured at mid length (a) Above 5 cm to 7.50 cm diametre.	1134.00	m	₹ 23.60	Rupees twenty three and paise sixty only	₹ 26,762.00
3	Driving bamboo pins of average 5 cm to 7.5 cm diametre (payment will be made for driven length only) (i) Where boats are not necessary	756.00	m	₹ 6.30	Rupees six and paise thirty only	₹ 4,763.00
4	Supplying, fitting, fixing with iron nails, half split bamboo wailing pieces. (Diametre of bamboo not less than 5 cm, to be measured at mid length)	336.00	m	₹ 19.30	Rupees nineteen and paise thirty only	₹ 6,485.00
5	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	3250.00	each	₹ 5.00	Rupees five only	₹ 16,250.00
6	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge.	3250.00	each	₹ 6.30	Rupees six and paise thirty only	₹ 20,475.00
7	Extra rate in Sl. No. 6 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres.			(₹ 2.30 x 5) =	Rupees eleven three and paise fifty only	
	5 (five) Extra Lead	3250.00	each	₹ 11.50		₹ 37,375.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
8	Earthwork, transporting the earth by manually operated thela/ van/ ricksaw etc. beyond the lead of 150 metres and upto 500 metre including removal of jungle and trees upto 30 cm girth, all cost of excavation of earth in all kinds of soil, loading, transporting, unloading, stacking, placing the same or making embankments, rough dressing etc. including all lifts, as directed by the Engineer-incharge.	175.00	cum	₹ 138.90	Rupees one hundred thirty eight and paise ninety only	₹ 24,308.00
9	Extra rate in Sl. No. 8 above for each additional lead of 500 metre or part there of beyond the initial lead of 500 metre. NB:- This item is applicable only where the track/ tractors are not accessible at site. 3 (three) Extra Lead	175.00	cum	(₹ 20.70 x 3) = ₹ 62.10	Rupees sixty two and paise ten only	₹ 10,868.00
10	SUPPLY OF LABOUR : Mazdoor	63.00	Per Day	₹ 206.00	Rupees two hundred six only	₹ 12,978.00
11	Supplying 500 C. P. incandescent lamp (i.e. Petromax daylight, Hasag etc.) on hire basis for 10 hours including supply of necessary fuel etc. complete.	21.00	each	₹ 134.40	Rupees one hundred thirty four and paise forty only	₹ 2,822.00
Total Amount put to Tender in figure =						₹ 1,79,256.00
Total Amount put to Tender in word :						Rupees One lakh seventy nine thousand two hundred and fifty six only


 Executive Engineer
 West Midnapore Division
 Irrigation & Waterways Dte.
 Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

NIT NO- WBIW/EE/WMD/NIT-08 of 2017-18

Sl. No. 22

Schedule of Quantity, Unit, Rate and Amount for the work, "Flood Precautionary Measure (FPM) of Dussaspur Circuit Embankment from Ch. 20.50 Km to 25.50 Km & 28.50 km to 29.50 km along L/B of Bhosra Khal in c/w monsoon- 2017 in Mouzas- Paikan Boalia, Jyotisab & Manikpur in Block- Daspur- I, Dist. Paschim Medinipur under Dussaspur- II Section of Ghatal Irrigation Sub-Division under West Midnapore Division."

Amount put to Tender : ₹ 1,92,912.00


Earnest Money : ₹ 3,858.00

Time allowed for Completion : 150 Days

Sl. No.	Description of Items	No. or Quantity	No. or Quantity	Unit	Estimated Rate		Amount
					Figure	Word	
1	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	3000.00	1500.00	sqm	₹ 7.70	Rupees seven and paise seventy only	₹ 11,550.00
2	Supplying, dressing and stacking at site bamboo pins (diametre to be measured at mid length) (a) Above 5 cm to 7.50 cm diametre.	2430.00	1215.00	m	₹ 23.60	Rupees twenty three and paise sixty only	₹ 28,674.00
3	Driving bamboo pins of average 5 cm to 7.5 cm diametre (payment will be made for driven length only) (i) Where boats are not necessary	1620.00	810.00	m	₹ 6.30	Rupees six and paise thirty only	₹ 5,103.00
4	Supplying, fitting, fixing with iron nails, half split bamboo wailing pieces. (Diametre of bamboo not less than 5 cm, to be measured at mid length)	552.00	276.00	m	₹ 19.30	Rupees nineteen and paise thirty only	₹ 5,327.00
5	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	8646.00	4323.00	each	₹ 5.00	Rupees five only	₹ 21,615.00
6	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge.	8646.00	4323.00	each	₹ 6.30	Rupees six and paise thirty only	₹ 27,235.00
7	Extra rate in Sl. No. 6 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres.		0.00		(₹ 2.30 x 5) =	Rupees eleven three and paise fifty only	
	5 (five) Extra Lead	8646.00	4323.00	each	₹ 11.50		₹ 49,715.00

Abstract of Cost

Sl. No.	Description of Items	No. or Quantity	No. or Quantity	Unit	Estimated Rate		Amount
					Figure	Word	
8	Earthwork, transporting the earth by manually operated thela/ van/ ricksaw etc. beyond the lead of 150 metres and upto 500 metre including removal of jungle and trees upto 30 cm girth, all cost of excavation of earth in all kinds of soil, loading, transporting, unloading, stacking, placing the same or making embankments, rough dressing etc. including all lifts, as directed by the Engineer-incharge.	300.00	150.00	cum	₹ 138.90	Rupees one hundred thirty eight and paise ninety only	₹ 20,835.00
9	Extra rate in Sl. No. 8 above for each additional lead of 500 metre or part there of beyond the initial lead of 500 metre. NB:- This item is applicable only where the track/ tractors are not accessible at site. 3 (three) Extra Lead	300.00	0.00		(₹ 20.70 x 3) =		
			150.00	cum	₹ 62.10	Rupees sixty two and paise ten only	₹ 9,315.00
10	SUPPLY OF LABOUR : Mazdoor	108.00	54.00	Per Day	₹ 206.00	Rupees two hundred six only	₹ 11,124.00
11	Supplying 500 C. P. incandescent lamp (i.e. Petromax daylight, Hasag etc.) on hire basis for 10 hours including supply of necessary fuel etc. complete.	36.00	18.00	each	₹ 134.40	Rupees one hundred thirty four and paise forty only	₹ 2,419.00
Total Amount put to Tender in figure =							₹ 1,92,912.00
Total Amount put to Tender in word :					Rupees One lakh ninety two thousand nine hundred and twelve only		


 Executive Engineer
 West Midnapore Division
 Irrigation & Waterways Dte.
 Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

NIT NO- WBIW/EE/WMD/NIT-08 of 2017-18

Sl. No. 23

Schedule of Quantity, Unit, Rate and Amount for the work, "Flood Precautionary Measure (FPM) of Chetua Circuit Embankment from Ch. 57.00 Km to 67.00 Km along R/B of River Kanki in c/w monsoon- 2017 in Mouzas- Jodupur, Rajnagar, Ananda garh, harirampur, Gurli, Suratpur & Sitakundu in Block- Daspur- I, Dist. Paschim Medinipur under Ghatal Section of Ghatal Irrigation Sub-Division under West Midnapore Division."

Amount put to Tender : ₹ 2,28,373.00

Earnest Money : ₹ 4,567.00

Time allowed for Completion : 150 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	2100.00	sqm	₹ 7.70	Rupees seven and paise seventy only	₹ 16,170.00
2	Supplying, dressing and stacking at site bamboo pins (diameter to be measured at mid length (a) Above 5 cm to 7.50 cm diameter.	1875.00	m	₹ 23.60	Rupees twenty three and paise sixty only	₹ 44,250.00
3	Driving bamboo pins of average 5 cm to 7.5 cm diameter (payment will be made for driven length only) (i) Where boats are not necessary	1250.00	m	₹ 6.30	Rupees six and paise thirty only	₹ 7,875.00
4	Supplying, fitting, fixing with iron nails, half split bamboo wailing pieces. (Diameter of bamboo not less than 5 cm, to be measured at mid length)	420.00	m	₹ 19.30	Rupees nineteen and paise thirty only	₹ 8,106.00
5	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	3471.50	each	₹ 5.00	Rupees five only	₹ 17,358.00
6	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge.	3471.50	each	₹ 6.30	Rupees six and paise thirty only	₹ 21,870.00
7	Extra rate in Sl. No. 6 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres.	0.00		(₹ 2.30 x 5) =	Rupees eleven three and paise fifty only	
	5 (five) Extra Lead	3471.50	each	₹ 11.50		₹ 39,922.00

Abstract of Cost

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
8	Earthwork, transporting the earth by manually operated thela/ van/ ricksaw etc. beyond the lead of 150 metres and upto 500 metre including removal of jungle and trees upto 30 cm girth, all cost of excavation of earth in all kinds of soil, loading, transporting, unloading, stacking, placing the same or making embankments, rough dressing etc. including all lifts, as directed by the Engineer-in-charge.	250.00	cum	₹ 138.90	Rupees one hundred thirty eight and paise ninety only	₹ 34,725.00
9	Extra rate in Sl. No. 8 above for each additional lead of 500 metre or part there of beyond the initial lead of 500 metre. NB:- This item is applicable only where the track/ tractors are not accessible at site. 3 (three) Extra Lead	0.00		(₹ 20.70 x 3) =		
		250.00	cum	₹ 62.10	Rupees sixty two and paise ten only	₹ 15,525.00
10	SUPPLY OF LABOUR : Mazdoor	90.00	Per Day	₹ 206.00	Rupees two hundred six only	₹ 18,540.00
11	Supplying 500 C. P. incandescent lamp (i.e. Petromax daylight, Hasag etc.) on hire basis for 10 hours including supply of necessary fuel etc. complete.	30.00	each	₹ 134.40	Rupees one hundred thirty four and paise forty only	₹ 4,032.00
Total Amount put to Tender in figure =						₹ 2,28,373.00
Total Amount put to Tender in word :						Rupees Two lakh twenty eight thousand three hundred seventy three only


 Executive Engineer
 West Midnapore Division
 Irrigation & Waterways Dte.
 Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

NIT NO- WBIW/EE/WMD/NIT-08 of 2017-18

Sl. No. 24

Schedule of Quantity, Unit, Rate and Amount for the work, "Flood Precautionary Measure (FPM) of Chetua Circuit Embankment from Ch. 35.00 Km to 40.00 Km & 41.00 km to 44.00 km along L/B of River Palaspai in c/w monsoon-2017 in Mouzas- Satpota, Palaspai Singhachak, Jote Gobinda & Panchberya in Block- Daspur- II, Dist. Paschim Medinipur under Ajouria Section of Ghatal Irrigation Sub-Division under West Midnapore Division."


Amount put to Tender : ₹ 2,37,422.00

Earnest Money : ₹ 4,748.00

Time allowed for Completion : 150 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	2880.00	sqm	₹ 7.70	Rupees seven and paise seventy only	₹ 22,176.00
2	Supplying, dressing and stacking at site bamboo pins (diametre to be measured at mid length (a) Above 5 cm to 7.50 cm diametre.	1608.00	m	₹ 23.60	Rupees twenty three and paise sixty only	₹ 37,949.00
3	Driving bamboo pins of average 5 cm to 7.5 cm diametre (payment will be made for driven length only) (i) Where boats are not necessary	1072.00	m	₹ 6.30	Rupees six and paise thirty only	₹ 6,754.00
4	Supplying, fitting, fixing with iron nails, half split bamboo wailing pieces. (Diametre of bamboo not less than 5 cm, to be measured at mid length)	464.00	m	₹ 19.30	Rupees nineteen and paise thirty only	₹ 8,955.00
5	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	4532.00	each	₹ 5.00	Rupees five only	₹ 22,660.00
6	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge.	4532.00	each	₹ 6.30	Rupees six and paise thirty only	₹ 28,552.00
7	Extra rate in Sl. No. 6 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres.	0.00		(₹ 2.30 x 5) =	Rupees eleven three and paise fifty only	
	5 (five) Extra Lead	4532.00	each	₹ 11.50		₹ 52,118.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
8	Earthwork, transporting the earth by manually operated thela/ van/ ricksaw etc. beyond the lead of 150 metres and upto 500 metre including removal of jungle and trees upto 30 cm girth, all cost of excavation of earth in all kinds of soil, loading, transporting, unloading, stacking, placing the same or making embankments, rough dressing etc. including all lifts, as directed by the Engineer-in-charge.	200.00	cum	₹ 138.90	Rupees one hundred thirty eight and paise ninety only	₹ 27,780.00
9	Extra rate in Sl. No. 8 above for each additional lead of 500 metre or part there of beyond the initial lead of 500 metre. NB:- This item is applicable only where the track/ tractors are not accessible at site. 3 (three) Extra Lead	0.00		(₹ 20.70 x 3) =		
		200.00	cum	₹ 62.10	Rupees sixty two and paise ten only	₹ 12,420.00
10	SUPPLY OF LABOUR : Mazdoor	72.00	Per Day	₹ 206.00	Rupees two hundred six only	₹ 14,832.00
11	Supplying 500 C. P. incandescent lamp (i.e. Petromax daylight, Hasag etc.) on hire basis for 10 hours including supply of necessary fuel etc. complete.	24.00	each	₹ 134.40	Rupees one hundred thirty four and paise forty only	₹ 3,226.00
Total Amount put to Tender in figure =						₹ 2,37,422.00
Total Amount put to Tender in word :						Rupees Two lakh thirty seven thousand four hundred twenty two only


 Executive Engineer
 West Midnapore Division
 Irrigation & Waterways Dte.
 Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

NIT NO- WBIW/EE/WMD/NIT-08 of 2017-18

Sl. No. 25

Schedule of Quantity, Unit, Rate and Amount for the work, "Flood Precautionary Measure (FPM) of Mohankhali Circuit Embankment from Ch. 29.00 Km to 35.00 Km & 38 km to 40 km along R/B of River Palaspai in c/w monsoon- 2017 in Mouzas- Chak Sultan, Rampur, Manua , Sitapur, Palaspai & Jote ghanashyam in Block- Daspur- II, Dist. Paschim Medinipur under Ajuria Section of Ghatal Irrigation Sub-Division under West Midnapore Division."

Amount put to Tender : ₹ 2,19,148.00

Earnest Money : ₹ 4,383.00

Time allowed for Completion : 150 Days

Sl. No.	Description of Items	No. or Qty	Unit	Estimated Rate		Amount
				Figure	Word	
1	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	3120.00	sqm	₹ 7.70	Rupees seven and paise seventy only	₹ 24,024.00
2	Supplying, dressing and stacking at site bamboo pins (diametre to be measured at mid length (a) Above 5 cm to 7.50 cm diametre.	1392.00	m	₹ 23.60	Rupees twenty three and paise sixty only	₹ 32,851.00
3	Driving bamboo pins of average 5 cm to 7.5 cm diametre (payment will be made for driven length only) (i) Where boats are not necessary	928.00	m	₹ 6.30	Rupees six and paise thirty only	₹ 5,846.00
4	Supplying, fitting, fixing with iron nails, half split bamboo walling pieces. (Diametre of bamboo not less than 5 cm, to be measured at mid length)	416.00	m	₹ 19.30	Rupees nineteen and paise thirty only	₹ 8,029.00
5	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	3953.50	each	₹ 5.00	Rupees five only	₹ 19,768.00
6	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge.	3953.50	each	₹ 6.30	Rupees six and paise thirty only	₹ 24,907.00
7	Extra rate in Sl. No. 6 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres.	0.00		(₹ 2.30 x 5) =	Rupees eleven three and paise thirty only	
	5 (five) Extra Lead	3953.50	each	₹ 11.50		₹ 45,465.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
8	Earthwork, transporting the earth by manually operated thela/ van/ ricksaw etc. beyond the lead of 150 metres and upto 500 metre including removal of jungle and trees upto 30 cm girth, all cost of excavation of earth in all kinds of soil, loading, transporting, unloading, stacking, placing the same or making embankments, rough dressing etc. including all lifts, as directed by the Engineer-Incharge.	200.00	cum	₹ 138.90	Rupees one hundred thirty eight and paise ninety only	₹ 27,780.00
9	Extra rate in Sl. No. 8 above for each additional lead of 500 metre or part there of beyond the initial lead of 500 metre. NB:- This item is applicable only where the track/ tractors are not accessible at site. 3 (three) Extra Lead	0.00		(₹ 20.70 x 3) =		
		200.00	cum	₹ 62.10	Rupees sixty two and paise ten only	₹ 12,420.00
10	SUPPLY OF LABOUR ; Mazdoor	72.00	Per Day	₹ 206.00	Rupees two hundred six only	₹ 14,832.00
11	Supplying 500 C. P. incandescent lamp (i.e. Petromax daylight, Hasag etc.) on hire basis for 10 hours including supply of necessary fuel etc. complete.	24.00	each	₹ 134.40	Rupees one hundred thirty four and paise forty only	₹ 3,226.00
Total Amount put to Tender in figure =						₹ 2,19,148.00
Total Amount put to Tender in word :						Rupees Two lakh nineteen thousand one hundred and forty eight only


 Executive Engineer
 West Midnapore Division
 Irrigation & Waterways Dte.
 Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

 (Signature of the Contractor)

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

NIT NO- WBIW/EE/WMD/NIT-08 of 2017-18

Sl. No. 26

Schedule of Quantity, Unit, Rate and Amount for the work, "Flood Precautionary Measure (FPM) of Mohankhali Circuit Embankment from Ch. 12.00 Km to 22.00 Km along L/B of River Durbachati in c/w monsoon- 2017 in Mouzas- Brindabanchak, Shripur & Khukurdaha , Khukurdaha, Arkhana & Sahapur in Block- Kolaghat & Daspur-I & II, Dist. Paschim Medinipur under Dussaspur- I Section of Ghatal Irrigation Sub-Division under West Midnapore Division."

Amount put to Tender : ₹ 2,40,528.00

Earnest Money : ₹ 4,811.00

Time allowed for Completion : 150 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	3000.00	sqm	₹ 7.70	Rupees seven and paise seventy only	₹ 23,100.00
2	Supplying, dressing and stacking at site bamboo pins (diameter to be measured at mid length (a) Above 5 cm to 7.50 cm diameter.	1800.00	m	₹ 23.60	Rupees twenty three and paise sixty only	₹ 42,480.00
3	Driving bamboo pins of average 5 cm to 7.5 cm diameter (payment will be made for driven length only) (i) Where boats are not necessary	1200.00	m	₹ 6.30	Rupees six and paise thirty only	₹ 7,560.00
4	Supplying, fitting, fixing with iron nails, half split bamboo walling pieces. (Diameter of bamboo not less than 5 cm, to be measured at mid length)	400.00	m	₹ 19.30	Rupees nineteen and paise thirty only	₹ 7,720.00
5	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	3809.00	each	₹ 5.00	Rupees five only	₹ 19,045.00
6	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge.	3809.00	each	₹ 6.30	Rupees six and paise thirty only	₹ 23,997.00
7	Extra rate in Sl. No. 6 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres.	0.00		(₹ 2.30 x 5) =	Rupees eleven	
	5 (five) Extra Lead	3809.00	each	₹ 11.50	three and paise fifty only	₹ 43,804.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
8	Earthwork, transporting the earth by manually operated thela/ van/ ricksaw etc. beyond the lead of 150 metres and upto 500 metre including removal of jungle and trees upto 30 cm girth, all cost of excavation of earth in all kinds of soil, loading, transporting, unloading, stacking, placing the same or making embankments, rough dressing etc. including all lifts, as directed by the Engineer-in-charge.	250.00	cum	₹ 138.90	Rupees one hundred thirty eight and paise ninety only	₹ 34,725.00
9	Extra rate in Sl. No. 8 above for each additional lead of 500 metre or part there of beyond the initial lead of 500 metre. NB:- This item is applicable only where the track/ tractors are not accessible at site. 3 (three) Extra Lead	0.00		(₹ 20.70 x 3) =		
		250.00	cum	₹ 62.10	Rupees sixty two and paise ten only	₹ 15,525.00
10	SUPPLY OF LABOUR : Mazdoor	90.00	Per Day	₹ 206.00	Rupees two hundred six only	₹ 18,540.00
11	Supplying 500 C. P. incandescent lamp (i.e. Petromax daylight, Hasag etc.) on hire basis for 10 hours including supply of necessary fuel etc. complete.	30.00	each	₹ 134.40	Rupees one hundred thirty four and paise forty only	₹ 4,032.00
₹ 2,40,528.00						
Total Amount put to Tender in figure =						
Total Amount put to Tender in word :						Rupees Two lakh forty thousand five hundred twenty eight only


 Executive Engineer
 West Midnapore Division
 Irrigation & Waterways Dte.
 Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

NIT NO- WBIW/EE/WMD/NIT-08 of 2017-18

Sl. No. 27

Schedule of Quantity, Unit, Rate and Amount for the work, "Flood Precautionary Measure (FPM) of Dussaspur Circuit Embankment from Ch. 0.00 Km to 1.00 Km and 1.50 Km to 10.50 Km along R/B of River Old Cossye in c/w monsoon- 2017 in Mouzas- Poshtanka, Janardanpur, Damodarpur & Srirampur, Fakirbazar & Kolmijorein Block- Daspur- I, Dist. Paschim Medinipur under Dussaspur- II Section of Ghatal Irrigation Sub-Division under West Midnapore Division.

Amount put to Tender : ₹ 2,41,724.00

Earnest Money : ₹ 4,834.00

Time allowed for Completion : 150 Days

Sl. No.	Description of Items	No. or Quantity		Unit	Estimated Rate		Amount
					Figure	Word	
1	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	3600.00	1800.00	sqm	₹ 7.70	Rupees seven and paise seventy only	₹ 13,860.00
2	Supplying, dressing and stacking at site bamboo pins (diameter to be measured at mid length (a) Above 5 cm to 7.50 cm diameter.	3900.00	1950.00	m	₹ 23.60	Rupees twenty three and paise sixty only	₹ 46,020.00
3	Driving bamboo pins of average 5 cm to 7.5 cm diameter (payment will be made for driven length only) (i) Where boats are not necessary	2600.00	1300.00	m	₹ 6.30	Rupees six and paise thirty only	₹ 8,190.00
4	Supplying, fitting, fixing with iron nails, half split bamboo walling pieces. (Diameter of bamboo not less than 5 cm, to be measured at mid length)	880.00	440.00	m	₹ 19.30	Rupees nineteen and paise thirty only	₹ 8,492.00
5	Supplying to site 2nd hand cement poly bags in good condition delivered and stacked (capacity 50 kg).	8100.00	4050.00	each	₹ 5.00	Rupees five only	₹ 20,250.00
6	Labour charge for filling poly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge.	8100.00	4050.00	each	₹ 6.30	Rupees six and paise thirty only	₹ 25,515.00
7	Extra rate in Sl. No. 6 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres.		0.00		(₹ 2.30 x 5) =	Rupees eleven three and paise	
	5 (five) Extra Lead	8100.00	4050.00	each	₹ 11.50	fifty only	₹ 46,575.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
8	Earthwork, transporting the earth by manually operated thela/ van/ ricksaw etc. beyond the lead of 150 metres and upto 500 metre including removal of jungle and trees upto 30 cm girth, all cost of excavation of earth in all kinds of soil, loading, transporting, unloading, stacking, placing the same or making embankments, rough dressing etc. including all lifts, as directed by the Engineer-incharge.	500.00	250.00	cum	₹ 138.90	Rupees one hundred thirty eight and paise ninety only ₹ 34,725.00
9	Extra rate in Sl. No. 8 above for each additional lead of 500 metre or part there of beyond the initial lead of 500 metre. NB:- This item is applicable only where the track/ tractors are not accessible at site. 3 (three) Extra Lead	500.00	0.00		(₹ 20.70 x 3) = ₹ 62.10	Rupees sixty two and paise ten only ₹ 15,525.00
10	SUPPLY OF LABOUR : Mazdoor	180.00	90.00	Per Day	₹ 206.00	Rupees two hundred six only ₹ 18,540.00
11	Supplying 500 C. P. incandescent lamp (i.e. Petromax daylight, Hasag etc.) on hire basis for 10 hours including supply of necessary fuel etc. complete.	60.00	30.00	each	₹ 134.40	Rupees one hundred thirty four and paise forty only ₹ 4,032.00
Total Amount put to Tender in figure =						₹ 2,41,724.00
Total Amount put to Tender in word :						Rupees Two lakh forty one thousand seven hundred and twenty four only


 Executive Engineer
 West Midnapore Division
 Irrigation & Waterways Dte.
 Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

NIT NO- WBIW/EE/WMD/NIT-08 of 2017-18

Sl. No. 28

Schedule of Quantity, Unit, Rate and Amount for the work, "Flood Precautionary Measure (FPM) of Dussaspur Circuit Embankment from Ch. 11.00 Km to 20.00 Km along R/B of River Old Cossye & Durbachati in c/w monsoon- 2017 in Mouzas- Maheshpur, Kismat Kalora, Tatarkhan, Basantapur, Tilanda & Nizampur in Block- Daspur- I, Dist. Paschim Medinipur under Dussaspur- II Section of Ghatal Irrigation Sub-Division under West Midnapore Division."


Amount put to Tender : ₹ 2,28,915.00

Earnest Money : ₹ 4,578.00

Time allowed for Completion : 150 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	2250.00	sqm	₹ 7.70	Rupees seven and paise seventy only	₹ 17,325.00
2	Supplying, dressing and stacking at site bamboo pins (diametre to be measured at mid length (a) Above 5 cm to 7.50 cm diametre.	1822.50	m	₹ 23.60	Rupees twenty three and paise sixty only	₹ 43,011.00
3	Driving bamboo pins of average 5 cm to 7.5 cm diametre (payment will be made for driven length only) (i) Where boats are not necessary	1215.00	m	₹ 6.30	Rupees six and paise thirty only	₹ 7,655.00
4	Supplying, fitting, fixing with iron nails, half split bamboo walling pieces. (Diametre of bamboo not less than 5 cm, to be measured at mid length)	414.00	m	₹ 19.30	Rupees nineteen and paise thirty only	₹ 7,990.00
5	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	3833.00	each	₹ 5.00	Rupees five only	₹ 19,165.00
6	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge.	3833.00	each	₹ 6.30	Rupees six and paise thirty only	₹ 24,148.00
7	Extra rate in Sl. No. 6 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres.	0.00		(₹ 2.30 x 5) =	Rupees eleven three and paise fifty only	
	5 (five) Extra Lead	3833.00	each	₹ 11.50		₹ 44,080.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
8	Earthwork, transporting the earth by manually operated thela/ van/ rickshaw etc. beyond the lead of 150 metres and upto 500 metre including removal of jungle and trees upto 30 cm girth, all cost of excavation of earth in all kinds of soil, loading, transporting, unloading, stacking, placing the same or making embankments, rough dressing etc. including all lifts, as directed by the Engineer-in-charge.	225.00	cum	₹ 138.90	Rupees one hundred thirty eight and paise ninety only	₹ 31,253.00
9	Extra rate in Sl. No. 8 above for each additional lead of 500 metre or part there of beyond the initial lead of 500 metre. NB:- This item is applicable only where the track/ tractors are not accessible at site. 3 (three) Extra Lead	0.00		(₹ 20.70 x 3) =		
		225.00	cum	₹ 62.10	Rupees sixty two and paise ten only	₹ 13,973.00
10	SUPPLY OF LABOUR : Mazdoor	81.00	Per Day	₹ 206.00	Rupees two hundred six only	₹ 16,686.00
11	Supplying 500 C. P. incandescent lamp (i.e. Petromax daylight, Hasag etc.) on hire basis for 10 hours including supply of necessary fuel etc. complete.	27.00	each	₹ 134.40	Rupees one hundred thirty four and paise forty only	₹ 3,629.00
Total Amount put to Tender in figure =						₹ 2,28,915.00
Total Amount put to Tender in word :						Rupees Two lakh twenty eight thousand nine hundred and fifteen only


 Executive Engineer
 West Midnapore Division
 Irrigation & Waterways Dte.
 Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

NIT NO- WBIW/EE/WMD/NIT-08 of 2017-18

SI. No. 29

Schedule of Quantity, Unit, Rate and Amount for the work, "Flood Precautionary Measure (FPM) of Chetua Circuit Embankment from Ch. 44.50 Km to 52.50 Km along L/B of River Old Cossye & Palaspai in c/w monsoon- 2017 in Mouzas- Uttar Gobindanagar, Banskhal, Kalora, Maheshpur, Kunjapur, Kolmijore & Paikan Durjyodhan in Block- Daspur- I, Dist. Paschim Medinipur under Dussaspur- I Section of Ghatal Irrigation Sub-Division under West Midnapore


Amount put to Tender : ₹ 2,24,949.00

Earnest Money : ₹ 4,499.00

Time allowed for Completion : 150 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	2400.00	sqm	₹ 7.70	Rupees seven and paise seventy only	₹ 18,480.00
2	Supplying, dressing and stacking at site bamboo pins (diametre to be measured at mid length) (a) Above 5 cm to 7.50 cm diametre.	1680.00	m	₹ 23.60	Rupees twenty three and paise sixty only	₹ 39,648.00
3	Driving bamboo pins of average 5 cm to 7.5 cm diametre (payment will be made for driven length only) (i) Where boats are not necessary	1120.00	m	₹ 6.30	Rupees six and paise thirty only	₹ 7,056.00
4	Supplying, fitting, fixing with iron nails, half split bamboo wailing pieces. (Diametre of bamboo not less than 5 cm, to be measured at mid length)	384.00	m	₹ 19.30	Rupees nineteen and paise thirty only	₹ 7,411.00
5	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	4127.00	each	₹ 5.00	Rupees five only	₹ 20,635.00
6	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge.	4127.00	each	₹ 6.30	Rupees six and paise thirty only	₹ 26,000.00
7	Extra rate in Sl. No. 6 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres.	0.00		(₹ 2.30 x 5) =	Rupees eleven three and paise	
	5 (five) Extra Lead	4127.00	each	₹ 11.50	fifty only	₹ 47,461.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
8	Earthwork, transporting the earth by manually operated thela/ van/ ricksaw etc. beyond the lead of 150 metres and upto 500 metre including removal of jungle and trees upto 30 cm girth, all cost of excavation of earth in all kinds of soil, loading, transporting, unloading, stacking, placing the same or making embankments, rough dressing etc. including all lifts, as directed by the Engineer-in-charge.	200.00	cum	₹ 138.90	Rupees one hundred thirty eight and paise ninety only	₹ 27,780.00
9	Extra rate in Sl. No. 8 above for each additional lead of 500 metre or part there of beyond the initial lead of 500 metre. NB:- This item is applicable only where the track/ tractors are not accessible at site. 3 (three) Extra Lead	0.00		(₹ 20.70 x 3) =		
		200.00	cum	₹ 62.10	Rupees sixty two and paise ten only	₹ 12,420.00
10	SUPPLY OF LABOUR : Mazdoor	72.00	Per Day	₹ 206.00	Rupees two hundred six only	₹ 14,832.00
11	Supplying 500 C. P. Incandescent lamp (i.e. Petromax daylight, Hasag etc.) on hire basis for 10 hours including supply of necessary fuel etc. complete.	24.00	each	₹ 134.40	Rupees one hundred thirty four and paise forty only	₹ 3,226.00
Total Amount put to Tender in figure =						₹ 2,24,949.00
Total Amount put to Tender in word :						Rupees Two lakh twenty four thousand nine hundred and forty nine only


 Executive Engineer
 West Midnapore Division
 Irrigation & Waterways Dte.
 Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

NIT NO- WBIW/EE/WMD/NIT-08 of 2017-18

SI. No. 30

Schedule of Quantity, Unit, Rate and Amount for the work, "Flood Precautionary Measure (FPM) of Chetua Circuit Embankment from Ch. 9.00 Km to 22.00 Km along R/B of River Rupnarayan in c/w monsoon- 2017 in Mouzas- Harispur, Shyamsunderpur, Jotkanuramgarh, Ranichack & Benal in Block- Ghatal & Daspur-II, Dist. Paschim Medinipur under Ghatal Section of Ghatal Irrigation Sub-Division under West Midnapore Division."


Amount put to Tender : ₹ 2,39,117.00

Earnest Money : ₹ 4,782.00

Time allowed for Completion : 150 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	3120.00	sqm	₹ 7.70	Rupees seven and paise seventy only	₹ 24,024.00
2	Supplying, dressing and stacking at site bamboo pins (diametre to be measured at mid length (a) Above 5 cm to 7.50 cm diametre.	1560.00	m	₹ 23.60	Rupees twenty three and paise sixty only	₹ 36,816.00
3	Driving bamboo pins of average 5 cm to 7.5 cm diametre (payment will be made for driven length only) (i) Where boats are not necessary	1040.00	m	₹ 6.30	Rupees six and paise thirty only	₹ 6,552.00
4	Supplying, fitting, fixing with iron nails, half split bamboo walling pieces. (Diametre of bamboo not less than 5 cm, to be measured at mid length)	364.00	m	₹ 19.30	Rupees nineteen and paise thirty only	₹ 7,025.00
5	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	3071.50	each	₹ 5.00	Rupees five only	₹ 15,358.00
6	Labpur charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge.	3071.50	each	₹ 6.30	Rupees six and paise thirty only	₹ 19,350.00
7	Extra rate in Sl. No. 6 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres.	0.00		(₹ 2.30 x 5) =	Rupees eleven three and paise	
	5 (five) Extra Lead	3071.50	each	₹ 11.50	fifty only	₹ 35,322.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
8	Earthwork, transporting the earth by manually operated thela/ van/ ricksaw etc, beyond the lead of 150 metres and upto 500 metre including removal of jungle and trees upto 30 cm girth, all cost of excavation of earth in all kinds of soil, loading, transporting, unloading, stacking, placing the same or making embankments, rough dressing etc. including all lifts, as directed by the Engineer-in-charge.	325.00	cum	₹ 138.90	Rupees one hundred thirty eight and paise ninety only	₹ 45,143.00
9	Extra rate in Sl. No. 8 above for each additional lead of 500 metre or part there of beyond the initial lead of 500 metre. NB:- This item is applicable only where the track/ tractors are not accessible at site. 3 (three) Extra Lead	0.00		(₹ 20.70 x 3) =		
		325.00	cum	₹ 62.10	Rupees sixty two and paise ten only	₹ 20,183.00
10	SUPPLY OF LABOUR : Mazdoor	117.00	Per Day	₹ 206.00	Rupees two hundred six only	₹ 24,102.00
11	Supplying 500 C. P. incandescent lamp (i.e. Petromax daylight, Hasag etc.) on hire basis for 10 hours including supply of necessary fuel etc. complete.	39.00	each	₹ 134.40	Rupees one hundred thirty four and paise forty only	₹ 5,242.00
Total Amount put to Tender in figure =						₹ 2,39,117.00
Total Amount put to Tender in word :						Rupees Two lakh thirty nine thousand one hundred seventeen only


 Executive Engineer
 West Midnapore Division
 Irrigation & Waterways Dte.
 Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)