

Issued to:

Sub-Divisional Officer
K.C. Sub-Division No. II
Amlagora, Paschim Medinipur

Schedule for the work "Irrigation Precautionary Measure for Garbeta Branch Canal from Ch.51.00 to Ch.976.00 in connection with Rabi Irrigation 2017-18(1st, 2nd & 3rd watering) under Adalia, Ukhla (South) & Ukhla (North) Section of K.C. Sub Divn No.II during 2017-18".

Sl. No.	Description of items	Quantity	Unit	Rate	Amount
1	Ref :- Item No. 19(b),Page no.13 of KC/SOR Supplying empty cement polythene bags in good condition including stacking and cost of carriage to site complete(Capicity 50 Kg).	300.00	Each	6.00	1,800.00
2	Ref :- Item No. 20,Page no.13 of KC/SOR Labour charges for filling gunny bags / polythene bags with all kinds of earth or sand wet or dry including sewing mouth and stacking within a lead of 150 Metres and all lifts	300.00	Each	6.00	1,800.00
3	Ref :- Item No. 22,Page no.13 of KC/SOR Labour charges for dumping filled up gunny bags / polythene bags in standing or flowing water with or without boats inclusive of placing in position with all leads and lifts complete as per direction of the Engineer-in-charge (Filled	300.00	Each	3.00	900.00
4	Ref :- Item No.1,Page No.1 of KC/SOR Earth work in excavation in the canals/drainage channels/borrow pits/River bed/Slope of bank as noted below as per designed section & throwing the spoils in layer of 23cm for making banks as per profile or to deposit the same in any other place as wanted by the Engineer - in - charge within an initial lead of 30 metre and initial lift of 2.00 metre including breaking clods,rough dressing etc. complete as per direction of the Engineer - in - charge. a)Local soil/soil mixed with moorum or kankar/silt, dry or moist/slushy silt/sticky soil.	320.00	Cum	77.00	24,640.00
5	Ref :- Item No.11,Page No. 12 of KC/SOR Supply dressing and stacking at site bamboo pins (Dia to be measured at half half length). (a) Above 6 Cm dia upto 7.50 cm. dia.	320.00	Metre	21.00	6,720.00
6	Ref :- Item No.12,Page No. 12 of KC/SOR Driving bamboo pins in standing & flowing water including scaffolding and driving appliances.	208.00	Metre	6.00	1,248.00
7	Ref :- Item No.13,Page No. 12 of KC/SOR Supplying fitting and fixing with iron nails or spikes half split bamboo walling piece (dia of bamboo not less than 6 cm.)	240.00	Metre	14.00	3,360.00
8	Ref :- Item No.7 a ,Page No. 2 of KC/SOR Cutting and removing ordinary thick or thorny jungles including clearing and depositing the same with all leads and lifts as per direction of the Engineer-in-Charge.	2743.00	SqMt	10.00	27,430.00
9	Ref :- Item No.23,Page No.XXII of Daily Labour Wages of KC/SOR Providing Unskilled Mazdoor (Male) for watching,Guarding of Crosss regulator Gates and other allied works as and when required.	468	No.	170.50	79,794.00
Total					147,692.00

(One lakh forty seven thousand six hundred and ninety two only)

Sub-Divisional Officer
Kangsabati Canal Sub-Division No. II
Amlagora, Paschim Medinipur

I/We do hereby agree to execute the above work @..... % Above/Low/At per than the Schedule of Rates attached herewith .

Signature of the Contractor(s)