



Government of West Bengal
Irrigation & Waterways Directorate
Office of the Executive Engineer
Kangsabati Canals Division No-IV
Midnapore, Paschim Medinipur.

BOQ

OFFLINE- N.I.T No – WBIW / EE / KCD-IV/NIT- 07/2017-18

M/R to L/B of Canal MBC from Ch. 935.00 to 940.00 and ch.1005.00 to ch.1010.00 of KCSD-XIV under KCD-IV

SL NO.	Description of Item	QTY	UNIT	Rate as per SoR Rs.	GST(%) Rs	Cess(@ 1%) Rs.	Rate including Cess Rs.	AMOUNT (Rs.)
1	[Ref : USoR Page-C-6, Item No.- 1.23] Cutting uprooting and clearing jungles including shrubs, water weeds, bushes, trees, plants, upto 30 cm. girth including removing as directed by Engineer-in-charge.	6000.00	Sqm.	5.00	Nil	0.05	5.05	30300.00
2	[Ref : USoR Page-C-1, Item No.- 1.02] Earthwork in excavation in the canals / drainage channels / borrow pits / River bed / slope of bank as noted below as per designed section & throwing the spoils in layers of 25 cm. for making banks as per profile or to deposit the same in any other place within an initial lead of 30 metre and initial lift of 1.5 metre including breaking clods, rough dressing etc. complete as per direction of the Engineer-in-charge. (a) Ordinary soil / local soil / soil mixed with moorum or kankar / silt, dry or moist / slushy silt / sticky soil.	3696.16	Cum	109.00	Nil	1.09	110.09	406910.25
3	[Ref : USoR Page-C-1, Item No.- 1.04] Extra rate over Item No. 1 for all kinds of soil for every additional lead of 30 metres or part thereof beyond the initial lead of 30 metres. One extra lead.	2690.32	Cum	12.00	Nil	0.12	12.12	32606.68
4	[Ref : USoR Page-C-2, Item No.- 1.05] Extra rate over Item No .1 for all kinds of soil for every additional lift of 1.50 metre or part thereof beyond the initial lift of 1.50 metre. One extra lift	2351.00	Cum	12.00	Nil	0.12	12.12	28494.12
Total								498311.05
Say								498311.00
Total amount including GST and Cess =								498311.00
Note	As there is no item, other than jungle and earthwork related items, no GST will be applicable in regard to this estimate. As such, GST rate is considered as '0%'.							

Executive Engineer
Kangsabati Canals Division No.-IV
Bidhannagar, Midnapore

I / We do hereby agree to execute the above work @ % (in figure)
..... (in words) percent **above /at par / below** than the schedule of rates. I shall abide by all terms and conditions laid down in the NIT & WBF 2911

(Signature of the Contractor)