



GOVERNMENT OF WEST BENGAL
Irrigation and Waterways Directorate
Office of the Executive Engineer
Teesta Canal Division No-I
Islampur, Uttar Dinajpur
Ph.03526-255074.

Tender Reference No. **WBIW/EE/TCD-I/e-NIT-04/2018-19**

Tender ID: 2018_IWD_191394_2

Name of the work: "Restoration of bituminous inspection path by repairing of Sub-base and pot holes of the Inspection Path of MMC in different places in between Ch. 20.050 km to Ch 21.275 km (Right Bank), and Ch.21.275 km to Ch.26.089 km (Left Bank). In P.S . & Block Chopra, Dist : Uttar Dinajpur, Under Teesta Canal Division No-I."

1st Addenda/Corrigendum

Last date for submission of e-bid has been extended due to unavoidable circumstances .

Bid submission last date & time: **26.10.2018** upto **16.00 Hrs** instead of **11.10.2018** at **14.30 Hrs**.


BOQ Item No.	In Place of	Please read	Remarks
3.2	Unit of Item no 3.2 of above work BOQ is "sqm"	Unit of Item no 3.2 of above work BOQ is "Cum."	Except Unit of the item, all other columns remain unchanged.
6	Hire and labour charges for shuttering with centering and necessary staging up to 4 m using approved st.c.ut props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams and columns, lintels curved or straight including fitting, fixing and striking out after completion of works (up to roof of ground floor). a) 25 mm to 30 mm thick wooden shuttering as per decision & direction of Engineer-In-Charge.	Open-Graded Premix Surfacing using Bituminous (Viscosity grade Paving Bitumen / Modified bitumen) Binder and Mobile Hot Mix Plant (Light Duty) Providing, laying and rolling of Open - graded premix surfacing of 20 mm thickness composed of 13.2 mm (@ 0.018 m ³ per m ²) and 11.2 mm (@ 0.009 m ³ per m ²) size stone aggregates, including thoroughly cleaning of the surface, screening, cleaning and pre-heating stone chips and fully pre-coating the same either using viscosity grade paving bitumen or cut-back or emulsion, carrying the mixture by any suitable arrangements, laying the mixture uniformly over the surface, including line, grade and level to serve as wearing course on a previously prepared base, including mixing in Mobile Hot Mix Plant (Light Duty) and thoroughly rolling with a smooth wheeled roller 8-10 tonne capacity, finished to required level and grades including the cost and carriage of stone chips and matrix, heating the matrix, preheating the aggregates to required temperature and including the hire charges of Mobile Hot Mix Plant (Light Duty) and other machinery, pay of operators, cost of fuel and lubricants etc. complete to be followed by seal coat of either Type A or Type B as per Technical Specification Clause 508 for Rural Roads of MORD.	Except Description of the item, all other columns remain unchanged.

All other terms and condition remain unchanged.


Executive Engineer
Teesta Canal Division No-I
Islampur, Uttar Dinajpur.

Copy submitted for favour of kind information and taking necessary action for wide circulation to the:-

01.	Chief Engineer, Teesta Barrage Project, Teesta Sech Bhawan, 2 nd Mile Sevoke Road, Siliguri.
02.	Superintending Engineer, Mahananda Barrage Circle, Tinbatti. Siliguri.
03.	Sub-Divisional Officer, Islampur Sub-Division, Islampur.
04.	The Chairman, Islampur Municipality, Islampur.
05.	Sub-Divisional Officer, Teesta Canal Sub-Division No-III, Haptiagachh.
06.	Divisional Accounts Officer, Grade- II of this office.
07.	Notice Board.


Executive Engineer
Teesta Canal Division No-I,
Islampur, U/Dinajpur