

Government of West Bengal Irrigation & Waterways Directorate Office of the Sub-Divisional Officer Kangsabati Canals Sub-Division No IV Sarenga, Bankura.

Memo No : 481 Date : 23.09.2019

NOTICE INVITNG TENDER

(For works of estimated cost up to Rs 5.00 lakh)
NOTICE INVITING TENDER NO: - WBIW/SDO/KCSD-IV/NIT 05 OF 2019-2020.

1.Invitation.

Separate sealed Tenders in printed forms are hereby invited by **the Sub-Divisional Officer**, **Kangsabati Canals Sub-Division No IV**, **Sarenga**, **Bankura** on behalf of the Governor of the State of West Bengal in West Bengal Form No.2911 for the works as per list attached herewith, from the eligible bonafide, reliable resourceful Contractors having sufficient experiences in execution of similar type of works.

2. Details of Work: -AS PER LIST ATTACHED IN PAGE 9&10 OF THIS NIT.

3.Time Schedule of Tender procedure:-

iv)	Date & Time and place of opening of Tenders.	01.10.2019	After 15:30hrs.	i)S.D.O/ K.C.Sub- Divn.No. IV, Sarenga.
iii)	Last Date & Time and Place for dropping Tender paper.	01.10.2019	Up to 15:00hrs.	i)S.D.O/ K.C.Sub- Divn.No. IV, Sarenga
ii)	Last Date & Time and Place for issue of authenticated Tender papers.	30.09.2019	Up to 17:00 hrs.	i)S.D.O/ K.C.Sub- Divn.No. IV, Sarenga
i)	Last Date & Time and Place for application(Application must be supported with self signed NIT, 2911 form, BOQ download from departmental website – www.wbiwd.gov.in along with all relevant papers and credentials i.e PAN, GSTIN Registration, Trade license, work credentials etc.	30.09.2019	Up to 15:00 hrs	i)S.D.O/ K.C.Sub- Divn.No. IV, Sarenga.

- **4.**<u>Tender documents</u>: The Tender documents shall consist of the followings and other relevant particulars may be seen by the intending Tenders or by their duly authorized representatives during office hours between 11.00 AM and 4 PM on every working day, till the last date of issue of the Tender Forms in the office of the undersigned: -a) Notice Inviting Tender. (download from departmental website www.wbiwd.gov.in)
- b) W.B.F. No. 2911 (download from departmental website www.wbiwd.gov.in)
- c) Price schedule i.e BOQ (download from departmental website www.wbiwd.gov.in)
- d) Plans and Drawings where necessary (these will not be required to be submitted with the tenders but this will form part of the tender documents at the time of executing the agreement after acceptance)
- * Kindly note that details will be available in the of the office of the undersigned on any working day in between 11-00 AM and 4-00 PM.

Sd/-Sub-Divisional Officer Kangsabati Canals Sub-Division No IV Sarenga, Bankura.

ELIGIBILITY CRITERIA OF THE TENDERER PARTICIPATING IN THE TENDERS INCLUDING SOME TERMS AND CONDITONS

5. Eligibility for participation

Bonafide outside Contractors, Registered Engineers Cooperative Societies, Consortiums and Partnership Firms registered with the State Government and contractors of equivalent Grade / Class registered with Central Government / MES / Railways for execution of civil works are eligible to participate.

(In case of consortiums, maximum number of constituents shall be restricted to 5 (Five) and each constituent must have at least some credential towards contracting business. Individual constituent of a consortium cannot be another consortium.)

6.. Participation in more than one work

Any contractor can submit tenders for a maximum of 50% of the total number of works (rounded up to next higher integer) published in any particular NIT, depending on his credential and financial capability, details of which are given later

7. <u>Application for purchase of Tender forms</u>: - a) Intending Tender's have to be submitted application duly enclosed with the self attested copies of the following documents addressed to the Sub-Divisional Officer, Kangsabati Canals Sub-Division No IV, Sarenga, Bankura.

b) Copies of documents;

GSTIN Registration Certificate, P.T. (Professional Tax) Clearance Certificate and PAN, Trade License valid at least up to the date of opening of Tenders should be considered.

c)Credentials

- i) Completion certificate/Payment certificate(s) for one single similar work as per categorization of works appended in list of works to an extent of **at least 50%** of the value of the work for which tender is desired, executed within last 5 (five) financial years (to be determined from the actual year of completion, considering current financial year as year 1 ii) List of Tools & Plants, Machinery, and Equipments etc. in possession.
- iii) List of Technical & Non-Technical staff.
- iv) List of works in progress with their respective value.
- v) Eligibility certificate/N.O.C. issued by the A.R.C.S.(for Engineer's Co-operative only)
- vi) A Statement showing number and value of works presently under execution by the Tenderer under the Irrigation & Waterways Department and other Govt. Department/Organizations ..
- vii) Declaration by the applicant to the effect that there is no other applications for Tender Paper for work in the N.I.T. in which he/she/they has/have common interests and in that case intending Tenderer has to disclose his/her name(s) and style of another firm/individuals (where he is also officiating) in the application for issuing Tender forms failing which the decision of the committee regarding the matter will be final and binding upon all.
- viii) Declaration by the contractor to the effect that he/they has/have no near relative is posted in any offices under the circle which intends to submit tender. In case of near relative posted in any offices under the circle, he/they will not be permitted to Tender for works in the circle of the Superintending Engineer.
- x) Completion Certificate of work executed in other Departments of State Government or organizations, like Public Works & Public Works(Roads) Department, Public Health Engineering Department, Sundarban Affairs Department and various other State Govt. Departments,

Zilla Parishads, West Bengal Housing Infrastructure Development Corporation Limited (WBHIDCO),

West Bengal State Electricity Distribution Company Limited (WBSEDCL), Kolkata Metropolitan Development Authority (KMDA), Kolkata Metropolitan Water Sanitation Authority (KMW&SA), Kolkata Municipal Corporation (KMC), Hooghly River Bridge Commissioner (HRBC) Engineering Departments of Central Government and Organization, like Farakka Barrage Project (FBP) Authority, Railways, Kolkata Port Trust (KPT), and companies owned or managed by the State Government, i.e Mackintosh Burn Ltd., Westinghouse Saxby Farmer Limited & Britannia Engineering Ltd. May also be considered. Such Completion Certificates are to be issued by an officer not below the rank of Executive Engineer/Divisional Engineer/District Engineer/Project Manager of other state/Central Govt. Departments/Organizations; authorised signatories of CC for Panchayat Samities and Municipalities shall be BDO & Ex-officio Executive Officer and Secretary or equivalent administrative officers respectively. Such certificates are further to be countersigned by immediate superior authority of the issuing Authority for all cases other than direct/State/Central Govt. Department and Railways.

8. Scope of disqualification for issuing Tender Forms: -

Due to any one of the followings, the Tender Paper may not be issued to the applicant (Contractors)

- i) Delay submission of application (after expiry of the schedule Time)
- ii) Insufficient and improper documents submitted with the applications.
- iii) Non-submission of completion, payment certificate properly.
- iv) Old completion certificate and payment certificate.
- v) Without signature of the applicant and serially numbered of the submitted documents.
- VI) Non-submission of copies of Partnership Deed and Firm Registration Certificate from the Registrar of Firms, West Bengal.
- vii) Valid N.O.C. issued by A.R.C.S. of the concern District (In case of un-employed Engineers Co-operative Societies Ltd.)
- viii) Bank Solvency Certificate valid during a year up to 30% of the value of the work
- ix) Submission of loose application with the documents excepting booklet or constrict Stitching.
- **9.** <u>Fulfillment of Criteria and issue of Tender Paper</u>:-All the above as stated under Para 7(a),(b),& (c) and Para (8) (i) to (ix) are to be fulfilled properly, pending fulfilment of which Tender Forms may not be issued.
- 10. <u>Order for issue of Tender forms: -</u> The application of the intending tender along with the all documents so received by the office of the undersigned will be verified by the office of the undersigned and after the decision of the undersigned for issuance will be final & bindings.

11. Not satisfied with the decision of the committee for issuing Tender Paper: -Intending

Tenders not satisfied with the decision of the Tender paper issuing authority may prefer an appeal to the next superior officer. Concerned Superintending Engineer will be the Appellate authority for the disputed tenders. Necessary communication regarding his appeal to the Appellate Authority must be brought to the Notice of such Authority within Two working days after the date of issue of Tender Paper and copy of such communication should also be submitted to the tender paper issuing Authority within the same period, failing which no such appeal will be entertained.

12. <u>Purchase of Tender forms</u>:- All the Tender documents downloaded by the applicants himself and submitted the same with the application. The said Tender documents. will be issued to the Tenderer from the office of the Sub-Divisional Officer, Kangsabati Canals Sub-Division No IV, Sarenga, Bankura.

free of cost, where he/they have got permission. The intending Tenders are requested to present themselves personally or send their authorized representative to that office to receive the tender form within the time schedule.

13.Inspection to Site by the intending Tenderer before submitting Tender:-Before submitting any Tender, the intending Tenderers should make himself/themselves acquainted thoroughly with the local conditions prevailing, by actual inspection of the site and take in to considerations all factors and difficulties likely to be involved in the execution of work in all aspects including transportation of materials, communication facilities, climate conditions, nature of soil, availability of local laborers and market rate prevailing in the locality etc. as no claim whatsoever will be entertained on these accounts afterward. In this connection the intending Tenderers may contact the office of the undersigned up to last date of issue of Tender Forms between 11.30 hours and 16.30 hours on any working day.

14. Earnest Money: - Earnest Money & Security Deposit: - In partial modification of Notification No. 03-W dated 18th January 2011 of the Secretary to the Govt. of West Bengal, Irrigation & Waterways Directorate communicated by the Deputy Secretary to the Govt. of West

Bengal, Irrigation & Waterways Directorate vide Memo. No. 89(6)-IB/IW/O/1B-Misc-12/2007dated 18th January 2011;sub rule229(iii) vide memo no:- 08/1(6)-IB dt. 30.04.2013 the following provisions have been made in different para's and that should be abided by the tender.

a)i) <u>DEPOSIT OF EARNEST MONEY</u>:- An Earnest Money amounting to 2% of the estimated cost put to tender so long as the estimated cost put to Tender.

ii)<u>DEPOSIT OF EARNEST MONEY & SECURITY DEOPSIT IN CASE OF UNEMPLOYED ENGINEERSCO-OPERATIVE SOCIETIES AND LABOUR CO-OPERATIVE SOCIETIES:-</u>

Both the above Co-operative Societies will have to be deposited the earnest money and Security Deposit as per the Notification No. 03-W dated 18th January 2011 of the Secretary to the Govt. of West Bengal, Irrigation & Waterways Directorate communicated by the Deputy Secretary to the Govt. of West Bengal, Irrigation & Waterways Directorate.

- c) DEDUCTION OF SECURITY MONEY FROM THE PROGRESSIVE BILL::-Earnest money already deposited during the Tender shall be converted as a part of security money and additional security shall be deducted from the progressive bills at 8% or such amount from each such bill, so that the total deduction together with the 2% E.M.D constitutes 10% of the tendered value of work as actually done.
- d)NO FURTHER DEDUCTION SECURITY MONEY FROM THE PROGRESSIVE BILL: In partial modification of sub-rule 231(b) enumerated in this Departmental Notification No-03-W Dt. 18 than 2011, such Tenders may also be permitted to deposit further security so as to make total 10% of the Tendered amount to avail the facility of no further deduction from the progressive bills, subject to the condition laid down in 231(c) contained in the above said notification
- e)SECURITY DEPOSIT FOR EXCESS WORK:-In Para (9),in case of excess works over the tendered amount, additional security is to be deposited for the amount of such excess beyond the tendered amount as per prescribed rate, before payment of final bill in case contractors opting for paying advance security and receiving payment against progressive bills without any deduction.
- f) SHAPE OF EARNEST MONEY:- In Para (11), **Demand Draft, Banker's Cheque, and Treasury Challan**, **Deposit at Call Receipt (D.C.R.)**of Scheduled Banks guaranteed by the Reserve Bank of India and payable at Midnapore may be accepted as earnest money and/ or security Deposit.

In terms of Memo. No. 108-IB/IW/O/IB-Misc-38/201(Part) dated 16.11.2011 of Deputy Secretary to the Govt. of West Bengal, I&W.D, the original copies of the Demand Draft/Banker's Cheque/Deposit at Call Receipts (DCR), towards Earnest Money Deposit (EMD) in favour of

Executive Engineer, Kangsabati Canals Division No I,Amlagora, Paschim Medinipur issued from any of the following Schedule Banks Payable at Midnapore should be dropped with the tender. <u>EMD issued from any bank other than the</u> schedule banks will liable to rejection of the Tender.

The list of Scheduled Banks in India (Public Sector & Private Sector) constitute those banks which have been included in the Second Schedule of Reserve Bank of India (RBI) Act, 1934. RBI in turn includes only those banks in this schedule which satisfy the criteria laid down vide section 42 (6) (a) of the Act are appended below.

• □ Scheduled Banks in India (Public Sector):

1)State Bank of India 2)State Bank of Bikaner and Jaipur3)State Bank of Hyderabad 4)State Bank of Indore5) State Bank of Mysore 6)State Bank of Saurashtra7) State Bank of Travancore 8)Andhra Bank 9)Allahabad Bank10) Bank of Baroda11) Bank of India12) Bank of Maharashtra13) Canara Bank14) Central Bank of India 15)Corporation Bank 16)Dena Bank 17)Indian Overseas Bank 18)Indian Bank 19)Oriental Bank of Commerce 20)Punjab National Bank 21)Punjab and Sind Bank 22)Syndicate Bank 23)Union Bank of India24)United Bank of India25) UCO Bank26)Vijay Bank.

•Scheduled Banks in India (Private Sector):

1)ING Vysya Bank Ltd 2)Axis Bank Ltd 3) Indusind Bank Ltd 4)ICICI Bank Ltd 5)South Indian Bank 6)HDFC Bank Ltd 7)Centurion Bank Ltd8) Bank of Punjab Ltd9)IDBI Bank Ltd.

g)ADJUSTMENT OF EARNEST MONEY:-No earnest money previously deposited for other works will be considered. Tender without or improper earnest money will forthwith be treated as 'INFORMAL'

h)<u>EXEMPTION OF EARNEST MONEY AND LIMITATION OF SECURITY DEPOSIT</u>:- Provision contained in clause no 7.4.2(iv) will not be applicable for Mackintosh Burn Ltd. ,Westing house

Saxby Farmers Ltd., & Britannia Engineering Ltd. which they previously enjoyed as per G.O. No.10500-F dated 19.11.2004 and subsequently extended vide G.O. No. 1110-F dated 10th

February, 2006. They can participate in all the serials in a particular N.I.T, subject to fulfilment of other credential criteria specified in 7.4.2(ii) to 7.4.2(iii) vide memo no:-46(5)-IB dt. 11th June- 2012, of Deputy Secretary to the Govt. of west Bengal.

- 15. <u>Dropping of Tenders:- All Tender documents should be submitted in sealed envelope mentioning the NIT No.</u>, Name & SI. No. of works,name & address of the Tenderer on the body of the said sealed envelope, will be dropped in the offices given below- on the schedule Date & Time and place as stated in Para (3) above and or the changing schedule made vide issuing necessary CORRIGENDUM.
- i) Office of the Sub-Divisional Officer, Kangsabati Canals Sub- Division No IV, Sarenga, Bankura.
- **16.** Opening of Tenders: -i) All the intending Tenderers or their authorised representative may present during opening of Tender.
- ii) In terms of Para 221(1), once the tenders are opened, no tenderer should be allowed to offer fresh quotations unless each of the tenderer is given equal opportunity. In case where the later steps taken, if time permits, fresh tenders may be invited so as to leave no room for any compliant or grievance whatsoever and,
- iii) In terms of Para 221(2), when the rates quoted in response to invitation of competitive tenders are considered high and fresh invitation of tenders cannot be taken recourse to either for want of time or because of no likelihood of getting more favourable rates and negotiations with contractors are considered necessary for obtaining rates lower than those received in response to the invitation of competitive tenders, negotiations should be made with all the contractors who quoted rates in response to the invitation of tenders, and not with the lowest tenderer alone.
- 17. Acceptance of Tender: in terms of NOTIFICATION No. 01/IW dated 19/07/2012 of Secretary to the Govt. of West Bengal, acceptance of the tender will rest with the Competent Authority who does not bind himself to accept the lowest tender and reserves the right to reject in any or all the tenders received and to distribute work between two or more than two Tenderers without assigning any reason thereof.

OTHER TERMS & CONDITIONS.

- **18.** In Terms of vide memo no:-46(5)-IB dt. 11th june-2012,of Deputy Secretary to the Govt. of west Bengal, Mackintosh Burn Ltd., Britannia Engineering Ltd. And Warehouse Saxby Farmer Ltd. Will not enjoy 10% preference in rate for the purpose of selection.
- **19.** Any suppression/misrepresentation of fact will automatically debar the applicant for participating in any Tender under the Division/Circle for at least 3(Three) years from the date of detection, in addition to such other penal action as the Government may deem proper.
- **20.** Intending Tenderers should be equipped with plants, machinery equipment and well point pumping machinery complete with all accessories as required for the work as the department may not be in a position to issue such plants & machinery. They must submit a list of such plants; machinery and equipments in their possession for necessary documentary evidence are to be produced.

- 21. If required, the intending Tenderers have to be produced Bank solvency certificate of an amount equal to 30% of the estimated amount of the work.
- **22.** Documents submitted along with the application should invariably be in the name of the applicant firm/ Individuals. In terms of Memo. No. 185/JS(W)/IA-11C-9(75)/09 dated 09.06.09 of the Secretary to the Govt. of West Bengal , I&W.D, Joint venture of Firms constituted and duly registered with the appropriate authority will be considered for issuance of Tender Papers.
- **23.** All pages of the documents submitted with the application shall be signed with signature by the applicant and also be serially numbered as 1/10.2/10,3/10.....10/10
- **24.** Copies of Partnership Deed and Firm Registration duly self-attested shall invariably be submitted with the application by a partnership firm.
- **25.** Tenderers should quote their rates both figures and words in terms of overall percentage, "below" or "above" or "at par" with the price schedule both in the 2nd page of W.B.F 2911 (ii) and the last page of price schedule.
- 26. Any tender containing over writing is liable to be rejected.
- **27.** All corrections are to be attested under the dated signature of the Tenderer.
- **28.** When a Tenderer signs his Tender in an Indian Language, the Total amount tendered should also be written in the same language. In case of illiterate Tenderer, the rates tendered should be attested by an witness.
- **29.** The Tenderer who will sign on behalf of a Company or Firm, must produce the registered documents within 3(Three) days from the date of opening the tender, if not submitted with the tender application or with the Tender documents) in support of his competency to enter in to an Agreement on behalf of the Company or the Firm under the Indian Companies or Partnership Act, failing which the tender will not be considered and the deposited Earnest Money will be forfeited.
- **30.**The rate quoted by in the tender form will be final and no subsequent modification in the rates will be entertained even it is done with any letter or other instrument submitted before sealing/closing the Tender box.
- **31.** Any superfluous conditional tender, which does not full fill any of the above conditions, and is incomplete in any respect, is liable to be rejected.
- **32.** VAT, Sales Tax, Royalty, and all other statutory Levy/Cess etc. will have to borne by the Contractor. The engaged Contractors need to get registered under BOCW (RECS) Act and shall have to contribute towards a fund namely "**The West Bengal Building & other Construction worker's Welfare Fund**" @1.00%(one point zero zero percent) of the total amount of the work value which will be deducted directly from the bill value and remitted as per requirement of the said Act as per Finance Department Notification No. 853-F dated 01.02.06..
- **33.** Canvassing in connection with the tenders is strictly prohibited and the tenders submitted by a tenderer who take resort to canvassing will be liable to rejection.
- **34.** Incomplete and illegible tender will be invalidated. All corrections in the tender should be signed with dated initial by the contractors before submission of tender and each page of the tender should also be signed and dated by the contractor.
- **35.** The contractor has to obtain the Labour license from the office of the Joint Labour Commissioner of the concerned District in which the location/site of the work falls, under the provision of W.B. Contract Labour (Regulation & Abolition) rules, 1972 and a copy of the license has to be submitted to this office for information & record, failing which the undersigned will in no case be hold responsible for any action taken by the Labour Department. The undersigned being the '**Principal Employer**' for the work, will however issue a certificate in specified pro forma of Labour Department in form V for doing the needful by the authority of labour Department.
- **36.**As per rule, the intending Tenderer has to disclosed his/their name (s) & style of another firm /individuals (where he is also officiating) in the application for issuing tender forms failing which the decision of the undersigned regarding the matter will be final & binding upon all.

- **37.** The Tenderer should submit a statement at the time of submission of his tender showing the Technical Staff to be engaged for the work, with their Technical qualifications, failing which the tender may be liable to rejection.
- **38.** The Tenderer will have to, if so desired by the Tender Accepting Authority, submit his analysis to justify the rate quoted by him/them.
- **39.**The Tenders will be opened, as specified in the list of works, in presence of the Participating Tenderers or their duly authorized representatives, who may be present at the time of opening and who may also put their signatures in the Tender opening Register.
- **40.**The successful Tenderer will have to execute the duplicate/triplicate/quadruplicate(Plain Paper)copies of his /their tender which will have to be obtained by additional cash payment in the office of the Executive Engineer (I&W Dte.), Kangsabati Canals Division No I,Amlagora, Paschim Medinipur., within 7(seven) days from the date of receipt of the intimation of acceptance of his tender failing which the Earnest Money shall forthwith stand forfeited in favour of the Government and the communication of acceptance of the tender shall automatically stand cancelled.
- **41.** If any Tenderer withdraws his tender before its acceptance or refuses/fails to convert it in to a contract within a reasonable time, without giving any satisfactory explanation for such withdrawal/refusal/failure, he shall be disqualified for submitting any tender in this Division/Circle for a period of 1(one) year and his/their case will be referred to the Government for order as to what further action will be taken against him/them.
- **42.** Materials such as cement, M.S. Rod, R.C.C. Hume Pipes, M.S. sheet Piles, etc. if available in stock, will be issued by the Department to the Contractor for the work as per issue rate fixed by the Engineer-in-charge. Place of issue materials as mentioned in Page 11 of W.B.F. 2911(ii) or in a separate sheet attached with the Tender documents to be supplied departmentally to the Contractor is furnished with the Tender documents for the work. Any other materials not listed therein, if supplied by the department, the issue rate for such materials will be fixed by the Engineer-in-charge.
- **43.** Hire charges for Tools & Plants Machinery, if issued departmentally, will be recovered from the contractor at such rate as will be fixed by the Engineer-in-charge. The period of hire charges of all Tools & plants Machinery issued from the Government go-down will be counted from the date of their issuance from the go-down and up to the date of return in to the same go- down and the hire charges will be recovered from the contractor accordingly. All Tools & plants Machinery issued to the contractor must be returned in good condition. In the case of any damages, the cost of repair to such damage or replacement will be recovered from the contractor.
- **44.** In the following case a tender may be declared **'INFORMAL**' and unacceptable.
- a) Correction, alterations, additions, etc. if not attested by the tenderer.
- b) (i) Earnest money in form of N.S.C./Government Security etc. not held by the Tenderer and not properly pledged.
- (ii) Earnest Money in the form of D.C.R/Demand Draft, etc. which are short deposited with interest bearing and/ornot deposited in favour of the **Executive Engineer**, **Kangsabati Canals Division No I,Amlagora**, **Paschim Medinipur** in proper shape.
- c) If, the all pages of the Tender documents are not signed by the Tenderer.
- d) (i) If, the Tender is not submitted in a cover properly sealed.
- (ii) If, the name of the work with N.I.T. No. & Serial No. of the work and the name of the addressee with the name of the Senders (Tenderers) are not exactly written on the envelope.
- **45.** a) In terms of the provision in Para 230 Page of I&W.D. Code Volume- 1 and at the same time provided in Para 150(3) of W.B. Works Departmental Manual, the Earnest Money of all the Tenderers other than the three lowest Tenderer should be refunded after the comparative statement has been prepared and checked and,
- (b) In terms of the provision laid down in Para 5 of the1st page of W.B.F. 2911. In case of rejected Tender it should be refunded within 10(ten) days from the date of decision.
- **46.** To verify the competency, capacity and financial stability of the intending Tenderers the Tender paper issuing authority may demand production of any necessary documents as it may deem necessary.

- **47.**As per G.O. No. 1627(8)/1A dated 26th November 2001 of Irrigation & Waterways Department, Government of West Bengal, Clause 25 of Tender Form No. 2911(ii) stand deleted in respect of contract of value less than 100.00 lakh.
- **48.** Normally Tender Paper for not more than one work in any one N.I.T. will be issued to an applicant, who may indicate the Serial No's. of the work in the order of priority. However, depending on response to various serials in the N.I.T., Tender Paper issuing Authority may issue Tender Paper for any serial even though it may not be preferred by the applicant.
- **49.** Applicants permitted to purchase Tender form will have to be participated in the tender failing which he/.they may be suspended to participate in the next Tender.
- **50.** Tender may be cancelled in any stage without assigning any reason.
- **51.** Any discrepancies if found, in the documents/statement the tender shall be cancelled in the subsequent stage with imposition of lawful action for this act of submission of documents.
- **52.** Apart from all the above conditions and criteria the 'Past and Present' performance of the agencies will be considered while issuing tender papers.
- 53. Gross value of the bill shall be strictly restricted up to the Tender amount as per order no. 378(7)-IB dtd.6.02.2017
- **54.**The payment of R/A as well as Final Bill for the work will be made according to the availability of fund and claim due to delay in payment will not be entertained.
- **55.** Subletting of work is strictly prohibited & will be viewed seriously & disqualify the agency to participate in the next Tender.
- **56.** Canvassing in connection with Tender is strictly prohibited and the Tenders submitted by a Tenderer who will resort to canvassing will be liable to rejection.
- **57.** All specifications, Terms and conditions etc. of the printed schedule of rates of Mahananda Barrage Circle, Teesta Barrage Circle, Teesta Canal Circle, P.W.D., P.W.D. (Roads), Member (P.I. &D), & Member (Execution) N.B.F.C.C. will be applicable, unless otherwise specified.
- **58.**Apart form all the above, only in the interest of the Government, the committee may allowed purchasing Tender Forms to such agency/agencies who/they will fulfilled the other criteria and his/their Past or Present performance is/are satisfactory but his/their credentials in regards to completion and Payment certificates stand less than the requirement.
- **59.** All applicants willing to participate in the Tender must have to be appeared before a Tender document scrutiny committee for verification of original of the submitted documents. In case, the applicant or his authorized person not appeared before the tender documents scrutiny committee with the original documents in the schedule date and time as stated under para-3 (ii), the application will be disqualified for issuing tender form.
- 60. Tender forms will not be issued after due date and no tender forms will be sent by post/E-Mail/Fax etc.
- **61.** <u>Additional Performance Security</u>: The additional performance security shall be obtained from the successful L1 bidder, if the accepted bid value is below 20% of the estimated amount put to the tender.

The additional performance security shall be equal to 10% of the tendered amount i.e. the L1 bid price.

The additional performance security shall have to be submitted by the selected bidder after issuance of letter of acceptance/letter of invitation (LoA/LoI) and before award of contractor (AoC) in the form of "Bank Guarantee" of any Scheduled Bank,payable at Kolkata or / in West Bengal in proper format. If the bidder fails to submit the additional performance security within seven working days from the date of issuance of LoA/LoL, its earnest money deposit (EMD) will be summarily forfeited.

If the bidder fails to complete the work successfully, this additional performance security shall be forfeited at any time during the pendency of the contract period after serving suitable notice to the contractor/bidder agency.

Sub-Divisional Officer Kangsabati Canals Sub-Division No IV Sarenga, Bankura.

LIST OF WORKS

NIT NO: - WBIW/SDO/KCSD-IV/NIT 01 OF 2019-20 Vide Memo No-481, date-23/09/2019.

i)	Last Date & Time and Place for application(Application must be supported with self signed NIT, 2911 form, BOQ download from departmental website – www.wbiwd.gov.in along with all relevant papers and credentials i.e PAN, GSTIN Registration, Trade license, work credentials etc.	30.09.2019	Up to 15:00 hrs	i)S.D.O/ K.C.Sub-Divn.No. IV, Sarenga, Bankura.
ii)	Last Date & Time and Place for issue of authenticated Tender papers.	30.09.2019	Up to 17:00 hrs.	i)S.D.O/ K.C.Sub-Divn.No. IV, Sarenga, Bankura.
iii)	Last Date & Time and Place for dropping Tender paper.	01.10.2019	Up to 15:00hrs.	i)S.D.O/ K.C.Sub-Divn.No. IV, Sarenga, Bankura.
iv)	Date & Time and place of opening of Tenders.	01.10.2019	After 15:30hrs.	i)S.D.O/ K.C.Sub-Divn.No. IV, Sarenga, Bankura.

SI.No.	Name of Work	Estimated cost (value of work put to tender) (Rs)	Earnest money (Rs) (2% of the estimated cost put to tender)	Cost of Tender Docum ents (Rs.)	Time of completio n of the work	Source of fund	Eligibility of Contractors
1	M/R to North East side boundary wall at Pirargari section office under K.C. Sub Divn No.IV of K.C Division No-I."	1,13,508.00	2270.00	Nil	30 days	Non Plan	Bona fide agency having Credential of execution of similar nature of work of value 50% of the amount put to tender within the last 5 years
2	M/R to Silt Clerance of Dy. No4 of K.M.C(L) Inbetween Ch142.00 and ch168.00 under Hd. Qrt. Section of K.C. Sub Division NoIV Sarenga, under K.C Divn.NoI Amlagora Paschim Midnapur, during 2019-2020.	54,239.00	1085.00	Nil	10 days	Non Plan	Bona fide agency having Credential of execution of similar nature of work of value 50% of the amount put to tender within the last 5 years
3	M/R to Silt Clerance of Dy. No4 of K.M.C(L) Inbetween Ch168.50 and ch204.00 under Hd. Qrt. Section of K.C. Sub Division NoIV Sarenga, under K.C Divn.NoI Amlagora Paschim Midnapur, during 2019-2020.	61,290.00	1226.00	Nil	10 day	Non Plan	Bona fide agency having Credential of execution of similar nature of work of value 50% of the amount put to tender within the last 5 years
4	M/R to Cutting & removing Jungles in-between Ch257.00 and ch.290.00 (L/B & R/B) of K.M.C(L)and inbetween ch-106.00 &Ch-111.00, Ch-146.00& Ch-151.00, Ch-326.00 & Ch-332.00, Ch-432.00 & Ch-437.00 Of M.B.C under Hd. Qrt. Section of K.C. Sub Division NoIV Sarenga, under K.C Divn.NoI Amlagora Paschim Midnapur, during 2019-2020	46,159.00	923.00	Nil	10 day	Non Plan	Bona fide agency having Credential of execution of similar nature of work of value 50% of the amount put to tender within the last 5 years

5	Soil Investigation for Proposed C.C. Lining in different reaches of MBC under K.C Sub-Division No-IV, Sarenga uder K.C Division No-I, Amlagora, Paschim Medinipur.	2,37,525.00	4751.00	Nil	15 day	Non Plan	Bona fide agency having Credential of execution of similar nature of work of value 50% of the amount put to tender within the last 5 years
6	M/R to Silt Clerance of Mr C of Dy. No4 of K.M.C(L) Inbetween Ch 0.00 and ch30.00 under Hd. Qrt. Section of K.C. Sub Division NoIV Sarenga, under K.C Divn.NoI Amlagora Paschim Midnapur, during 2019-2020.	37,420.00	748.00	Nil	10 day	Non Plan	Bona fide agency having Credential of execution of similar nature of work of value 50% of the amount put to tender within the last 5 years
7	M/R to Silt Clerance of Sub- Minor A of Minor B of Dy. No4 of K.M.C(L) Inbetween Ch 168.50 and ch204.00 under Hd. Qrt. Section of K.C. Sub Division NoIV Sarenga, under K.C Divn.NoI Amlagora Paschim Midnapur, during 2019-2020	43,647.00	873.00	Nil	10 day	Non Plan	Bona fide agency having Credential of execution of similar nature of work of value 50% of the amount put to tender within the last 5 years
8	Soil Investigation for Proposed C.C. Lining in different reaches of Dy. No12, 12A & its minor of KMC(U) under K.C Sub-Division No-IV, Sarenga of K.C Division No-I, Amlagora, Paschim Medinipur	1,15,357.00	2307.00	Nil	10 day	Non Plan	Bona fide agency having Credential of execution of similar nature of work of value 50% of the amount put to tender within the last 5 years

Sd/-Sub-Divisional Officer Kangsabati Canals Sub-Division No IV Sarenga, Bankura.

FORM-6*

SPECIMEN FORMAT FOR THE BANK GUARNATEE FOR ADDITIOANAL PERFORMANCE SECURITY DEPOSIT

(*To be submitted only **if the bid price quoted by the bidder is below 20% of the estimated cost put to tender**, non submission within 7 working days from date of issuance of LOA/LOI will lead to rejection of selected bidder. Similar standard format issued by RBI approved Bank pledging Bank Guarantee of the required value and period in favour of Engineer-in-Charge is acceptable)

' '
To,
(Designation of Engineer-in-Charge)
(Office address of Engineer-in-Charge)
WHEREAS (name and address of Contractor) (hereafter called "the Contractor") had undertaken, in pursuance of Contract No: dated to execute (name of Contract and brief description of Works) (hereinafter called "the Contractor").
AND WHEREAS it has been stipulated by you in the said Contract that the Contractor shall furnish you with Bank Guarantee by a Scheduled commercial bank for the sum specified therein for 'ADDITIONA' PERFORMANCE SECURITY DEPOSIT' for compliance with his obligation in accordance with the Contract:
AND WHEREAS we (Indicate the name of the bank and branch) have agreed to give the Contractor such a Bank Guarantee:
NOW THEREFORE we ; (Indicate the name of bank and branch) hereby affirm that we are the Guarantor and responsible to you on behalf of the Contractor, upto a total of Rs. (amount of guarantee) (in words). We undertake to pay you, upon your first written demand and without cavil or argument, a sum within the limits of (amount of guarantee) as aforesaid without you needing to prove or to show grounds or reasons for your demand for the sum specified therein.
We (Indicate the name of the bank and branch) hereby waive the necessity of your demanding the said debt from the contractor before presenting us with the demand.
We (Indicate the name of the bank and branch) further agree to pay to you any money s demanded not withstanding any dispute or disputes raised by the contractor(s) in any suit or proceeding pending before any court or Tribunal relating thereto, our liability under this present absolute and unequivocal.
The payment/so made by us under this bond shall be a valid discharge of our liability for payment there under and the contractor(s) shall have no claim against us for making such payment.
We (Indicate the name of the bank and branch) further agree that no change or addition to or other modification of the terms of the Contract or of the works to be performed there under or of any of the contract documents which may be made between you and the contractor shall in any way release us from an liability under this guarantee, and we hereby waive notice of any such change, addition or modification.
We (Indicate the name of the bank and branch) lastly undertake not to revoke this guarante except with the previous consent of you in writing.

This guarantee shall be valid upto -----. It come into force with immediate effect and shall remain

in force and valid for a period upto the time of completion of the work under the stated contract plus

against this guarantee is restricted	d to Rs (Rs.	•) and u	anything mentioned above, our liability inless a claim in writing is lodged with use all our liabilities under this guarantee
Signed and sealed this	day of	20	at	
				SIGNED, SEALED AND DELIVERED
				For and on behalf of the BANK by:
				(Signature)
		(Designation	on)	
		(Code Num	nber)	
		(Address)		

NOTES:

i. The bank guarantee should contain the name, designation and code number of the officer(s) signing the guarantee

The address, telephone number and other details of the Head Office of the Bank as well as of issuing Branch (within West Bengal/AT PAR ANYWHERE IN INDIA only to be accepted) should be mentioned on the covering letter of issuing Branch.

Memo No: -481/1(30) Dated:-23.09.2019

Copy submitted/forwarded for information and wide circulation to:-

- 1. The Chief Engineer (south-West), Khasjungle, Abas, Midnapur.
- 2. The District Magistrate, Bankura.
- 3. The Savadhipati, Bankura Zilla Parishad.
- 4. The Superintending Engineer-I/II Kangsabati Circle, Bankura.
- 5. The Superintending Engineer, Western Circle-II, Midnapur.
- 6. The Superintending Engineer, Subarnarekha Barrage Circle/Canal Circle, Abas, Midnapur.
- 7. The Executive Engineer, West Midnapur Division/ KKB Division, Paschim Medinipur.
- 8. The Executive Engineer, Subarnarekha Barrage Division/ Head Quarters Division, Abas, Midnapore.
- 9. The Executive Engineer, Kangsabati Canals Division No.- I/II/III/IV/V/BI Division.
- 10. The Director of Information & Cultural affairs Dte, Government of West Bengal, Nabanna, Howrah.
- 11. The District Information Officer, Midnapur, Paschim Medinipur for information.
- 12. Sabhapati, Sarenga Panchyat Samity
- 13 Sabhapati, Simlapal Panchyat Samity
- 14. Assistant Labour Commissioner, Bankura.
- 15. The Sub-Divisional Officer, Bankura.
- 16. The Sub-Divisional Officer, Kangsabati Canals Sub-Division No-I/II/VII.
- 17. The Divisional Accounts Officer (Gr. I), K.C.Division No-I
- 18. Estimating Branch of K.C.Division No-I.
- 19. Notice Board of K.C.Sub-Division No-IV.
- 20. The Nodal Officer, E-Governance, DVC Study Cell, I&W Dte. JalSampad Bhaban, Salt LakeCity, Kolkata-91 for publication in the Departmental Official Website www.wbiwd.gov.in.

Sd/-Sub-Divisional Officer Kangsabati Canals Sub-Division No IV Sarenga, Bankura.

NIT No. - WBIW/SDO/KCSD-IV/NIT 05 0f 2019-20

Sl. No. - 1

"M/R to North-East side boundary wall at Pirargari Section office under K.C. Sub-Division No. - IV of K.C. Division No. - I during 2019-20."

Item Description of itmes Quantity Unit Rate Amount No.		during 2019-20."							
1 Stripping off wom out plaster and raking out joints of walls, celings etc. upto any height and in any floor including removing rubbish within a lead of 75m as directed. 2 Earth work in excavation of foundation trenches or drains, in all sorts of soil (including mixed soil but excluding laterite or sandstone) including removing, spreading or stacking the spoils within a lead of 75 m. as directed. The item includes necessary trimming the sides of trenches, levelling, dressing and ramming the bottom, bailing out water as required complete. (a) Depth of excavation not exceeding 1,500 mm. 3 Filling in foundation or plinth by fine sand in layers not exceeding 150 mm as directed and consolidating the same by thorough saturation with water, ramming complete including the cost of supply of sand. (payment to be made on measurement of finished quantity). 4 Supplying and laying Polythene Sheet (150gm / sq.m.) over damp proof course or below flooring or roof terracing or in foundation or in foundation trenches. 5 Ordinary Cement concrete (mix 1:2:4) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement, ff any, in ground floor as per relevant IS codes. Pakur Variety. 6 Ordinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes. Pakur Variety. 7 Hire and labour charges for shuttering with centering and necessary staging upto 4 m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams and columns, lintels curved or straight including fitting, fixing and striking out after completion of works (upto roof of ground floor) (When the height of a particular floor is more than 4 m the equivalent floor height shall be taken as 4 m and extra for works beyond the initial 4 m ht. shall be allowed under 12 (e) for every 4 m or part thereof) (a) 25 mm to 30 mm thick wooden shuttering as per decision & direction of fing	Item	Description of itmes	Quantity	Unit	Rate	Amount			
upto any height and in any floor including removing rubbish within a lead of 75m as directed. 2 Earth work in excavation of foundation trenches or drains, in all sorts of soil (including mixed soil but excluding laterite or sandstone) including removing, spreading or stacking the spoils within a lead of 75 m. as directed. The item includes necessary trimming the sides of trenches, levelling, dressing and ramming the bottom, bailing out water as required complete. (a) Depth of excavation not exceeding 1,500 mm. 3 Filling in foundation or plinth by fine sand in layers not exceeding 150 mm as directed and consolidating the same by thorough saturation with water, ramming complete including the cost of supply of sand. (payment to be made on measurement of finished quantity). 4 Supplying and laying Polythene Sheet (150gm / sq.m.) over damp proof course or below flooring or roof terracing or in foundation or in foundation trenches. 5 Ordinary Cement concrete (mix 1:2:4) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement, and no size excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes. Pakur Variety. 6 Ordinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes. Pakur Variety. 7 Hire and labour charges for shuttering with centering and necessary staging upto 4 m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams and columns, lintels curved or straight including fitting, fixing and striking out after completion of works (upto roof of ground floor) (a) 25 mm to 30 mm thick wooden shuttering as per decision & direction of Engineer-in-Charge. 8 125 mm to 30 mm thick wooden shuttering as per decision & direction of Engineer-in-Charge. 9 Earth work in filling in foundation trenches or plinth with good earth, in layers not exceeding 150 mm. including watering and r	No.				(Rs.)	(Rs.)			
of 75m as directed. 2 Earth work in excavation of foundation trenches or drains, in all sorts of soil (including mixed soil but excluding laterite or sandstone) including removing, spreading or stacking the spoils within a lead of 75 m. as directed. The item includes necessary trimming the sides of trenches, levelling, dressing and ramming the bottom, bailing out water as required complete. (a) Depth of excavation not exceeding 1,500 mm. as directed and consolidating the same by thorough saturation with water, ramming complete including the cost of supply of sand. (payment to be made on measurement of finished quantity). 4 Supplying and laying Polythene Sheet (150gm / sq.m.) over damp proof course or below flooring or roof terracing or in foundation trenches. 5 Ordinary Cement concrete (mix 1:2:4) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement, and size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes. Pakur Variety. 6 Ordinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes. Pakur Variety. 7 If it and labour charges for shuttering with centering and necessary staging upto 4 m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams and columns, linets curved or straight including fitting, king and striking out after completion of works (upto roof of ground floor) (When the height of a particular floor is more than 4 m the equivalent floor height shall be allowed under 12 (e) for every 4 m or part thereof) (a) 25 mm to 30 mm thick wooden shuttering as per decision & direction of Engineer-in-Charge. 8 125 mm. thick brick work with 1st class bricks in cement mortar (1:4) in ground floor. 9 Earth work in filling in foundation trenches or plinth with good earth, in layers not exceeding 150 mm. including watering and armining etc. layer by layer comple	1	Stripping off worn out plaster and raking out joints of walls, celings etc.							
2 Earth work in excavation of foundation trenches or drains, in all sorts of soil (including mixed soil but excluding laterite or sandstone) including removing, spreading or stacking the spoils within a lead of 75 m. as directed. The item includes necessary trimming the sides of trenches, levelling, dressing and ramming the bottom, bailing out water as required complete. (a) Depth of excavation not exceeding 1,500 mm. 3 Filling in foundation or plinth by fine sand in layers not exceeding 150 mm as directed and consolidating the same by thorough saturation with water, ramming complete including the cost of supply of sand. (payment to be made on measurement of finished quantity). 4 Supplying and laying Polythene Sheet (150gm / sq.m.) over damp proof course or below flooring or roof terracting or in foundation or in foundation trenches. 5 Ordinary Cement concrete (mix 1:2:4) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement, if any, in ground floor as per relevant IS codes. 6 Ordinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes. 7 Pakur Variety. 7 Ilire and labour charges for shuttering with centering and necessary staging upto 4 m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams and columns, lintels curved or straight including fitting, fixing and striking out after completion of works (upto roof of ground floor) 8 125 mm to 30 mm thick wooden shuttering as per decision & direction of Engineer-in-Charge. 8 125 mm to 30 mm thick wooden shuttering as per decision & direction of Engineer-in-Charge. 9 127 mm to 30 mm thick wooden shuttering as per decision & direction of Engineer-in-Charge. 10 Patset (to wall, floor, celling etc.) with sand and cement mortar (1:4) in ground floor. 11 Plaster (to wall, floor, celling etc.) with sand and cement mortar including rounding off or chamfe		upto any height and in any floor including removing rubbish within a lead	_						
soil (including mixed soil but excluding laterite or sandstone) including removing, spreading or stacking the spoils within a lead of 75 m. as directed. The item includes necessary trimming the sides of trenches, levelling, dressing and ramming the bottom, bailing out water as required complete. [a] Depth of excavation not exceeding 1,500 mm. 3 Filling in foundation or plinth by fine sand in layers not exceeding 150 mm as directed and consolidating the same by thorough saturation with water, ramming complete including the cost of supply of sand. (payment to be made on measurement of finished quantity). 4 Supplying and laying Polythene Sheet (150gm / sq.m.) over damp proof course or below flooring or roof terracing or in foundation or in foundation trenches. 5 Ordinary Cement concrete (mix 1:2-4) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement, if any, in ground floor as per relevant IS codes. Pakur Variety. 6 Ordinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes. Pakur Variety. 7 Hire and labour charges for shuttering with centering and necessary staging upto 4 m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams and columns, lintels curved or straight including fitting, fixing and striking out after completion of works (upto roof of ground floor) (a) 25 mm to 30 mm thick wooden shuttering as per decision & direction of Engineer-In-Charge. 8 125 mm. thick brick work with 1st class bricks in cement mortar (1:4) in ground floor. 9 Earth work in filling in foundation trenches or plinth with good earth, in layers not exceeding 150 mm. including watering and ramming etc. layer by layer complete, (Payment to be made on the basis of measurement of finished quantity of work) (a) With earth obtained from excavation of foundation. 10 Plaster (to wall, floor, ceiling etc.) with sand and		of 75m as directed.	32.90 m^2	sqm	21.49	707.00			
removing, spreading or stacking the spoils within a lead of 75 m. as directed. The item includes necessary trimming the sides of trenches, levelling, dressing and ramming the bottom, bailing out water as required complete. (a) Depth of excavation not exceeding 1,500 mm. Filling in foundation or plinth by fine sand in layers not exceeding 150 mm as directed and consolidating the same by thorough saturation with water, ramming complete including the cost of supply of sand. (payment to be made on measurement of finished quantity). Supplying and laying Polythene Sheet (150gm / sq.m.) over damp proof course or below flooring or roof terracing or in foundation or in foundation trenches. Ordinary Cement concrete (mix 1:2:4) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement, and floor as per relevant IS codes. Pakur Variety. Odinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes. Pakur Variety. Odinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes. Pakur Variety. Odinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes. Pakur Variety. Odinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes. Pakur Variety. Odinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes. Pakur Variety. Odinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes. Pakur Variety. Odinary Cement concrete (mix 1:1.5:3) with	2	Earth work in excavation of foundation trenches or drains, in all sorts of							
removing, spreading or stacking the spoils within a lead of 75 m. as directed. The item includes necessary trimming the sides of trenches, levelling, dressing and ramming the bottom, bailing out water as required complete. (a) Depth of excavation not exceeding 1,500 mm. Filling in foundation or plinth by fine sand in layers not exceeding 150 mm as directed and consolidating the same by thorough saturation with water, ramming complete including the cost of supply of sand. (payment to be made on measurement of finished quantity). Supplying and laying Polythene Sheet (150gm / sq.m.) over damp proof course or below flooring or roof terracing or in foundation or in foundation trenches. Ordinary Cement concrete (mix 1:2:4) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement, and floor as per relevant IS codes. Pakur Variety. Odinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes. Pakur Variety. Odinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes. Pakur Variety. Odinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes. Pakur Variety. Odinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes. Pakur Variety. Odinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes. Pakur Variety. Odinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes. Pakur Variety. Odinary Cement concrete (mix 1:1.5:3) with		soil (including mixed soil but excluding laterite or sandstone) including							
levelling, dressing and ramming the bottom, bailing out water as required complete. (a) Depth of excavation not exceeding 1,500 mm. 3 Filling in foundation or plinth by fine sand in layers not exceeding 150 mm as directed and consolidating the same by thorough saturation with water, ramming complete including the cost of supply of sand. (payment to be made on measurement of finished quantity). 4 Supplying and laying Polythene Sheet (150gm / sq.m.) over damp proof course or below flooring or roof terracing or in foundation or in foundation trenches. 5 Ordinary Cement concrete (mix 1:2:4) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement, if any, in ground floor as per relevant IS codes. Pakur Variety. 6 Ordinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes. Pakur Variety. 7 Hire and labour charges for shuttering with centering and necessary staging upto 4 m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams and columns, lintels curved or straight including fitting, fixing and striking out after completion of works (upto roof of ground floor) (When the height of a particular floor is more than 4 m the equivalent floor height shall be taken as 4 m and extra for works beyond the initial 4 m ht. shall be allowed under 12 (e) for every 4 m or part thereof) (a) 25 mm to 30 mm thick worden shuttering as per decision & direction of Engineer-In-Charge. 8 125 mm. thick brick work with 1st class bricks in cement mortar (1:4) in ground floor. 9 Earth work in filling in foundation trenches or plinth with good earth, in layers not exceeding 150 mm. including watering and ramming etc. layer by layer complete. (Payment to be made on the basis of measurement of finished quantity of work) (a) With earth obtained from excavation of foundation. 10 Plaster (to wall, floor, ceiling etc.) with sand a		removing, spreading or stacking the spoils within a lead of 75 m. as							
complete. (a) Depth of excavation not exceeding 1,500 mm. 3 Filling in foundation or plinth by fine sand in layers not exceeding 150 mm as directed and consolidating the same by thorough saturation with water ramming complete including the cost of supply of sand. (payment to be made on measurement of finished quantity). 4 Supplying and laying Polythene Sheet (150gm / sq.m.) over damp proof course or below flooring or roof terracing or in foundation or in foundation trenches. 5 Ordinary Cement concrete (mix 1:2:4) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement.if any, in ground floor as per relevant IS codes. Pakur Variety. 6 Ordinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes. Pakur Variety. 7 Hire and labour charges for shuttering with centering and necessary staging upto 4 m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams and columns, lintels curved or straight including fitting, fixing and striking out after completion of works (upto roof of ground floor) (When the height of a particular floor is more than 4 m the equivalent floor height shall be taken as 4 m and extra for works beyond the initial 4 m ht. shall be allowed under 12 (e) for every 4 m or part thereof) (a) 25 mm to 30 mm thick wooden shuttering as per decision & direction of Engineer-In-Charge. 8 125 mm. thick brick work with 1st class bricks in cement mortar (1:4) in ground floor. (a) With earth obtained from excavation of foundation. 10 Plaster (to wall, floor, celling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor), [Excluding cost of chipping over oncrete surface] (ii) With 1:4 cement mortar									
(a) Depth of excavation not exceeding 1.500 mm. 6.68 m² %cum 13491.82 901.00		levelling, dressing and ramming the bottom, bailing out water as required							
Filling in foundation or plinth by fine sand in layers not exceeding 150 mm as directed and consolidating the same by thorough saturation with water, ramming complete including the cost of supply of sand. (payment to be made on measurement of finished quantity). Supplying and laying Polythene Sheet (150gm / sq.m.) over damp proof course or below flooring or roof terracing or in foundation trenches. Ordinary Cement concrete (mix 1:2:4) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement, if any, in ground floor as per relevant IS codes. Pakur Variety. Ordinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes. Pakur Variety. Ordinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes. Pakur Variety. Ordinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes. Pakur Variety. 3.291 m³ cum 6717.99 22109.00 Hire and labour charges for shuttering with centering and necessary staging upto 4 m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slasbs, beams and columns, lintels curved or straight including fitting, fixing and striking out after completion of works (upto roof of ground floor) (When the height of a particular floor is more than 4 m the equivalent floor height shall be taken as 4 m and extra for works beyond the initial 4 m ht. shall be allowed under 12 (e) for every 4 m or part thereof) (a) 25 mm to 30 mm thick wooden shuttering as per decision & direction of Engineer-In-Charge. Earth work in filling in foundation trenches or plinth with good earth, in layers not exceeding 150 mm. including watering and ramming etc. layer by layer complete. (Payment to be made on the basis		complete.	5 50 3		1010100	001.00			
as directed and consolidating the same by thorough saturation with water, ramming complete including the cost of supply of sand. (payment to be made on measurement of finished quantity). 4 Supplying and laying Polythene Sheet (150gm / sq.m.) over damp proof course or below flooring or roof terracing or in foundation or in foundation trenches. 5 Ordinary Cement concrete (mix 1:2:4) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement,if any, in ground floor as per relevant IS codes. Pakur Variety. 6 Ordinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes. Pakur Variety. 7 Hire and labour charges for shuttering with centering and necessary staging upto 4 m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams and columns, lintels curved or straight including fitting, fixing and striking out after completion of works (upto roof of ground floor) (When the height of a particular floor is more than 4 m the equivalent floor height shall be taken as 4 m and extra for works beyond the initial 4 m ht. shall be allowed under 12 (e) for every 4 m or part thereof) (a) 25 mm to 30 mm thick wooden shuttering as per decision & direction of Engineer-In-Charge. 8 125 mm. thick brick work with 1st class bricks in cement mortar (1:4) in ground floor. 9 Earth work in filling in foundation trenches or plinth with good earth, in layers not exceeding 150 mm. including watering and ramming etc. layer by layer complete. (Payment to be made on the basis of measurement of finished quantity of work). (a) With earth obtained from excavation of foundation. 10 Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor), [Excluding cost of			6.68 m ³	%cum	13491.82	901.00			
ramming complete including the cost of supply of sand. (payment to be made on measurement of finished quantity). 4 Supplying and laying Polythene Sheet (150gm / sq.m.) over damp proof course or below flooring or roof terracing or in foundation or in foundation trenches. 5 Ordinary Cement concrete (mix 1:2:4) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement, if any, in ground floor as per relevant IS codes. Pakur Variety. 6 Ordinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes. Pakur Variety. 7 Illire and labour charges for shuttering with centering and necessary staging upto 4 m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams and columns, lintels curved or straight including fitting, fixing and striking out after completion of works (upto roof of ground floor) (When the height of a particular floor is more than 4 m the equivalent floor height shall be taken as 4 m and extra for works beyond the initial 4 m ht. shall be allowed under 12 (e) for every 4 m or part thereof) (a) 25 mm to 30 mm thick wooden shuttering as per decision & direction of Engineer-in-Charge. 8 125 mm. thick brick work with 1st class bricks in cement mortar (1:4) in ground floor. 9 Earth work in filling in foundation trenches or plinth with good earth, in layers not exceeding 150 mm. including watering and ramming etc. layer by layer complete. (Payment to be made on the basis of measurement of finished quantity of work) (a) With earth obtained from excavation of foundation. 10 Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor). [Excluding cost of chipping over oncrete surface] (ii) With 1:4 cement mortar	3								
made on measurement of finished quantity). 4 Supplying and laying Polythene Sheet (150gm / sq.m.) over damp proof course or below flooring or roof terracing or in foundation or in foundation trenches. 5 Ordinary Cement concrete (mix 1:2:4) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement, if any, in ground floor as per relevant IS codes. Pakur Variety. 6 Ordinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes. Pakur Variety. 7 Hire and labour charges for shuttering with centering and necessary staging upto 4 m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams and columns, lintels curved or straight including fitting, fixing and striking out after completion of works (upto roof of ground floor) (When the height of a particular floor is more than 4 m the equivalent floor height shall be taken as 4 m and extra for works beyond the initial 4 m ht. shall be allowed under 12 (e) for every 4 m or part thereof) (a) 25 mm to 30 mm thick wooden shuttering as per decision & direction of Engineer-In-Charge. 8 125 mm. thick brick work with 1st class bricks in cement mortar (1:4) in ground floor. 9 Earth work in filling in foundation trenches or plinth with good earth, in layers not exceeding 150 mm. including watering and ramming etc. layer by layer complete. (Payment to be made on the basis of measurement of finished quantity of work) (a) With earth obtained from excavation of foundation. 10 Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor). [Excluding cost of chipping over oncrete surface] (ii) With 1:4 cement mortar									
4 Supplying and laying Polythene Sheet (150gm / sq.m.) over damp proof course or below flooring or roof terracing or in foundation or in foundation trenches. 5 Ordinary Cement concrete (mix 1:2:4) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement, if any, in ground floor as per relevant IS codes. Pakur Variety. 6 Ordinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes. Pakur Variety. 7 Hire and labour charges for shuttering with centering and necessary staging upto 4 m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams and columns, lintels curved or straight including fitting, fixing and striking out after completion of works (upto roof of ground floor) (When the height of a particular floor is more than 4 m the equivalent floor height shall be taken as 4 m and extra for works beyond the initial 4 m ht. shall be allowed under 12 (e) for every 4 m or part thereof) (a) 25 mm to 30 mm thick wooden shuttering as per decision & direction of Engineer-In-Charge. 8 125 mm. thick brick work with 1st class bricks in cement mortar (1:4) in ground floor. 9 Earth work in filling in foundation trenches or plinth with good earth, in layers not exceeding 150 mm. including watering and ramming etc. layer by layer complete. (Payment to be made on the basis of measurement of finished quantity of work) (a) With earth obtained from excavation of foundation. 10 Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor). [Excluding cost of chipping over oncrete surface] (ii) With 1:4 cement mortar			3						
course or below flooring or roof terracing or in foundation or in foundation trenches. Ordinary Cement concrete (mix 1:2:4) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement, if any, in ground floor as per relevant IS codes. Pakur Variety. Ordinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes. Pakur Variety. Ordinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes. Pakur Variety. Jerica and labour charges for shuttering with centering and necessary staging upto 4 m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams and columns, lintels curved or straight including fitting, fixing and striking out after completion of works (upto roof of ground floor) (When the height of a particular floor is more than 4 m the equivalent floor height shall be taken as 4 m and extra for works beyond the initial 4 m ht. shall be allowed under 12 (e) for every 4 m or part thereof (a) 25 mm to 30 mm thick wooden shuttering as per decision & direction of Engineer-In-Charge. 22.44 m² sqm 363.12 8148.00 Earth work in filling in foundation trenches or plinth with good earth, in layers not exceeding 150 mm. including watering and ramming etc. layer by layer complete. (Payment to be made on the basis of measurement of finished quantity of work) (a) With earth obtained from excavation of foundation. Jerster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).(Excluding cost of chipping over oncrete surface) With earth obtained from excavation of chipping over oncrete surface)			0.62 m ³	%cum	55135.82	342.00			
trenches. 5 Ordinary Cement concrete (mix 1:2:4) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement, if any, in ground floor as per relevant IS codes. Pakur Variety. 6 Ordinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes. Pakur Variety. 7 Hire and labour charges for shuttering with centering and necessary staging upto 4 m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams and columns, lintels curved or straight including fitting, fixing and striking out after completion of works (upto roof of ground floor) (When the height of a particular floor is more than 4 m the equivalent floor height shall be taken as 4 m and extra for works beyond the initial 4 m ht. shall be allowed under 12 (e) for every 4 m or part thereof) (a) 25 mm to 30 mm thick wooden shuttering as per decision & direction of Engineer-In-Charge. 8 125 mm. thick brick work with 1st class bricks in cement mortar (1:4) in ground floor. 9 Earth work in filling in foundation trenches or plinth with good earth, in layers not exceeding 150 mm. including watering and ramming etc. layer by layer complete. (Payment to be made on the basis of measurement of finished quantity of work) (a) With earth obtained from excavation of foundation. 10 Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor). [Excluding cost of chipping over oncrete surface] (ii) With 1:4 cement mortar	4								
Ordinary Cement concrete (mix 1:2:4) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement, if any, in ground floor as per relevant IS codes. Pakur Variety. Ordinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes. Pakur Variety. Jirch and labour charges for shuttering with centering and necessary staging upto 4 m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams and columns, lintels curved or straight including fitting, fixing and striking out after completion of works (upto roof of ground floor) (When the height of a particular floor is more than 4 m the equivalent floor height shall be taken as 4 m and extra for works beyond the initial 4 m ht. shall be allowed under 12 (e) for every 4 m or part thereof) (a) 25 mm to 30 mm thick wooden shuttering as per decision & direction of Engineer-In-Charge. Z2.44 m ² sqm 363.12 8148.00 125 mm. thick brick work with 1st class bricks in cement mortar (1:4) in ground floor. Barth work in filling in foundation trenches or plinth with good earth, in layers not exceeding 150 mm. including watering and ramming etc. layer by layer complete. (Payment to be made on the basis of measurement of finished quantity of work) (a) With earth obtained from excavation of foundation. Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor). [Excluding cost of chipping over oncrete surface] Barth work in flicting should be added to the complete of the property o			0 = 0 2		0= 1=	0			
nominal size) excluding shuttering and reinforcement, if any, in ground floor as per relevant IS codes. Pakur Variety. Ordinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes. Pakur Variety. 7 Hire and labour charges for shuttering with centering and necessary staging upto 4 m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams and columns, lintels curved or straight including fitting, fixing and striking out after completion of works (upto roof of ground floor) (When the height of a particular floor is more than 4 m the equivalent floor height shall be taken as 4 m and extra for works beyond the initial 4 m ht. shall be allowed under 12 (e) for every 4 m or part thereof) (a) 25 mm to 30 mm thick wooden shuttering as per decision & direction of Engineer-In-Charge. 8 125 mm. thick brick work with 1st class bricks in cement mortar (1:4) in ground floor. 9 Earth work in filling in foundation trenches or plinth with good earth, in layers ont exceeding 150 mm. including watering and ramming etc. layer by layer complete. (Payment to be made on the basis of measurement of finished quantity of work) (a) With earth obtained from excavation of foundation. 10 Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor). [Excluding cost of chipping over oncrete surface] (ii) With 1:4 cement mortar			9.79 m ²	sqm	27.15	266.00			
floor as per relevant IS codes. Pakur Variety. Ordinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes. Pakur Variety. Thire and labour charges for shuttering with centering and necessary staging upto 4 m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams and columns, lintels curved or straight including fitting, fixing and striking out after completion of works (upto roof of ground floor) (When the height of a particular floor is more than 4 m the equivalent floor height shall be taken as 4 m and extra for works beyond the initial 4 m ht. shall be allowed under 12 (e) for every 4 m or part thereof) (a) 25 mm to 30 mm thick wooden shuttering as per decision & direction of Engineer-In-Charge. 125 mm. thick brick work with 1st class bricks in cement mortar (1:4) in ground floor. Earth work in filling in foundation trenches or plinth with good earth, in layers not exceeding 150 mm. including watering and ramming etc. layer by layer complete. (Payment to be made on the basis of measurement of finished quantity of work) (a) With earth obtained from excavation of foundation. Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor). [Excluding cost of chipping over oncrete surface] (ii) With 1:4 cement mortar	5								
Pakur Variety. Ordinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes. Pakur Variety. 7 Hire and labour charges for shuttering with centering and necessary staging upto 4 m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams and columns, lintels curved or straight including fitting, fixing and striking out after completion of works (upto roof of ground floor) (When the height of a particular floor is more than 4 m the equivalent floor height shall be taken as 4 m and extra for works beyond the initial 4 m ht. shall be allowed under 12 (e) for every 4 m or part thereof) (a) 25 mm to 30 mm thick wooden shuttering as per decision & direction of Engineer-In-Charge. 8 125 mm. thick brick work with 1st class bricks in cement mortar (1:4) in ground floor. 9 Earth work in filling in foundation trenches or plinth with good earth, in layers not exceeding 150 mm. including watering and ramming etc. layer by layer complete. (Payment to be made on the basis of measurement of finished quantity of work) (a) With earth obtained from excavation of foundation. Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor). [Excluding cost of chipping over oncrete surface] (ii) With 1:4 cement mortar									
Ordinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes. Pakur Variety. 3.291 m³ cum 6717.99 22109.00 Hire and labour charges for shuttering with centering and necessary staging upto 4 m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams and columns, lintels curved or straight including fitting, fixing and striking out after completion of works (upto roof of ground floor) (When the height of a particular floor is more than 4 m the equivalent floor height shall be taken as 4 m and extra for works beyond the initial 4 m ht. shall be allowed under 12 (e) for every 4 m or part thereof) (a) 25 mm to 30 mm thick wooden shuttering as per decision & direction of Engineer-In-Charge. 22.44 m² sqm 363.12 8148.00 8 125 mm. thick brick work with 1st class bricks in cement mortar (1:4) in ground floor. 9 Earth work in filling in foundation trenches or plinth with good earth, in layers not exceeding 150 mm. including watering and ramming etc. layer by layer complete. (Payment to be made on the basis of measurement of finished quantity of work) (a) With earth obtained from excavation of foundation. 10 Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor). [Excluding cost of chipping over oncrete surface] (ii) With 1:4 cement mortar			0.000 3		600444	2205.00			
nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes. Pakur Variety. 7 Hire and labour charges for shuttering with centering and necessary staging upto 4 m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams and columns, lintels curved or straight including fitting, fixing and striking out after completion of works (upto roof of ground floor) (When the height of a particular floor is more than 4 m the equivalent floor height shall be taken as 4 m and extra for works beyond the initial 4 m ht. shall be allowed under 12 (e) for every 4 m or part thereof) (a) 25 mm to 30 mm thick wooden shuttering as per decision & direction of Engineer-In-Charge. 8 125 mm. thick brick work with 1st class bricks in cement mortar (1:4) in ground floor. 9 Earth work in filling in foundation trenches or plinth with good earth, in layers not exceeding 150 mm. including watering and ramming etc. layer by layer complete. (Payment to be made on the basis of measurement of finished quantity of work) (a) With earth obtained from excavation of foundation. 10 Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor). [Excluding cost of chipping over oncrete surface] (ii) With 1:4 cement mortar			0.393 m°	cum	6094.14	2395.00			
floor as per relevant IS codes. Pakur Variety. 7 Hire and labour charges for shuttering with centering and necessary staging upto 4 m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams and columns, lintels curved or straight including fitting, fixing and striking out after completion of works (upto roof of ground floor) (When the height of a particular floor is more than 4 m the equivalent floor height shall be taken as 4 m and extra for works beyond the initial 4 m ht. shall be allowed under 12 (e) for every 4 m or part thereof) (a) 25 mm to 30 mm thick wooden shuttering as per decision & direction of Engineer-In-Charge. 8 125 mm. thick brick work with 1st class bricks in cement mortar (1:4) in ground floor. 9 Earth work in filling in foundation trenches or plinth with good earth, in layers not exceeding 150 mm. including watering and ramming etc. layer by layer complete. (Payment to be made on the basis of measurement of finished quantity of work) (a) With earth obtained from excavation of foundation. 10 Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor). [Excluding cost of chipping over oncrete surface] (ii) With 1:4 cement mortar	6								
Pakur Variety. 3.291 m³ cum 6717.99 22109.00 Hire and labour charges for shuttering with centering and necessary staging upto 4 m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams and columns, lintels curved or straight including fitting, fixing and striking out after completion of works (upto roof of ground floor) (When the height of a particular floor is more than 4 m the equivalent floor height shall be taken as 4 m and extra for works beyond the initial 4 m ht. shall be allowed under 12 (e) for every 4 m or part thereof) (a) 25 mm to 30 mm thick wooden shuttering as per decision & direction of Engineer-In-Charge. 22.44 m² sqm 363.12 8148.00 125 mm. thick brick work with 1st class bricks in cement mortar (1:4) in ground floor. Earth work in filling in foundation trenches or plinth with good earth, in layers not exceeding 150 mm. including watering and ramming etc. layer by layer complete. (Payment to be made on the basis of measurement of finished quantity of work) (a) With earth obtained from excavation of foundation. 3.837 m³ %cum 8771.32 337.00 Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor). [Excluding cost of chipping over oncrete surface] (ii) With 1:4 cement mortar		, , , , , , , , , , , , , , , , , , , ,							
Hire and labour charges for shuttering with centering and necessary staging upto 4 m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams and columns, lintels curved or straight including fitting, fixing and striking out after completion of works (upto roof of ground floor) (When the height of a particular floor is more than 4 m the equivalent floor height shall be taken as 4 m and extra for works beyond the initial 4 m ht. shall be allowed under 12 (e) for every 4 m or part thereof) (a) 25 mm to 30 mm thick wooden shuttering as per decision & direction of Engineer-In-Charge. 22.44 m² sqm 363.12 8148.00 8 125 mm. thick brick work with 1st class bricks in cement mortar (1:4) in ground floor. 9 Earth work in filling in foundation trenches or plinth with good earth, in layers not exceeding 150 mm. including watering and ramming etc. layer by layer complete. (Payment to be made on the basis of measurement of finished quantity of work) (a) With earth obtained from excavation of foundation. 3.837 m³ %cum 8771.32 337.00 10 Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over oncrete surface] (ii) With 1:4 cement mortar		•	2 201 3		6717.00	22400.00			
staging upto 4 m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams and columns, lintels curved or straight including fitting, fixing and striking out after completion of works (upto roof of ground floor) (When the height of a particular floor is more than 4 m the equivalent floor height shall be taken as 4 m and extra for works beyond the initial 4 m ht. shall be allowed under 12 (e) for every 4 m or part thereof) (a) 25 mm to 30 mm thick wooden shuttering as per decision & direction of Engineer-In-Charge. 8		-	3.291 m	cum	6/1/.99	22109.00			
of approved thickness with required bracing for concrete slabs, beams and columns, lintels curved or straight including fitting, fixing and striking out after completion of works (upto roof of ground floor) (When the height of a particular floor is more than 4 m the equivalent floor height shall be taken as 4 m and extra for works beyond the initial 4 m ht. shall be allowed under 12 (e) for every 4 m or part thereof) (a) 25 mm to 30 mm thick wooden shuttering as per decision & direction of Engineer-In-Charge. 22.44 m² sqm 363.12 8148.00 8 125 mm. thick brick work with 1st class bricks in cement mortar (1:4) in ground floor. 9 Earth work in filling in foundation trenches or plinth with good earth, in layers not exceeding 150 mm. including watering and ramming etc. layer by layer complete. (Payment to be made on the basis of measurement of finished quantity of work) (a) With earth obtained from excavation of foundation. 10 Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor). [Excluding cost of chipping over oncrete surface] (ii) With 1:4 cement mortar	7								
columns, lintels curved or straight including fitting, fixing and striking out after completion of works (upto roof of ground floor) (When the height of a particular floor is more than 4 m the equivalent floor height shall be taken as 4 m and extra for works beyond the initial 4 m ht. shall be allowed under 12 (e) for every 4 m or part thereof) (a) 25 mm to 30 mm thick wooden shuttering as per decision & direction of Engineer-In-Charge. 8 125 mm. thick brick work with 1st class bricks in cement mortar (1:4) in ground floor. 9 Earth work in filling in foundation trenches or plinth with good earth, in layers not exceeding 150 mm. including watering and ramming etc. layer by layer complete. (Payment to be made on the basis of measurement of finished quantity of work) (a) With earth obtained from excavation of foundation. 10 Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor). [Excluding cost of chipping over oncrete surface] (ii) With 1:4 cement mortar									
after completion of works (upto roof of ground floor) (When the height of a particular floor is more than 4 m the equivalent floor height shall be taken as 4 m and extra for works beyond the initial 4 m ht. shall be allowed under 12 (e) for every 4 m or part thereof) (a) 25 mm to 30 mm thick wooden shuttering as per decision & direction of Engineer-In-Charge. 8 125 mm. thick brick work with 1st class bricks in cement mortar (1:4) in ground floor. 9 Earth work in filling in foundation trenches or plinth with good earth, in layers not exceeding 150 mm. including watering and ramming etc. layer by layer complete. (Payment to be made on the basis of measurement of finished quantity of work) (a) With earth obtained from excavation of foundation. 10 Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over oncrete surface] (ii) With 1:4 cement mortar									
(When the height of a particular floor is more than 4 m the equivalent floor height shall be taken as 4 m and extra for works beyond the initial 4 m ht. shall be allowed under 12 (e) for every 4 m or part thereof) (a) 25 mm to 30 mm thick wooden shuttering as per decision & direction of Engineer-In-Charge. 8 125 mm. thick brick work with 1st class bricks in cement mortar (1:4) in ground floor. 9 Earth work in filling in foundation trenches or plinth with good earth, in layers not exceeding 150 mm. including watering and ramming etc. layer by layer complete. (Payment to be made on the basis of measurement of finished quantity of work) (a) With earth obtained from excavation of foundation. 10 Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor). [Excluding cost of chipping over oncrete surface] (ii) With 1:4 cement mortar									
height shall be taken as 4 m and extra for works beyond the initial 4 m ht. shall be allowed under 12 (e) for every 4 m or part thereof) (a) 25 mm to 30 mm thick wooden shuttering as per decision & direction of Engineer-In-Charge. 8 125 mm. thick brick work with 1st class bricks in cement mortar (1:4) in ground floor. 9 Earth work in filling in foundation trenches or plinth with good earth, in layers not exceeding 150 mm. including watering and ramming etc. layer by layer complete. (Payment to be made on the basis of measurement of finished quantity of work) (a) With earth obtained from excavation of foundation. 10 Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor). [Excluding cost of chipping over oncrete surface] (ii) With 1:4 cement mortar									
shall be allowed under 12 (e) for every 4 m or part thereof) (a) 25 mm to 30 mm thick wooden shuttering as per decision & direction of Engineer-In-Charge. 8 125 mm. thick brick work with 1st class bricks in cement mortar (1:4) in ground floor. 9 Earth work in filling in foundation trenches or plinth with good earth, in layers not exceeding 150 mm. including watering and ramming etc. layer by layer complete. (Payment to be made on the basis of measurement of finished quantity of work) (a) With earth obtained from excavation of foundation. 10 Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor). [Excluding cost of chipping over oncrete surface] (ii) With 1:4 cement mortar									
(a) 25 mm to 30 mm thick wooden shuttering as per decision & direction of Engineer-In-Charge. 8 125 mm. thick brick work with 1st class bricks in cement mortar (1:4) in ground floor. 9 Earth work in filling in foundation trenches or plinth with good earth, in layers not exceeding 150 mm. including watering and ramming etc. layer by layer complete. (Payment to be made on the basis of measurement of finished quantity of work) (a) With earth obtained from excavation of foundation. 10 Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor). [Excluding cost of chipping over oncrete surface] (ii) With 1:4 cement mortar									
of Engineer-In-Charge. 8 125 mm. thick brick work with 1st class bricks in cement mortar (1:4) in ground floor. 9 Earth work in filling in foundation trenches or plinth with good earth, in layers not exceeding 150 mm. including watering and ramming etc. layer by layer complete. (Payment to be made on the basis of measurement of finished quantity of work) (a) With earth obtained from excavation of foundation. 10 Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor). [Excluding cost of chipping over oncrete surface] (ii) With 1:4 cement mortar									
8 125 mm. thick brick work with 1st class bricks in cement mortar (1:4) in ground floor. 9 Earth work in filling in foundation trenches or plinth with good earth, in layers not exceeding 150 mm. including watering and ramming etc. layer by layer complete. (Payment to be made on the basis of measurement of finished quantity of work) (a) With earth obtained from excavation of foundation. 10 Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over oncrete surface] (ii) With 1:4 cement mortar		* *	22.44 m^2	sqm	363.12	8148.00			
ground floor. 9 Earth work in filling in foundation trenches or plinth with good earth, in layers not exceeding 150 mm. including watering and ramming etc. layer by layer complete. (Payment to be made on the basis of measurement of finished quantity of work) (a) With earth obtained from excavation of foundation. 10 Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor). [Excluding cost of chipping over oncrete surface] (ii) With 1:4 cement mortar	8	e		*					
Earth work in filling in foundation trenches or plinth with good earth, in layers not exceeding 150 mm. including watering and ramming etc. layer by layer complete. (Payment to be made on the basis of measurement of finished quantity of work) (a) With earth obtained from excavation of foundation. Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over oncrete surface] (ii) With 1:4 cement mortar			16.51 m ²	sgm	707.00	11673.00			
layers not exceeding 150 mm. including watering and ramming etc. layer by layer complete. (Payment to be made on the basis of measurement of finished quantity of work) (a) With earth obtained from excavation of foundation. 3.837 m³ %cum 8771.32 337.00 Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over oncrete surface] (ii) With 1:4 cement mortar	9								
by layer complete. (Payment to be made on the basis of measurement of finished quantity of work) (a) With earth obtained from excavation of foundation. 7. Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor). [Excluding cost of chipping over oncrete surface] (ii) With 1:4 cement mortar									
finished quantity of work) (a) With earth obtained from excavation of foundation. 7 Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over oncrete surface] (ii) With 1:4 cement mortar									
(a) With earth obtained from excavation of foundation. 3.837 m³ %cum 8771.32 337.00 Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over oncrete surface] (ii) With 1:4 cement mortar									
Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over oncrete surface] (ii) With 1:4 cement mortar			3.837 m^3	%cum	8771.32	337.00			
rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over oncrete surface] (ii) With 1:4 cement mortar	10								
including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over oncrete surface] (ii) With 1:4 cement mortar									
necessary (Ground floor).[Excluding cost of chipping over oncrete surface] (ii) With 1:4 cement mortar									
surface] (ii) With 1:4 cement mortar									
[(a) 20 mm thick plaster 86.89 m ² sam 195.70 17004.00		(ii) With 1:4 cement mortar	_						
100 m 54m 250m 1700 mo		(a) 20 mm thick plaster	86.89 m ²	sqm	195.70	17004.00			

Item	Description of itmes	Quantity	Unit	Rate	Amount
No.				(Rs.)	(Rs.)
11	Applying Exterior grade Acrylic primer of approved quality and brand on				
	plastered or cencrete surface old or new surface to receive decorative				
	textured(matt finish) or smooth finish acrylic exterior emulsion paint including scraping and preparing the surface throughly, complete as per				
	manufacturer's specification and as per direction of the EIC.				
	In Ground Floor:				
	(a) One Coat	229.74 m ²	%sqm	3551.97	8160.00
12	Protective and Decorative Acrylic exterior emulsion paint of approved		701.1		
	quality, as per manufacturer's specification and as per direction of EIC to				
	be applied over acrylic primer as required. The rate includes cost of				
	material, labour, scaffolding and all incidental charges but excluding the				
	cost of primer.				
	In Ground floor (Two Coat)	2			
	a) Normal Acrylic Emulsion	229.74 m ²	sqm	75.79	17412.00
13	Scraping of moss, blisters etc. thoroughly from exterior surface of walls				
	necessitating the use of scraper, wire brush etc.(Payment against this item				
	will be made only when this has been done on the specific direction of the	142.85 m ²		7.92	1131.00
1.4	Engineer-in-charge)	142.85 M	sqm	7.92	1131.00
14	Reinforcement for reinforced concrete work in all sorts of structures including distribution bars, stirrups, binders etc initial straightening and				
	removal of loose rust (if necessary), cutting to requisite length, hooking				
	and bending to correct shape, placing in proper position and binding with				
	16 gauge black annealed wire at every intersection, complete as per				
	drawing and direction.				
	(a) For works in foundation and upto roof of ground floor/upto 4 m				
	(i) Tor steel/Mild Steel				
	II. Other than SAIL/TATA/RINL	0.259 MT	MT	79859.85	20684.00
15	Clearing compound premises of shurbs, plants, jungles etc. by cutting and				
	removing as directed (Specific permission of Engineer-in-Charge prior to				
	execution will be necessary). (Payment to be made on area cleared)	180.00 m ²		12.44	2220.00
		180.00 m	sqm	12.44	2239.00
			Total	Amount =	113508.00

Sub-Divisional officer Kangsabati Canals Sub-Division No.- IV Sarenga, Bankura

NIT No. - WBIW/SDO/KCSD-IV/NIT05 0f 2019-20

Sl. No. - 2

Name of Work:- M/R to Silt Clerance of Dy. No.-4 of K.M.C(L) Inbetween Ch.- 142.00 and ch.-168.00 under Hd. Qrt. Section of K.C. Sub Division No.-IV Sarenga, under K.C Divn.No.-I Amlagora Paschim Midnapur, during 2019-2020.

Item	Description of itmes	Unit	Quantity	Rate	Amount (Rs.)
No.					
	Cutting uprooting and clearing jungles including shrubs, water weeds,				
	bushes, trees, plants, up to 30 cm. girth including removing as directed by				
	Engineer-in-charge.	Sqm	1228.95 m ²	5.05	6206.00
	Earth work from borrow pits over existing embankment or for repairs to embankment, closing breaches etc. with in an initial lead of 30metre and lift of 1.50metre including breaking clods and depositing the same in layers not exceeding 25cm. and rough dressing etc. complete as per profile.				
		Cum	587.13 m ³	81.81	48033.00
Total Rs. =					

(Rupees Fifty Four Thousand Two Hundred Thirty Nine Only)

Sub-Divisional officer Kangsabati Canals Sub-Division No.-IV Sarenga, Bankura

Name of Work: M/R to Silt Clerance of Dy. No.-4 of K.M.C(L) Inbetween Ch.- 168.50 and ch.-204.00 under Hd. Qrt. Section of K.C. Sub Division No.-IV Sarenga, under K.C Divn.No.-I Amlagora Paschim Midnapur, during 2019-2020.

Item	Description of itmes	Unit	Quantity	Rate	Amount (Rs.)
No.					
	Cutting uprooting and clearing jungles including shrubs, water weeds,				
	bushes, trees, plants, up to 30 cm. girth including removing as directed by				
	Engineer-in-charge.	Sqm	585.22 m^2	5.05	2955.00
	Earth work from borrow pits over existing embankment or for repairs to embankment, closing breaches etc. with in an initial lead of 30metre and lift of 1.50metre including breaking clods and depositing the same in layers not exceeding 25cm. and rough dressing etc. complete as per profile.				
		Cum	713.05 m ³	81.81	58335.00
Total Rs. =					

(Rupees Sixty one Thousand Two Hundred Ninety Only)

Sub-Divisional officer Kangsabati Canals Sub-Division No.-IV Sarenga, Bankura

NIT No WBIW/SDO/KCSD-IV/NIT05	0f 2019-20	Sl. No 4

Name of Work: M/R to Cutting & removing Jungles in-between Ch.-257.00 and ch.290.00 (L/B & R/B) of K.M.C(L) and inbetween ch-106.00 & Ch-111.00, Ch-146.00 & Ch-151.00, Ch-326.00 & Ch-332.00, Ch-432.00 & Ch-437.00 Of M.B.C under Hd. Qrt. Section of K.C. Sub Division No.-IV Sarenga, under K.C Divn.No.-I Amlagora Paschim Midnapur, during 2019-2020.

Item No.	Description of itmes	Unit	Quantity	Rate	Amount (Rs.)
1	Cutting uprooting and clearing jungles including shrubs, water weeds, bushes, trees, plants, up to 30 cm. girth including removing as directed by Engineer-in-charge.	Sqm	9140.34 m ²	5.05	46159.00
				Total Rs. =	46159.00

(Rupees Forty Six Thousand One Hundred Fifty Nine Only)

Sub-Divisional officer Kangsabati Canals Sub-Division No.-IV Sarenga, Bankura

"Soil Investigation for Proposed C.C. Lining in different reaches of MBC under K.C Sub-Division No-IV, Sarenga uder K.C Division No-I, Amlagora, Paschim Medinipur.

Item	Description of itmes	Unit	Quantity		Rate	Amount (Rs.)
No.	Description of funes	Onic	Quantity		including GST & Cess	Amount (Rs.)
1	Mobilisation Charges of all tools & Plants along with accessories, material, labour, supervision etc. at site of work required in connection with boring and testing work, including setting up boring rigs and shifting to different Borehole points etc. and also including withdrawal of same from the site after completion of work, complete as per direction of Engineer-in-Charge. b) Detailed Investigation.					
		L.S	1		29795.00	29795.00
2	Labour for making Bore-Holes of 150mm to 250mm dia. by any standard method to any depth below ground level / bed level in all kinds of soil like clay, , silt, sand, stiff clay, mixed soils etc. except rocks (for the purpose of collecting Disturbed & Un disturbed soil samples, conducting Standard Penetration Test at suitable intervals etc.) including preparation and submission of bore-log as per IRC: 75 and 78 and Clause 2400 of Specifications for Road & Bridge Works (5th Revision), Published by IRC, and also including hire charges of tools and plants complete as per the direction of Engineer-in-Charge. b) When drilling mud "Bentonite of suitable consistency" is used to prevent collapse of bore hole. (i) Depth 0.00 m to 10.00 m					
		m	324.00	m	345.62	111981.00
3	B Field Investigation: v) Collection of Undisturbed soil sample from the bore hole to be made by the concerned Division / Party at their cost. (i)0.0 m - 10.0 m	Each	72.00	Nos	274.11	19736.00
4	Carriage of all Disturbed & Undisturbed Samples from site of work to the Divisional office or elsewhere including loading and unloading as per direction of Engineer-in-Charge. Detailed Investigation.	L.S	1		1906.88	1907.00
5	A. Laboratory Investigation: xvii) Laboratory Determination of Permeability as per IS 2720 (Part– XVII).			N		
6	A. Laboratory Investigation:	Each	36	Nos	822.34	29604.00
0	xxviii) Determination of Swelling Pressure of Soil as per IS 2720 (Part–VIII).	Each	36	Nos	822.34	29604.00
7	Preparation and submission of report in 6 (Six) copies, giving all relevant information data like site plan, Bore log and water table, test results, calculations, discussions, suggestions and recommendations in respect of suitable foundation etc. including determination of silt factor calculation of waterways and complete design of foundation including analysis of Bearing Capacities and settlements in bound and presentable form complete as per direction of Engineer-in-Charge. b) Detailed Investigation.					
		L.S	1		14898.00	14898.00
					Total Rs. =	237525.00

(Rupees Two Lakh Thirty Seven Thousand Five Hundred Twenty Five Only)

Sub-Divisional officer Kangsabati Canals Sub-Division No.-IV Sarenga, Bankura

NIT No. - WBIW/SDO/KCSD-IV/NIT05 0f 2019-20

Sl. No. - 6

Name of Work: M/R to Silt Clerance of Mr C of Dy. No.-4 of K.M.C(L) Inbetween Ch.- 0.00 and ch.-30.00 under Hd. Qrt. Section of K.C. Sub Division No.-IV Sarenga, under K.C Divn.No.-I Amlagora Paschim Midnapur, during 2019-2020.

Item	Description of itmes	Unit	Quantity	Rate	Amount (Rs.)
No.					
	Cutting uprooting and clearing jungles including shrubs, water weeds, bushes, trees, plants, up to 30 cm. girth including removing as directed by				
	Engineer-in-charge.	Sqm	1280.16 m ²	5.05	6465.00
	Earth work from borrow pits over existing embankment or for repairs to embankment, closing breaches etc. with in an initial lead of 30metre and lift of 1.50metre including breaking clods and depositing the same in layers not exceeding 25cm. and rough dressing etc. complete as per profile.				
		Cum	378.38 m^3	81.81	30955.00
				Total Rs. =	37420.00

Sub-Divisional officer Kangsabati Canals Sub-Division No.-IV Sarenga, Bankura

NIT No. - WBIW/SDO/KCSD-IV/NIT05 0f 2019-20

Sl. No. - 7

Name of Work:- M/R to Silt Clerance of Sub- Minor A of Minor B of Dy. No.-4 of K.M.C(L) Inbetween Ch.- 168.50 and ch.- 204.00 under Hd. Qrt. Section of K.C. Sub Division No.-IV Sarenga, under K.C Divn.No.-I Amlagora Paschim Midnapur, during 2019-2020.

Item	Description of itmes	Unit	Quantity	Rate	Amount (Rs.)
No.					
	Cutting uprooting and clearing jungles including shrubs, water weeds,				
	bushes, trees, plants, up to 30 cm. girth including removing as directed by		_		
	Engineer-in-charge.	Sqm	1941.58 m ²	5.05	9805.00
	Earth work from borrow pits over existing embankment or for repairs to embankment, closing breaches etc. with in an initial lead of 30metre and lift of 1.50metre including breaking clods and depositing the same in layers not exceeding 25cm. and rough dressing etc. complete as per profile.		2		
		Cum	413.67 m ³	81.81	33842.00
Total Rs. =					43647.00

Sub-Divisional officer Kangsabati Canals Sub-Division No.-IV Sarenga, Bankura

"Soil Investigation for Proposed C.C. Lining in different reaches of Dy. No. -12, 12A & its minor of KMC(U) under K.C Sub-Division No-IV, Sarenga of K.C Division No-I, Amlagora, Paschim Medinipur

Item No.	Description of itmes	Unit	Quantity		Rate including GST & Cess	Amount (Rs.)
1	Mobilisation Charges of all tools & Plants along with accessories, material, labour, supervision etc. at site of work required in connection with boring and testing work, including setting up boring rigs and shifting to different Borehole points etc. and also including withdrawal of same from the site after completion of work, complete as per direction of Engineer-in-Charge. b) Detailed Investigation.					
	Labour formaching Dana Halos of 450m 1, 250m 1, 1	L.S	1		29795.00	29795.00
2	Labour for making Bore-Holes of 150mm to 250mm dia. by any standard method to any depth below ground level / bed level in all kinds of soil like clay, , silt, sand, stiff clay, mixed soils etc. except rocks (for the purpose of collecting Disturbed & Un disturbed soil samples, conducting Standard Penetration Test at suitable intervals etc.) including preparation and submission of bore-log as per IRC: 75 and 78 and Clause 2400 of Specifications for Road & Bridge Works (5th Revision), Published by IRC, and also including hire charges of tools and plants complete as per the direction of Engineer-in-Charge. b) When drilling mud "Bentonite of suitable consistency" is used to prevent collapse of bore hole. (i) Depth 0.00 m to 10.00 m					
		m	48.80	m	345.62	16866.00
3	B Field Investigation: v) Collection of Undisturbed soil sample from the bore hole to be made by the concerned Division / Party at their cost. (i)0.0 m - 10.0 m	Each	32.00	Nos	274.11	8772.00
4	Carriage of all Disturbed & Undisturbed Samples from site of work to the Divisional office or elsewhere including loading and unloading as per direction of Engineer-in-Charge. Detailed Investigation.	L.S	2	1103	1906.88	3814.00
5	A. Laboratory Investigation:	1.0			1700.00	5611.00
	xvii) Laboratory Determination of Permeability as per IS 2720 (Part– XVII).					
		Each	16	Nos	822.34	13157.00
6	A. Laboratory Investigation: xxviii) Determination of Swelling Pressure of Soil as per IS 2720 (Part–VIII).					
		Each	16	Nos	822.34	13157.00
7	Preparation and submission of report in 6 (Six) copies, giving all relevant information data like site plan, Bore log and water table, test results, calculations, discussions, suggestions and recommendations in respect of suitable foundation etc. including determination of silt factor calculation of waterways and complete design of foundation including analysis of Bearing Capacities and settlements in bound and presentable form complete as per direction of Engineer-in-Charge. b) Detailed Investigation.					
		L.S	2		14898.00	29796.00
					Total Rs. =	115357.00

Sub-Divisional officer Kangsabati Canals Sub-Division No.-IV Sarenga, Bankura