

ar
d, Jalpaiguri.
te:- 22.05.2020



GOVERNMENT OF WEST BENGAL
Irrigation and Waterways Directorate
Office of the Executive Engineer
Alipurduar Irrigation Division,
College Halt, Alipurduar

e-mail: eeapdid@gmail.com // Phone No: 03564 255305 // Fax No: 03564 255305

CORRIGENDUM-1

Memo No: 429

Date: 22.05.2020

e-NIT No - WBIW/EE/APD/e-NIT-02(e)/2020-21 (SI-03)


Tender ID: - 2020_IWD_282703_3

Name of work: Protection work by HDPE bags at Khokla bosty area adjacent the Dumping Yard, Himalitoll and Gorkha Bhawan for the length of 576 meter along the right bank of river Gaburjyoti in Block - Kalchini, & P.S.- Jaigaon, Dist.- Alipurduar.

Due to typographical mistake following corrections to be made in BOQ as shown below:-

	In place of	To be read as
SI No	Item Description	Item Description
1	Supplying Nylon cage netting 1 metre x 1 metre x 0.60 metre size with knot having mesh size 17.5 cm x 17.5 cm constructed with nylon thread (210x 24) having tensile strength not less than 250 Kg. / sq. cm. including carriage, delivery and stacking at site inclusive of all taxes complete.	Labour charges for dumping and placing in position properly filled in nylon crates with filled in HDPE bags (minimum 13 nos.) with local earth/sand, sewing and tying the crate with nylon wire within a lead of 150m and all lifts in river slope or bed by cutting trenches upto 50 cms depth, if necessary, or by boat including cost of hire charges of boat, boatmen and other necessary equipments and also including cost of bags, carriage and charges of filling bags with earth/sand but excluding cost of nylon crate as per direction of the Engineer-in Charge. NB: Volume of each earth/sand filled HDPE bags should not be less than 0.0328 cum. Size of Nylon crate is 1metre X 1metre X 0.60 metres.
2	Labour charges for dumping and placing in position properly filled in nylon crates with filled in HDPE bags (minimum 13 nos.) with local earth/sand, sewing and tying the crate with nylon wire within a lead of 150m and all lifts in river slope or bed by cutting trenches upto 50 cms depth, if necessary, or by boat including cost of hire charges of boat, boatmen and other necessary equipments and also including cost of bags, carriage and charges of filling bags with earth/sand but excluding cost of nylon crate as per direction of the Engineer-in Charge. NB: Volume of each earth/sand filled HDPE bags should not be less than 0.0328 cum. Size of Nylon crate is 1metre X 1metre X 0.60 metres.	Supplying Nylon cage netting 1 metre x 1 metre x 0.60 metre size with knot having mesh size 17.5 cm x 17.5 cm constructed with nylon thread (210x 24) having tensile strength not less than 250 Kg. / sq. cm. including carriage, delivery and stacking at site inclusive of all taxes complete.

All other contents of BOQ will remain unchanged.



(PRIYAM GOSWAMI)
Executive Engineer
Alipurduar Irrigation Division,
Irrigation & Waterway Directorate

Date:- 22.05.2020

Memo:- 429/1(14)

Copy forwarded to the:-

1. Chief Engineer, North East, I & W Dte. Club Road , Jalpaiguri.
2. Superintending Engineer, North East Irrigation Circle-I, Debibari, Coochbehar
3. Superintending Engineer & P.A. to the Chief Engineer, North East, Club Road , Jalpaiguri.
4. District Magistrate, Alipurduar
- 5-7. Executive Engineer, Jalpaiguri/Siliguri/Coochbehar Irrigation Division.
8. Nodal officer of e-Tendering. Irrigation & Waterways Department Jalsampad Bhawan, 7th Floor, Salt Lake City, Kolkata-700091
- 9-11. Sub-Divisional Officer, Alipurduar Irrigation/Alipurduar Investigation/Kamakhyaguri Irrigation Sub- Division
12. Sr. Divisional Accounts Officer, Alipurduar Irrigation Division.
13. Office Notice Board.


(PRIYAM GOSWAMI)
Executive Engineer
Alipurduar Irrigation Division,
Irrigation & Waterway Directorate

Memo:- 429/1(14)

Date -22.05.2020

Copy submitted to the Honb'le Sabhadhipati Alipurduar Zilla Parisad, Alipurduar.

(PRIYAM GOSWAMI)
Executive Engineer
Alipurduar Irrigation Division
Irrigation & Waterway Directorate