

GOVERNMENT OF WEST BENGAL
IRRIGATION & WATERWAYS DIRECTORATE
OFFICE OF THE SUB-DIVISIONAL OFFICER, JAMALPUR IRRIGATION SUB-DIVISION
JAMALPUR, PURBA BARDHAMAN

NOTICE INVITING TENDER NO. : 04 of 2021-22

Serial No. : 1

Name of Work :

Flood protection & mitigation work for reducing vulnerability of people by strengthening of Ex-zamindari embankment of river Damodar in between Ch 74.60 km to Ch 76.40 km for a length of 100 m from Adibasipara to Sajmontala, G.P. - Jarogram, P.S. & Block - Jamalpur, Dist. : Purba Bardhaman.

Amount put to tender Rs. 4,69,185.00

Earnest Money Rs. 9,384.00

G.S.T. @12.00% has been considered

Completion time : 7 Days.

SCHEDULE OF WORK

Sl. No.	Description	Quantity	Unit	Rate (Rs.)	Amount (Rs.)
1	Cutting uprooting and clearing jungles including shrubs, water weeds, bushes, trees, plants, upto 30 cm. girth including removing as directed by Engineer-in-charge.	1,182.83	Sqm.	5.66	6,695.00
2	Earthwork in closing ghoges in embankments including cutting, filling, puddling with water and ramming including all leads and lifts, if necessary.	2,562.28	Cum.	122.17	3,13,034.00
3	Loading in to trucks at the lifting point, unloading at destination, stacking properly in go downs or yard etc. as directed including carriage by head load up to a lead of 50.00 m at each of the two points. Sand	208.80	Cum.	87.10	18,186.00
4	Carriage of Sand, Moorum and similar materials over pucca road.	208.80	Cum.	224.77	46,932.00
5	Labour charges for filling empty cement gunny bag / polythene bag (capacity 50 kg) with all kinds of earth (wet or dry), sand or aggregates (stone / brick) and sewing as done in case of cement bags ,(tying with a knot after filling will not be accepted) , and stacking within a lead of 30 metre as per direction of Engr-in-charge (cost is excluding the cost of any types of filling materials).	7,457	Each Bag	7.92	59,059.00
6	Dumping in position earth / sand filled gunny / poly bags (capacity 50 kg) within a lead of 30 metre inclusive of all lifts.	7,457	Each Bag	3.39	25,279.00

4,69,185.00

Rupees Four lakh Sixty Nine Thousand One Hundred Eighty Five Only

Sub-Divisional Officer
Jamalpur Irrigation Sub-Division

I do hereby agree to execute the work @ % ()
the attached schedule.

percent) below / above / at par than

Signature of Agency

GOVERNMENT OF WEST BENGAL
IRRIGATION & WATERWAYS DIRECTORATE
OFFICE OF THE SUB-DIVISIONAL OFFICER, JAMALPUR IRRIGATION SUB-DIVISION
SINGUR, HOOGHLY, PHONE NO. : 033-26300170
NOTICE INVITING TENDER NO. : 04 of 2021-22

Serial No. : 2

Name of Work :

Flood protection & mitigation work for reducing vulnerability of people by strengthening of Damodar Left embankment of river Damodar in between Ch. 68.20 km to Ch. 73.00 km for a length of 130 m from Jot Kubi to Baratikira , G.P. - Jamalpur-II & Jarogram, P.S. & Block - Jamalpur , Dist. : Purba Bardhaman.

Amount put to tender Rs. 4,72,706.00

Earnest Money Rs. 9,454.00

G.S.T. @12.00% has been considered

Completion time : 7 Days.

SCHEDULE OF WORK

Sl. No.	Description	Quantity	Unit	Rate (Rs.)	Amount (Rs.)
1	Cutting uprooting and clearing jungles including shrubs, water weeds, bushes, trees, plants, upto 30 cm. girth including removing as directed by Engineer-in-charge.	820.12	Sqm.	5.66	4,642.00
2	Earthwork in closing ghoges in embankments including cutting, filling, puddling with water and ramming including all leads and lifts, if necessary.	2,705.85	Cum.	122.17	3,30,574.00
3	Loading in to trucks at the lifting point, unloading at destination, stacking properly in go downs or yard etc. as directed including carriage by head load up to a lead of 50.00 m at each of the two points. Sand	192.08	Cum.	87.10	16,730.00
4	Carriage of Sand, Moorum and similar materials over pucca road.	192.08	Cum.	224.77	43,174.00
5	Labour charges for filling empty cement gunny bag / polythene bag (capacity 50 kg) with all kinds of earth (wet or dry), sand or aggregates (stone / brick) and sewing as done in case of cement bags, (tying with a knot after filling will not be accepted), and stacking within a lead of 30 metre as per direction of Engr-in-charge (cost is excluding the cost of any types of filling materials).	6,860	Each Bag	7.92	54,331.00
6	Dumping in position earth / sand filled gunny / poly bags (capacity 50 kg) within a lead of 30 metre inclusive of all lifts.	6,860	Each Bag	3.39	23,255.00

4,72,706.00

Rupees Four lakh Seventy Two Thousand Seven Hundred Six Only

Sub-Divisional Officer
Jamalpur Irrigation Sub-Division

I do hereby agree to execute the work @ _____ % (

percent) below / above / at par than

the attached schedule.

Signature of Agency

GOVERNMENT OF WEST BENGAL
IRRIGATION & WATERWAYS DIRECTORATE
OFFICE OF THE SUB-DIVISIONAL OFFICER, JAMALPUR IRRIGATION SUB-DIVISION
SINGUR, HOOGHLY, PHONE NO. : 033-26300170
NOTICE INVITING TENDER NO. : 04 of 2021-22

Serial No. : 3

Name of Work :

Flood protection & mitigation work for reducing vulnerability of people by strengthening of Left bank of river Damodar in between Ch 68.30 km to Ch 68.50 km for a length of 160 m at Haragobindapur , G.P. - Chakdighi, P.S. & Block - Jamalpur, Dist. : Purba Bardhaman.

Amount put to tender Rs. 4,72,561.00

Earnest Money Rs. 9,451.00

G.S.T. @12.00% has been considered

Completion time : 7 Days.

SCHEDULE OF WORK

Sl. No.	Description	Quantity	Unit	Rate (Rs.)	Amount (Rs.)
1	Cutting uprooting and clearing jungles including shrubs, water weeds, bushes, trees, plants, upto 30 cm. girth including removing as directed by Engineer-in-charge.	740.92	Sq.m.	5.66	4,194.00
2	Earthwork in closing ghoges in embankments including cutting, filling, puddling with water and ramming including all leads and lifts, if necessary.	1,577.73	Cum.	122.17	1,92,751.00
3	Loading in to trucks at the lifting point, unloading at destination, stacking properly in go downs or yard etc. as directed including carriage by head load up to a lead of 50.00 m at each of the two points. Sand	193.48	Cum.	87.10	16,852.00
4	Carriage of Sand, Moorum and similar materials over pucca road.	193.48	Cum.	224.77	43,488.00
5	Labour charges for filling empty cement gunny bag / polythene bag (capacity 50 kg) with all kinds of earth (wet or dry), sand or agreeegates (stone / brick) and sewing as done in case of cement bags, (tying with a knot after filling will not be accepted), and stacking within a lead of 30 metre as per direction of Engr-in-charge (cost is excluding the cost of any types of filling materials).	6,910	Each Bag	7.92	54,727.00
6	Dumping in position earth / sand filled gunny / poly bags (capacity 50 kg) within a lead of 30 metre inclusive of all lifts.	6,910	Each Bag	3.39	23,425.00
7	Labour charges for dumping and placing in position properly filled in Nylon crates with filled in gunny / poly cement bags (minimum 25 nos. having capacity 50 kg) with local earth or sand, sewing and tying the crate with nylon wire within a lead of 150 m. and all lifts in river slope or bed by cutting trenches upto 50 cms depth, if necessary, or by boat including cost of hire charges of boat, boatmen and other necessary equipments and also including cost of bags, carriage and charge of filling bags with earth / sand but excluding cost of nylon crate as per direction of the Engineer – in – Charge. NB:- Volume of each earth/sand filled bags should not be less than 0.028 m3. Size of Nylon crate is 1metre X 1metre X 1metre. (a) Where boats are not necessary	290	Each	472.84	1,37,124.00

4,72,561.00

Rupees Four lakh Seventy Two Thousand Five Hundred Sixty One Only

Sub-Divisional Officer
Jamalpur Irrigation Sub-Division

I do hereby agree to execute the work @ % (

percent) below / above / at par than the attached schedule.

Signature of Agency

GOVERNMENT OF WEST BENGAL
IRRIGATION & WATERWAYS DIRECTORATE
OFFICE OF THE SUB-DIVISIONAL OFFICER, JAMALPUR IRRIGATION SUB-DIVISION
SINGUR, HOOGHLY, PHONE NO. : 033-26300170
NOTICE INVITING TENDER NO. : 04 of 2021-22

Serial No. : 4

Name of Work :

Flood protection & mitigation work for reducing vulnerability of people by strengthening of Damodar Left embankment of river Damodar in between Ch 62.40 km to Ch 62.70 km for a length of 60 m at Dobadhi, G.P. - Jamalpur-I, P.S. & Block-Jamalpur, Dist. : Purba Bardhaman.

Amount put to tender Rs. 2,19,710.00

Earnest Money Rs. 4,394.00

G.S.T. @12.00% has been considered

Completion time : 7 Days.

SCHEDULE OF WORK

Sl. No.	Description	Quantity	Unit	Rate (Rs.)	Amount (Rs.)
1	Cutting uprooting and clearing jungles including shrubs, water weeds, bushes, trees, plants, upto 30 cm. girth including	1,003.35	Sqm.	5.66	5,679.00
2	Earthwork in closing ghoges in embankments including cutting, filling, puddling with water and ramming including all leads and lifts, if necessary.	1,348.24	Cum.	122.17	1,64,714.00
3	Loading in to trucks at the lifting point, unloading at destination, stacking properly in go downs or yard etc. as directed including carriage by head load up to a lead of 50.00 m at each of the two points. Sand	78.12	Cum.	87.10	6,804.00
4	Carriage of Sand, Moorum and similar materials over pucca road.	78.12	Cum.	140.27	10,958.00
5	Labour charges for filling empty cement gunny bag / polythene bag (capacity 50 kg) with all kinds of earth (wet or dry), sand or agreeegates (stone / brick) and sewing as done in case of cement bags, (tying with a knot after filling will not be accepted), and stacking within a lead of 30 metre as per direction of Engr-in-charge (cost is excluding the cost of any types of filling materials).	2,790	Each Bag	7.92	22,097.00
6	Dumping in position earth / sand filled gunny / poly bags (capacity 50 kg) within a lead of 30 metre inclusive of all lifts.	2,790	Each Bag	3.39	9,458.00

2,19,710.00

Rupees Two lakh Nineteen Thousand Seven Hundred Ten Only

Sub-Divisional Officer
Jamalpur Irrigation Sub-Division

I do hereby agree to execute the work @ % (

percent) below / above / at par than

the attached schedule.

Signature of Agency

GOVERNMENT OF WEST BENGAL
IRRIGATION & WATERWAYS DIRECTORATE
OFFICE OF THE SUB-DIVISIONAL OFFICER, JAMALPUR IRRIGATION SUB-DIVISION
SINGUR, HOOGHLY, PHONE NO. : 033-26300170
NOTICE INVITING TENDER NO. : 04 of 2021-22

Serial No. : 5

Name of Work :

Improvement of inspection path to the Ex-zamindari embankment of river Damodar for a length of 300 m at Sajmontala in between Ch 75.60 km to Ch 75.90 km , G.P. : Jarogram, P.S. & Block - Jamalpur, Dist. : Purba Bardhaman.

Amount put to tender Rs. 3,30,311.00

Earnest Money Rs. 6,606.00

G.S.T. @12.00% has been considered

Completion time : 7 Days.

SCHEDULE OF WORK

Sl. No.	Description	Quantity	Unit	Rate (Rs.)	Amount (Rs.)
1	Water Bound Macadam Sub Base by consolidating Jhama metal / Laterite chelly or stone metal / shingles of specific size in hard crust to requisite thickness (measured after compaction) in layers including screening of metals etc. as necessary, hand packing, sweeping, watering and rolling in stages with power roller to proper line, grade and camber, lighting, guarding & barricading and making necessary earthen bundh of one metre width on each side where necessary to protect edges and preparing the bed by necessary cutting or filling and rolling all complete including the cost of all materials and hire and labour charges of all men and machineries and compacting to the required density, as per Clause 404 of Specifications for Road & Bridge Works of MoRT&H (5th Revision).	114.30	Cum.	2,152.66	2,46,049.00
2	Supplying, spreading and consolidating Moorum to a depth of 75 mm at desired density and C.B.R. as per specification with power roller to proper gradient and camber including watering as necessary, and lighting, guarding, barricading and making adequate earthen bundh where necessary to protect the edges and curing with water for 2 to 3 days, mending cracks by rolling where necessary including all incidental charges of roller, cost of fuel & lubricants etc. complete as per specification.	45.00	Cum.	1,872.48	84,262.00

3,30,311.00

Rupees Three lakh Thirty Thousand Three Hundred Eleven Only

Sub-Divisional Officer
Jamalpur Irrigation Sub-Division

I do hereby agree to execute the work @ % (

percent) below / above / at par than

the attached schedule.

Signature of Agency

GOVERNMENT OF WEST BENGAL
IRRIGATION & WATERWAYS DIRECTORATE
OFFICE OF THE SUB-DIVISIONAL OFFICER, JAMALPUR IRRIGATION SUB-DIVISION
SINGUR, HOOGHLY, PHONE NO. : 033-26300170
NOTICE INVITING TENDER NO. : 04 of 2021-22

Serial No. : 6

Name of Work :

Improvement of inspection path to the Damodar Left embankment of river Damodar for a length of 500 m at in between Ch 65.90 km to Ch 71.10 km from Jorbundh to Sonargaria, G.P. : Jamalpur-II & Jarogram, P.S. & Block - Jamalpur , Dist. : Purba Bardhaman.

Amount put to tender Rs. 4,62,515.00

Earnest Money Rs. 9,250.00

G.S.T. @12.00% has been considered

Completion time : 7 Days.

SCHEDULE OF WORK

Sl. No.	Description	Quantity	Unit	Rate (Rs.)	Amount (Rs.)
1	Water Bound Macadam Sub Base by consolidating Jhama metal / Laterite chelly or stone metal / shingles of specific size in hard crust to requisite thickness (measured after compaction) in layers including screening of metals etc. as necessary, hand packing, sweeping, watering and rolling in stages with power roller to proper line, grade and camber, lighting, guarding & barricading and making necessary earthen bundh of one metre width on each side where necessary to protect edges and preparing the bed by necessary cutting or filling and rolling all complete including the cost of all materials and hire and labour charges of all men and machineries and compacting to the required density, as per Clause 404 of Specifications for Road & Bridge Works of MoRT&H (5th Revision).	117.00	Cum.	2,152.66	2,51,861.00
2	Supplying, spreading and consolidating Moorum to a depth of 75 mm at desired density and C.B.R. as per specification with power roller to proper gradient and camber including watering as necessary, and lighting, guarding, barricading and making adequate earthen bundh where necessary to protect the edges and curing with water for 2 to 3 days, mending cracks by rolling where necessary including all incidental charges of roller, cost of fuel & lubricants etc. complete as per specification.	112.50	Cum.	1,872.48	2,10,654.00

4,62,515.00

Rupees Four lakh Sixty Two Thousand Five Hundred Fifteen Only

Sub-Divisional Officer
Jamalpur Irrigation Sub-Division

I do hereby agree to execute the work @ % (

percent) below / above / at par than the attached schedule.

Signature of Agency