



GOVERNMENT OF WEST BENGAL
Irrigation & Waterways Directorate
Office of The Assistant Engineer-III
Purulia Irrigation Division
Bhatbandh, Purulia

Notice Inviting Quotation.

NIQ NO-01 of AE-III/PID/2022-23

Memo. No.- 37

Dated: - 16.03.2023

Sealed Quotations are hereby invited on prescribed format by the undersigned to ascertain unit rate of following items to be Supplied and installed (with ancillary work in complete at site) in several Dams under the Circle of the OSD(SE), 1&W Dte., Purulia.

SI No	Description of Item	Qty	Unit	Rate in (Rs.)		Amount in (Rs.)	
				figure	word	figure	word
1	Supplying and installation charges of Casagrande porous tube piezomete, as per IS:7355 (Part-I) with ancillary works at site complete. Specification: Casagrande tip-38mm OD, 25mm ID, 60cm long semi-rigid plastic stand pipe-27mm OD, 17mm ID, 3m long.	01	Each				
2	Supplying and installation charges of V-notch (capacity: 10-30 Lit/sec.) with ancillary works at site complete.	01	Each				
3	Supplying and installation charges of Base Plate settlement instrument (Mechanical type) made of steel, 0.6mX0.6mX 5mm thick, with male threaded coupling welded at center at site complete.	01	Each				
4	Supplying and installation charges of automatic Rain Gauge instrument (measuring and recording type) with ancillary works at site complete. Specifications: - I. Sensor mounting mast should be made of mild steel having length 5.0 M. II. Sensor should be of tipping bucket type having rim diameter 203 mm and collecting area 325mm ² III. Rain gauge shell, bucket and monitoring assembly should be made of FRP, stainless steel and powder coated brass respectively (SS 316 body).	01	Each				

5	Supplying and installation charges of Electronic water level indicator (with buzzer and indicator) at site complete I. Tape resolution-1m II. Probe material-stainless steel III. Depth-30.00 M	01	Each				
---	----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	----	------	--	--	--	--

The quotationers should quote their rate [including supply, installation, commissioning, calibration, and all ancillary work (complete in all respect a site as per proforma given by the Office of the udder signed Quoted rate should be exclusive of GST, CESS (Will be applicable as per prevailing Govt. rules) and inclusive of all other charges (no part rate will be accepted) **Last date of receiving quotation paper is 30.03.2023 up to 11.00 hrs. and will be opened on the same day at 11.30 hrs. at Office of AE-III/PID** in presence of the participating quotationars (if present), The quotations will be accepted by the Executive Engineer, Purulia Irrigation Division however the rate will be approved by the OSD (SE), I&W Dte. Purulia. The OSD (S.E), I&W Dte. Purulia will reserve the right to cancel each or the entire items without assigning any reason. Conditional quotations shall not be accepted.

NO EMD IS REQUIRED AS THIS NIQ IS ONLY TO ASCERTAIN UNIT RATE (FOR BUDGETARY QUOTE ONLY)

Sd/-
 Assistant Engineer-III
 Purulia Irrigation Division

Memo. No:37/(3)

Dated: -16.03.2023

Copy forwarded to the: -

1. The OSD (S.E), I&W Dte. Purulia
2. The Executive Engineer, Purulia Irrigation Division, Purulia.
3. Notice board (Office of The AE-III/PID).

Sd/-
 Assistant Engineer-III
 Purulia Irrigation Division